



November 30, 2020

Mr. Andrew Wheeler
Administrator
US EPA

Dear Mr. Wheeler:

On August 28, 2020, the EPA finalized revisions to the CCR Rule that would require unlined CCR surface impoundments to cease receipt of waste as soon as technically feasible, but no later than April 11, 2021, unless the owner/operator can demonstrate that CCR and/or non-CCR wastestreams must continue to be managed in that CCR surface impoundment based on a lack of alternative capacity.

This Alternative Capacity Infeasibility Demonstration revises the original version submitted on November 6, 2020. This version was prepared to document and explain in greater detail why development of alternative capacity by April 11, 2021 is infeasible for the Evaporation Pond, an unlined CCR surface impoundment, at the CPS Energy Calaveras Power Station located in Bexar County, Texas.


Please call me at (210) 353-3625 with any questions.

Sincerely,

A handwritten signature in black ink, appearing to read "Michael M. Malone".

Michael M. Malone, P.E., LEED Green Associate, R.E.M.
CPS Energy Senior Manager
Environmental Management

cc: Kirsten Hillyer
Frank Behan
Richard Huggins



Alternative Capacity Infeasibility Demonstration

Evaporation Pond
CPS Energy Calaveras Power Station
Bexar County, Texas

30 November 2020

Project No.: 0503422

Signature Page


30 November 2020

Alternative Capacity Infeasibility Demonstration


Evaporation Pond
CPS Energy Calaveras Power Station
Bexar County, Texas



Charles Johnson, P.E.
Senior Consultant



Walter Zverina
Project Manager



Jeffery L. Bauguss, P.E.
Partner

Environmental Resources Management Southwest, Inc.
Capitol Tower
206 East 9th Street, Suite 1700
Austin, Texas 78701

© Copyright 2020 by ERM Worldwide Group Ltd and/or its affiliates ("ERM").
All rights reserved. No part of this work may be reproduced or transmitted in any form,
or by any means, without the prior written permission of ERM.

CONTENTS

1.	INTRODUCTION	1
1.1	Demonstration Purpose and Objectives	1
1.2	Organization of the Demonstration	1
2.	FACILITY DESCRIPTION AND UNIT DESCRIPTION	2
3.	WORK PLAN	3
3.1	Alternative Capacity On-Site.....	3
3.2	Alternative Capacity Off-site	4
3.3	Role of EP in Continued Plant Operations	6
3.4	Narrative Discussing the Approach Selected to Obtain Alternative Capacity for CCR and/or Non-CCR Wastestreams	6
3.4.1	Retrofitting an Existing Surface Impoundment.....	7
3.4.2	Constructing a New Surface Impoundment	8
3.4.3	Summary of Alternatives Evaluated and Selected Alternative	12
3.5	Detailed Schedule of the Fastest Feasible Time to Complete Measures Necessary for Alternative Capacity.....	12
3.6	Narrative Discussion of the Schedule and Visual Timeline Representation.....	12
3.7	Narrative Discussion of the Progress Made to Obtain Alternative Capacity for the CCR and/or Non-CCR Wastestreams	14
4.	COMPLIANCE WITH SUBPART D	16

List of Figures

Figure 2.1	Facility Location Map
Figure 2.2	CCR Unit Location Map
Figure 3.1	Surface Impoundment Location Map
Figure 3.2	New Evaporation Pond Project Schedule

List of Exhibits

Exhibit 3.1	Off-Site Treatment Facilities
Exhibit 3.2	Calaveras Power Station Surface Impoundments
Exhibit 3.3	Proposed Process Flow Diagram for Consolidating WWTP Flows
Exhibit 3.4	Proposed Site Plan

List of Appendices

- Appendix A Owner Certification of Compliance
- Appendix B Groundwater Monitoring Well Locations Map
- Appendix C Well Construction Diagrams and Drilling Logs
- Appendix D Groundwater Flow Direction Maps
- Appendix E Constituent Concentrations Summary Tables
- Appendix F Site Hydrogeology and Cross-Sections
- Appendix G Structural Stability and Safety Factor Assessments

1. INTRODUCTION

Title 40, Code of Federal Regulations, Part 257 (40 CFR §257) Subpart D (a.k.a. the Coal Combustion Residual (CCR) Rule) was published in the Federal Register in April 2015 and became effective in October 2015. Under the CCR Rule, CPS Energy operates active surface impoundments and a landfill primarily for temporary storage and historically for disposal of fly ash and bottom ash.

On August 28, 2020, the Environmental Protection Agency (EPA) finalized revisions to the CCR Rule that would require unlined CCR surface impoundments to cease receipt of waste as soon as technically feasible but no later than April 11, 2021, unless the owner/operator can demonstrate that CCR and/or non-CCR wastestreams must continue to be managed in that CCR surface impoundment based on a lack of alternative capacity. On behalf of CPS Energy, this Alternative Capacity Infeasibility Demonstration (Demonstration) was prepared to document, under the finalized 40 CFR §257.103(f), that development of alternative capacity is infeasible for the Evaporation Pond (EP), an unlined CCR surface impoundment, at the CPS Energy Calaveras Power Station located in Bexar County, Texas.

1.1 Demonstration Purpose and Objectives

This Demonstration was prepared in accordance with requirements in finalized 40 CFR §257.103(f) to demonstrate that CCR and/or non-CCR flows must continue to be managed in the EP because it is infeasible to complete measures necessary to provide alternative disposal capacity on-site or off-site by April 11, 2021. CPS Energy therefore requests to keep operating the EP until May 26, 2022, which is the anticipated fastest technically feasible time in which development of alternative capacity can be completed.

1.2 Organization of the Demonstration

This Demonstration is organized into the following sections:

- Facility Description and Unit Description
- Work Plan - 40 CFR §257.103(f)(1)(iv)(A) and 40 CFR §257.103(f)(1)(i)-(ii)
- Compliance with Subpart D - 40 CFR §257.103(f)(1)(iv)(B) and 40 CFR §257.103(f)(1)(iii)

2. FACILITY DESCRIPTION AND UNIT DESCRIPTION

CPS Energy owns and operates the Calaveras Power Station located at 12940 U.S. Highway 181 South in San Antonio, Texas. A Facility Location Map is provided as Figure 2.1. The Calaveras Power Station consists of three power plants of which two plants (J.T. Deely and J.K. Spruce) are subject to regulation under the CCR Rule. Specifically, CPS Energy operates three CCR units at the Calaveras Power Station: EP, Fly Ash Landfill, and the Sludge Recycle Holding Pond. Although the J.T. Deely Power Plant ceased operation at the end of December 2018, and sluiced bottom ash is no longer being received at the Bottom Ash Ponds (BAPs), the BAPs will continue to be monitored until the units have undergone closure. A CCR Unit Location Map is provided as Figure 2.2.

Groundwater in the vicinity of all the CCR units at the Calaveras Power Station has been monitored since December 2016. No statistically significant increase (SSI) of Appendix III constituents above background levels has been determined for any of the CCR units, and therefore, CPS Energy is currently in, and will continue with, a detection monitoring program.

The existing EP was originally constructed as a fly ash landfill in 1990, and then converted to a fly ash impoundment in 1996. The function of the fly ash impoundment changed from storing fly ash to dewatering various liquid wastestreams by evaporation after 1996. The existing EP contains a liner system, but the liner design does not meet the specific liner requirements of the CCR Rule (40 CFR §257.72), and is therefore considered unlined. There are no inlet or outlet structures to the existing EP. A four-inch polyethylene pipe is present in the eastern embankment and supplies water for equipment washout purposes within the EP area.

The primary operational functions of the existing EP include receiving non-CCR flows (industrial wastestreams) that are trucked to the EP, and allowing the evaporation of these industrial wastestreams. Currently, the existing EP does not receive any CCR flows, but in addition to the non-CCR industrial wastestreams from the J.K. Spruce Plant, the EP also receives non-CCR industrial wastestreams from other CPS Energy power generation facilities. Cessation of non-CCR flows to the existing EP requires alternative capacity that will, at a minimum, fulfill these primary operational functions, or the power plants designs must be modified to eliminate these flows.

3. WORK PLAN

In accordance with 40 CFR §257.103(f)(1)(iv)(A) and 40 CFR §257.103(f)(1)(i)-(ii), this section provides:

1. A narrative that no alternative disposal capacity is available on-site or off-site,
2. A narrative that it is technically infeasible to obtain alternative capacity prior to April 11, 2021,
3. A narrative regarding the selected option and justification for the selected alternative capacity,
4. A detailed schedule and narrative discussion of the fastest technically feasible time to complete the development of the selected alternative capacity, and
5. A narrative discussion of the progress made to date to obtain alternative capacity.

3.1 Alternative Capacity On-Site

The cessation of non-CCR flows to the EP requires alternative capacity that, at a minimum, will replace the primary operational functions, or the power plants designs must be modified to eliminate these flows. Two alternatives were evaluated to obtain alternative capacity on-site including:

1. Retrofitting an existing surface impoundment
2. Constructing a new surface impoundment

A summary of the evaluated alternatives is provided below. Importantly, and as detailed in the description of each, both alternatives require several years to complete and do not provide for alternative capacity at this time, but CPS Energy is actively working towards construction of its selected alternative (Alternative 2). Details of each evaluated alternative are provided in Section 3.4 of this Demonstration.

- Alternative 1 – Retrofitting an existing surface impoundment to receive the EP flow is a more complex alternative and was not selected for the following reasons:
 - The duration for the removal of all CCR in the existing EP and the design, procurement, and installation of a new liner system is longer than the selected alternative (Alternative 2). In addition, the footprint of the existing EP is not large enough to handle both the planned sanitary and industrial wastestreams.
 - Excluding the existing EP, there are nine other active surface impoundments (both CCR and non-CCR surface impoundments) at the Calaveras Power Station. Six of these nine surface impoundments are needed for stormwater management and release to Calaveras Lake as permitted discharges. These six surface impoundments also do not have sufficient capacity to receive industrial wastestreams in addition to their designed stormwater capacity. Since these six surface impoundments are unavailable for added capacity and since the industrial wastestreams managed in the EP would not meet the low discharge permit limits for metals (specifically iron and copper), these surface impoundments are not available for retrofit as alternative capacity. In addition, a major amendment for a discharge permit renewal would take between one and two years for approval.
 - As for the three active surface impoundments not associated with stormwater management, the footprint of two are not large enough to handle the industrial wastestreams managed in the EP and one (SRH Pond) is being closed as an unlined CCR surface impoundment. Therefore, these three surface impoundments are also not available for retrofit as alternative capacity.
 - The two inactive surface impoundments, the North and South Bottom Ash Ponds, have ceased receiving flow and will be clean closed. The schedule for release of these surface impoundments for re-development following closure is unknown and these surface impoundments will not be available for retrofit until all closure activities are complete.

- Alternative 2 – The selected alternative, designing and constructing a new lined surface impoundment, is the least complex alternative and it can be implemented in the shortest duration. An overall duration of 22 months is expected for this alternative to allow the cessation of non-CCR flow to the EP by May 26, 2022. Constructing a new lined surface impoundment also retains the primary operational functionality of the existing EP and requires minimal modifications to the existing power plants.

3.2 Alternative Capacity Off-site

The existing EP currently manages a variety of wastewaters generated at the Calaveras Power Station. The large majority of the wastes are metal cleaning wastes generated during discrete maintenance events. This section documents the infeasibility of obtaining alternate capacity off-site for the large majority of the wastes managed at the EP.

Obtaining off-site management and disposal capacity as an alternate to manage flows to the EP includes transportation of wastewaters currently managed by the EP for disposal or treatment at an off-site facility. The only off-site wastewater treatment facility in the vicinity (approximately 20 miles away) of the Calaveras Power Station is the San Antonio Water Service (SAWS) Steven M. Clouse Water Recycling Center (Clouse WRC). No industrial wastewater treatment facilities exist in San Antonio and the surrounding area capable of treating the wastewaters currently managed by the EP (see reasons listed below). Other wastewater treatment facilities in San Antonio and the surrounding area are municipal systems owned by SAWS, the San Antonio River Authority, surrounding municipalities, or private companies and these facilities are subject to the same limitations as the SAWS Clouse WRC considered in this Demonstration. A list of the facilities considered was obtained from EPA's Facility Registry Service and is provided in Exhibit 3.1.

Exhibit 3.1 – Off-Site Treatment Facilities

Facility Name	Street	City	EPA FRS ID
BFI TESSMAN ROAD LANDFILL	7000 I-10 EAST	SAN ANTONIO	110060901653
BFI WASTE TESSMAN ROAD LANDFILL	7790 TESSMAN ROAD	SAN ANTONIO	110002371781
BRIDGEWOOD WWTP	SW CORNER DOMINION SUBDIVISION ADJACENT LEON CRK	SAN ANTONIO	110014436627
CIBOLO CREEK MUNICIPAL AUTHORITY WWTP	12423 AUTHORITY LANE	SCHERTZ	110000504990
CITY OF CASTROVILLE WWTF	818 ALSACE AVE	CASTROVILLE	110027991957
CITY OF HONDO WASTE WATER PLANT	1400 FEET EAST OF THE INTERSECTION OF FM 462 AND 3	HONDO	110070356320
CITY OF LA COSTE WWTP	11331 CR 584	LA COSTE	110009773959
CITY OF LA VERNIA WWTP	2000' E. FMR 775, APPROX 400' E SE INTEX RV ST AND	LA VERNIA	110009779784
CITY OF LYTLE WWTP	2300F SE FMR 3175 IH-35	LYTLE	110006687228
CITY OF NIXON	HIGHWAY 80 NORTH & US HWY 87	NIXON	110009778213
CITY OF SAN ANTONIO	SALADO CREEK WWTP	SAN ANTONIO	110014389704
CITY OF SCHERTZ WWFT	6700FT SW INTERSECTION OF	BEXAR COUNTY	110024412410
CITY OF SEGUIN GERONIMO CREEK WWTP	450 SEITZ RD	SEGUIN	110034285299
CITY OF SMILEY WWTP	APPROX 4200' NW OF INTERX FMR 108	SMILEY	110009746490
CITY OF STOCKDALE WWTP	OLD FLORESVILLE ROAD, CR #401	STOCKDALE	110009746301
COVEL GARDENS LANDFILL AND RECYCLING	8611 COVEL RD	SAN ANTONIO	110070377738
DISPOSAL PROPERTIES	4303 PROFIT DRIVE	SAN ANTONIO	110000464818
DOS RIOS WATER RECYCLING CENTER	3495 VALLEY RD	SAN ANTONIO	110000501840
DOS RIOS WATER RECYCLING CENTER	3495 VALLEY RD	SAN ANTONIO	110014434727
FIRST RESPONDERS ACADEMY WWTP	15775 IH 35 S	ATASCOSA	110063878184
GERONIMO CREEK WWTP	450 SEITZ RD	SEGUIN	110000501430
GONZALES WARM SPRINGS WWTF	1000' S OF THE INTX OF FM 1586 AND FM 2019	GONZALES COUNTY	110009780317
HIGHWAY 181 SOUTH WWTP	14542 CASSIANO RD	SAN ANTONIO	110020063474
HONDO WWTP	1400' E OF INTERX OF FM 462	HONDO	110039914554
LEON CREEK WATER RECYCLING CENTER	1104 MAJERMANN RD	SAN ANTONIO	110031272655
LIQUID ENVIRONMENTAL SOLUTIONS OF TEXAS	10360 W US HIGHWAY 90	SAN ANTONIO	110038485975
MARION WWTP	1400' W OF FM 465 & 1800' S OF	MARION	110009745927
MARTINEZ II CREEK WWTF	1280 FM 1516 S	SAN ANTONIO	110034410812
MARTINEZ III WWTF	.35MI S LOOP 1604, IH-10 AND LP 1604	SAN ANTONIO	110010921413
MEDINA COUNTY WCID 2 WWTF	414 CR 512	MEDINA COUNTY	110009777544
MEDIO CREEK WATER RECYC. CTR.	2231 HUNT LANE	SAN ANTONIO	110064605146
MITCHELL LAKE WWTF	10762 PLEASANTON RD	SAN ANTONIO	110006823376
NELSON GARDENS	8339 COVEL RD	SAN ANTONIO	110033180607
ODO J RIEDL	12423 AUTHORITY LANE	SCHERTZ	110070365759
PAPER RETRIEVER OF TEXAS	7510 GRISSOM RD	SAN ANTONIO	110070673293
POST OAK MUNICIPAL SOLID WASTE LANDFILL	7787 FM RD 1150	SEGUIN	110070708905
POTRANCO RANCH SUBDIVISON WWTP	APPROX 3.54 MI W OF ST HWY 211	MEDINA COUNTY	110063881009
QUAIL RUN WWTP	500' SSE OF PINE VALLEY DR	WILSON COUNTY	110024412474
SALADO CREEK WWTP	13496 BLUE WING ROAD	SAN ANTONIO	110039694195
SALATRILLO CREEK WWTF	9638 SCHAEFER RD	CONVERSE	110070356078
SALATRILLO CREEK WWTP	9638 SCHAEFER ROAD	CONVERSE	110001123640
SAN ANTONIO WATER SYSTEM	LESLIE ROAD	SAN ANTONIO	110002151536
SANTA CLARA CREEK	3930 LINNE RD	SEGUIN	110064854867
SAWS MEDIO CREEK WATER RECYCLING CENTER	2231 HUNT LN	SAN ANTONIO	110070365451
SOMERSET WWTP	4300F SE CITY HALL, 3500F S	SOMERSET	110006683589
SOUTH CENTRAL WATER CO WWTF	500FT NE N LAKE HOUSTON PKWY	HOUSTON	110022417133
SOUTH REGIONAL WATER RECLAMATION PLANT	7424 TRAINER HALE RD	CITY OF SCHERTZ	110064779306
STANDARD INDUSTRIES	8189 NELSON RD	SAN ANTONIO	110020479828
UPPER MARTINEZ CREEK WWTF	ON 8203 BINZ-EMGELMAN SAN ANTONIO TX 78219	SAN ANTONIO	110070360659
WALNUT BRANCH WWTP	101 EAST KLEIN	SEGUIN	110000501449
WALNUT BRANCH WWTP	EAST KLEIN ST & S. AUSTIN ST	SEGUIN	110039946994
WOMAN HOLLERING TREATMENT PLANT	8705 GREAVES LN	SCHERTZ	110064781179

Transportation and disposal of wastewater off-site as an alternative is infeasible for the following reasons:

- Management of EP wastewaters off-site are subject to EPA Categorical Industrial User pretreatment standards [40 CFR 423.17] and San Antonio industrial user local limits prior to being transported off-site and introduced to the SAWS publicly owned treatment works (POTW). The large majority of the wastewaters managed by the EP are metal cleaning wastes; estimated to be approximately 800,000 gallons annually and typically generated during discrete maintenance events over a relatively short period of time. Available analytical data indicates concentrations of copper in the wastewater

generated during these maintenance events are above the EPA Categorical standard and local limit. As a result, these wastewaters require pretreatment to remove dissolved metals before they can be treated at the off-site POTW. This pretreatment of metal cleaning wastewaters requires construction of an on-site wastewater treatment facility (WWTF). The requirement to pretreat EP wastewaters removes any benefit of management off-site.

- Management of wastewater off-site would also require transportation of wastewater by tanker truck. The resulting truck traffic, especially during discrete metal cleaning maintenance events, would substantially increase 1) the risk of a traffic accident, 2) the risk of a spill or release to the environment, and 3) fuel consumption and carbon emissions.

3.3 Role of EP in Continued Plant Operations

The J.K. Spruce Plant has a generation capacity of 1,410 MW and comprises approximately 18.3% of the CPS Energy's generation portfolio. The J.K. Spruce Plant is an essential part of the baseload capacity within the CPS Energy fleet, particularly during peak demand periods. During the summer of 2019, the Electric Reliability Council of Texas (ERCOT) reported that they were forced to rely on demand response reserves to maintain reliability with the grid. Although reserve margins are expected to grow in coming years, the Capacity Demand and Reserves (CDR) report indicates a continuation limited reserve margin in the near term.

The existing EP receives boiler chemical cleanouts and other chemical cleaning wastes generated during maintenance events. CPS Energy must manage the wastestreams generated during these needed maintenance events for the continued safe operation of the J.K. Spruce Plant and other CPS Energy power generation facilities.

Maintenance needed for continued operation of the J.K. Spruce Plant and other CPS Energy power generation facilities is dependent on the continued operation of the existing EP until alternative capacity is available. If non-CCR flows to the EP cease on or prior to April 11, 2021 without alternative capacity available, the J.K. Spruce Plant and other CPS Energy power generation facilities will not be able to continue operation.

3.4 Narrative Discussing the Approach Selected to Obtain Alternative Capacity for CCR and/or Non-CCR Wastestreams

The existing EP is located generally northeast of the J.K. Spruce Plant and is approximately 5.1 acres in size. The existing EP contains a liner system, but the liner design does not meet the specific liner requirements of the CCR Rule, and is therefore considered unlined. The existing EP was originally constructed as a fly ash landfill in 1990, and then converted to a fly ash impoundment in 1996. The function of the fly ash impoundment changed from storing fly ash to dewatering various liquid wastes by evaporation after 1996.

Currently, the existing EP does not receive any CCR flows, but in addition to the non-CCR industrial wastestreams from the J.K. Spruce Plant, the EP also receives non-CCR industrial wastestreams from other CPS Energy power generation facilities. During typical plant operations, the non-CCR flow volume of nonhazardous liquids to the existing EP ranges between 1,000,000 and 2,000,000 gallons per year. The existing EP does not have an inlet pipe or discharge pipe and only receives various non-CCR flows discharged via tanker trucks, which include:

- Boiler cleaning liquid waste
- Ion exchange wastewater
- Steam turbine cleaning liquid waste

- Plasma cutter liquid waste
- Acid/base vessel cleaning liquid waste
- Spill cleanup liquid waste
- Laboratory analyte solution liquid waste
- Air preheater basket cleaning liquid waste
- Heat exchanger condenser cleaning liquid waste
- Circulating water from service activities on plant equipment

The cessation of the non-CCR flows (industrial wastestreams) to the existing EP requires alternative capacity that, at a minimum, will replace the primary operational functions of receiving and allowing the evaporation of these industrial wastestreams, or the power plants designs must be modified to eliminate these flows.

The alternatives evaluated by CPS Energy for providing alternative capacity for these flows included the following:

- Alternative 1 - Retrofitting an existing surface impoundment
- Alternative 2 - Constructing a new surface impoundment

CPS Energy is in the process of reducing their environmental risk exposure by eliminating/reducing the number of outfalls and wastestreams that return to Calaveras Lake. During the initial EP alternatives evaluation, CPS Energy recognized that if they added a separate wastewater treatment facility (WWTF) to manage the industrial wastestreams, they would be adding a wastestream and thus increasing their environmental risk exposure. During the initial EP alternatives evaluation, CPS Energy also recognized they could combine the efforts of this project with a separate ongoing project which involved constructing a new EP for storing and treating domestic wastewater (i.e., sanitary waste). Domestic wastewater is currently being treated at four existing wastewater treatment plants (WWTPs) on-site. By combining the projects, CPS Energy could utilize a single EP to store and treat both domestic wastewater and the industrial wastestreams.

3.4.1 Retrofitting an Existing Surface Impoundment

All the existing surface impoundments at the Calaveras Power Station have a liner system; however, none of these systems meet the specific liner requirements in the CCR Rule (40 CFR §257.72) and are therefore classified as unlined. All surface impoundments (including CCR and non-CCR surface impoundments) at the Calaveras Power Station are listed in Exhibit 3.2. A Surface Impoundment Location Map is provided as Figure 3.1.

Exhibit 3.2 – Calaveras Power Station Surface Impoundments

Name	Description	Storage Capacity (MM gallons)	Liner	Status
Pond #1	Diked Oil Storage Area	0.2	Unlined	Active
Pond #2	Coal Pile Runoff Pond	32.6	Unlined	Active
Pond #3	North Bottom Ash Pond	20.5	Unlined	Inactive
Pond #4	South Bottom Ash Pond	22.5	Unlined	Inactive
Pond #5	Stormwater (Southwest Runoff Pond 3)	1.7	Unlined	Active
Pond #6	Stormwater (CRP Runoff Pond 1)	5.9	Unlined	Active
Pond #7	SRH Pond	4.0	Unlined	Active
Pond #8	Stormwater (CRP Runoff Pond 2)	2.7	Unlined	Active
Pond #9	Stormwater Runoff (Fly Ash) Pond	9.7	Unlined	Active
Pond #10	Evaporation Pond	5.1	Unlined	Active
Pond #11	Clarifier Sludge Recycling Pond	0.8	Unlined	Active
Pond #12	Stormwater (Coal conveyor area temporary holding pond)	1.1	Unlined	Active

Excluding the existing EP, there are nine other active surface impoundments (both CCR and non-CCR surface impoundments) at the Calaveras Power Station. Six of these nine surface impoundments are needed for stormwater management and release to Calaveras Lake as permitted discharges. These six surface impoundments also do not have sufficient capacity to receive industrial wastestreams in addition to their designed stormwater capacity. Since these six surface impoundments are unavailable for added capacity and since the industrial wastestreams managed in the EP would not meet the low discharge permit limits for metals (specifically iron and copper), these surface impoundments are not available for retrofit as alternative capacity. In addition, a major amendment for a discharge permit renewal would take between one and two years for approval.

As for the three active surface impoundments not associated with stormwater management, the footprint of two are not large enough to handle the industrial wastestreams managed in the EP and one (SRH Pond) is being closed as an unlined CCR surface impoundment. Therefore, these three surface impoundments are also not available for retrofit as alternative capacity. The two inactive surface impoundments, the North and South Bottom Ash Ponds, have ceased receiving flow and will be clean closed. The schedule for release of these surface impoundments for re-development following closure is unknown and these surface impoundments will not be available for retrofit until all closure activities are complete.

The anticipated combined flow volume to the existing EP was also reviewed and it was determined that the existing EP footprint is not large enough to handle both the sanitary and industrial wastestreams. In addition, the duration for the removal of all CCR in the existing EP and the design, procurement, and installation of a new liner system is longer than the selected alternative (constructing a new surface impoundment).

3.4.2 Constructing a New Surface Impoundment

The selected alternative, constructing a new lined surface impoundment, is the least complex alternative and it can be implemented in the shortest duration of time. CPS Energy has been working on preliminary design and evaluation of alternative capacity since May 2019. Now that CPS Energy has selected an option, the detailed design, contractor selection, and construction work has commenced. An overall duration of 22 months is expected for this alternative to allow the cessation of non-CCR flow to the EP by May 26, 2022. Constructing a new lined surface impoundment also retains the primary operational functionality of the existing EP and requires minimal modifications to the existing power plants. In

addition, Alternative 2 allows for a single EP, constructed with a liner system compliant with State requirements, to store and treat both domestic wastewater and the industrial wastestreams and allows for the existing EP to be closed per the CCR Rule and thus minimizing the potential environmental compliance risks from continuing to use the existing EP.

A primary goal of the alternatives evaluated was to consolidate wastewater flows at the Calaveras Power Station so that treatment can be accomplished at a single, centralized location as opposed to the four existing WWTPs located on-site. The consolidation approach is shown on the process flow diagram (PFD) provided as Exhibit 3.3. The proposed alignment for consolidating flows and preliminary layout for the new EP is shown on the preliminary site plan provided as Exhibit 3.4.


Temporary storage tanks were evaluated for the period while the new EP is being planned and constructed. The existing EP has a hydraulic retention capacity of over 5,000,000 gallons. During typical plant operations, the non-CCR flow volume of nonhazardous liquids to the existing EP ranges between 1,000,000 and 2,000,000 gallons per year. These flows are intermittent and mostly occur during discrete maintenance/ cleaning events over a relatively short period of time. The existing EP does not have an inlet or discharge pipe and only receives various non-CCR flows discharged via tanker trucks. In the short term, while the new EP is being planned and constructed, an estimated 1,000,000 gallons of storage will be required for the various power plants to continue operation.

Utilizing frac tanks with capacities of 21,000 gallons, approximately 50 frac tanks would be required to replace the estimated 1,000,000 gallons of storage. Finding a suitable location for 50 frac tanks would be difficult at the site and the overall footprint would be even larger due to the spill containment measures required for the frac tanks. Due to the large number of frac tanks required, the risk of spill or release to the environment would be greatly increased. An additional downside of frac tanks is that they would not allow for evaporation of the liquids and ultimately the contents would have to be discharged into the new EP once it is in service.

The other option for temporary storage is modular tanks. The maximum height of a modular tank is about 12 feet, however, using a 6-foot high tank would allow for greater surface area for additional evaporation. Modular tanks may be constructed with a bolted steel frame and geosynthetic membrane liner and require a large flat graded area. To store a volume of 1,000,000 gallons, a 6-foot high tank (assuming a water height of 4 feet) would require approximately 34,000 square feet of flat space. A flat space of this size is limited at the site. An additional downside of modular tanks is the increased likelihood of a failure resulting in a release to the environment.

Due to the limited area available for installation and the risk of release to the environment, temporary storage tanks are technically not a feasible option.

Exhibit 3.3: Proposed Process Flow Diagram for Consolidating WWTP Flows



Based on the work completed to date, CPS Energy identified the following primary scope items for construction of the new EP:

- Construction of the new EP to store and treat domestic wastewater and industrial wastestreams. The preliminary footprint is approximately 6.5 acres and consists of two cells to assist with pond maintenance. The new EP will be constructed with a liner system that will be compliant with State requirements.
- Redirection of the existing industrial wastestreams to the new EP.
- Commencement of closure of the existing EP.
- Consolidation of domestic wastewater flows from the four existing WWTPs. A PFD of the proposed improvements for the domestic waste is shown as Exhibit 3-3. New pumps will be provided at each existing WWTP for pumping from the various units to the Sommers/Deely WWTP. A preliminary force main alignment is shown on Exhibit 3-4; however, the Sommers/Deely WWTP will be relocated to be adjacent to the new EP.
- Direction of WWTP flows to the new EP.

Exhibit 3.4: Proposed Site Plan



3.4.3 Summary of Alternatives Evaluated and Selected Alternative

A summary of the two evaluated alternatives is provided below.

- Alternative 1 – Retrofitting an existing surface impoundment to receive the EP flow is a more complex alternative and was not selected for the following reasons:
 - The duration for the removal of all CCR in the existing EP and the design, procurement, and installation of a new liner system is longer than the selected alternative (Alternative 2). In addition, the footprint of the existing EP is not large enough to handle both the planned sanitary and industrial wastestreams.
 - Excluding the existing EP, there are nine other active surface impoundments (both CCR and non-CCR surface impoundments) at the Calaveras Power Station. Six of these nine surface impoundments are needed for stormwater management and release to Calaveras Lake as permitted discharges. These six surface impoundments also do not have sufficient capacity to receive industrial wastestreams in addition to their designed stormwater capacity. Since these six surface impoundments are unavailable for added capacity and since the industrial wastestreams managed in the EP would not meet the low discharge permit limits for metals (specifically iron and copper), these surface impoundments are not available for retrofit as alternative capacity. In addition, a major amendment for a discharge permit renewal would take between one and two years for approval.
 - As for the three active surface impoundments not associated with stormwater management, the footprint of two are not large enough to handle the industrial wastestreams managed in the EP and one (SRH Pond) is being closed as an unlined CCR surface impoundment. Therefore, these three surface impoundments are also not available for retrofit as alternative capacity.
 - The two inactive surface impoundments, the North and South Bottom Ash Ponds, have ceased receiving flow and will be clean closed. The schedule for release of these surface impoundments for re-development following closure is unknown and these surface impoundments will not be available for retrofit until all closure activities are complete.
- Alternative 2 – The selected alternative, constructing a new lined surface impoundment, is the least complex alternative and it can be implemented in the shortest duration of time. An overall duration of 22 months is expected for this alternative to allow the cessation of CCR and non-CCR flow to the EP by May 26, 2022. Constructing a new lined surface impoundment also retains the primary operational functionality of the existing EP and requires minimal modifications to the existing power plants.

3.5 Detailed Schedule of the Fastest Feasible Time to Complete Measures Necessary for Alternative Capacity

Engineering, construction, procurement and start-up of the new EP will require approximately 22 months. A graphic schedule for the activities outlined in Sections 3.6 and 3.7 is included as Figure 3.2.

3.6 Narrative Discussion of the Schedule and Visual Timeline Representation

As shown in Figure 3.2 and described in Sections 3.6 and 3.7, CPS Energy has already undertaken significant planning steps towards initiating closure of the existing EP. This section is focused on the remaining work necessary to obtain alternative disposal capacity for the industrial wastestreams and domestic wastewater flows. The durations shown in the schedule in Figure 3.2 are based on a number of factors, including a 50-hour per week construction schedule, the estimated piping quantities for the new EP, and the estimated volume of earthwork required.

Detailed engineering for the water redirection and new EP construction will begin after the study phase and is scheduled to be completed in March of 2021. Preparation of equipment specifications and the technical specifications will occur concurrently with detailed engineering. The construction contract will include construction of the new EP and installation of the major utility corridors (i.e., piping to/from the WWTP to the new Sommers/Deely WWTP and new EP) and new lift stations. Construction drawings for the new EP design will be submitted to the Texas Commission on Environmental Quality (TCEQ) for General Permit, Texas Pollutant Discharge Elimination (TPDES) and Engineer's Certification of Surface Impoundment review and permit approval. A Tree Survey and Cultural Resources review will be submitted to the City of San Antonio for review and approval. The permit drawings will be submitted following the 60% review meeting and this effort is anticipated to take up to five months to complete. CPS Energy will issue the detailed design drawings for bid prior to receiving the permit, but will not award the construction contract until the TCEQ approval is received. Bid documents will be issued in March of 2021. Three months were included for the bid period and bid review, with the construction contract award and contract negotiations completing in October of 2021.

In the bidding phase, potential contractors will be issued a RFP in March 2021 for the procurement and construction project. The bid, selection and award phase includes the following tasks:

- Contractor Bid Period – 8 weeks

A duration of 8 weeks is planned for the bidders to prepare their proposals. A bidder meeting will be scheduled shortly following issue of the Request for Proposal. The meeting may be held at the site during which the bidders can walkdown the project area and present their questions. The bidders may also formally submit questions throughout the bid cycle.

The project scope includes vendor engineered procurements, shop fabricated components, construction, start-up and commissioning. The construction scope includes civil earthworks, structural, mechanical, electrical, instrumentations and control system modifications. This broad scope may require some bidders to engage subcontractors or partners to execute this work. This type of arrangement typically requires a longer period of time for the bidders to prepare a response due to these formalized agreements.

- Bid Evaluation and Management Review – 8 weeks

Proposals received by the submittal date will be evaluated. The initial review involves an assessment to confirm the proposals are complete and meet the minimum requirements of the RFP. Proposals submitted will then be evaluated versus the specifications and preliminary design documents. This involves a detailed assessment of the proposed equipment, material quantities, staffing and schedule. Included is a review of the proposed means and methods and any alternates that may improve the design or reduce cost. Other criteria such as experience performing similar work, safety record and proposed project staffing are also evaluated. The duration of the initial evaluation of the bids is 4 - 6 weeks and is dependent on the quality of the proposals. During this process, bidders may be requested to provide additional information or clarify their offering.

The preliminary evaluation and a preliminary ranking of the bidders will be issued to CPS Energy management for review. A period of 2 to 4 weeks is planned for management review and approval to move forward with a recommendation to the Board of Trustees. The overall evaluation period from receipt of proposals to recommendation to the Board is 8 weeks.

- **Contract Negotiation – 6 to 8 weeks**

Prior to CPS Energy Board of Trustees approval, the negotiations with the recommended bidder(s) will be initiated. During this period, the bidders will be requested to address any clarifications and exceptions, respond to any outstanding questions and finalize the project terms and conditions. Negotiations require legal review and management approval. A project of this size typically requires multiple meetings over a period of 6 to 8 weeks to address all technical and commercial items.

- **CPS Energy Board Review and Approval – 8 weeks**

At the end of the negotiation period, the recommendation will be presented to the CPS Energy Board of Trustees. CPS Energy is governed by a Board comprised of citizens representing each quadrant of the city and the San Antonio mayor. The Board meets monthly and the agenda is set 1 month prior to each meeting. As a result, a minimum of 2 months is required for Board review and approval.

- **Contract Award – 2 to 4 weeks**

Following Board approval, CPS Energy Procurement will enter into a formal contract agreement with the selected vendor. A period of 2 to 4 weeks is planned for this procurement process.

During construction of the new EP, the anticipated worker schedule will involve work 5 days per week, working approximately 10 hours per day. If weather or other delays are encountered, the worker schedule may be adjusted (increased) for additional workdays in the event that the contractor gets behind schedule. The contractor will mobilize following contract award. Procurement of major equipment, including pumps, piping, and liner materials, will occur while the contractor proceeds with site clearing and major earthwork activities. In general, construction work will proceed as follows:

- Contractor will begin construction of the new EP, including mobilization, site clearing and earthwork to build the pond berms (October 2021 – January 2022).
- Contractor will install TCEQ-required leak detection system, composite liner system, and protective cover over the pond bottom (January – April 2022).
- Startup and commissioning of the new EP (April – May 2022). At this point, CPS Energy can relocate non-CCR flows to the new EP and may begin closure of the existing EP.
- Contractor will install force main/lift stations to consolidate WWTP flows and direct them to the new Sommers/Deely WWTP location (April – May 2022).
- Contractor will relocate the Sommers/Deely WWTP effluent to the new EP (May-July 2022).
- Startup and commissioning of the new force main and Sommers/Deely WWTP (August – September 2022).

The new EP construction is expected to be finalized by May 26, 2022, allowing for final receipt of non-CCR wastestreams in the existing EP. The actual dates and duration may be altered by a number of factors, including delays caused by adverse weather, contractor efficiency, or potential craft shortages associated with COVID-19. Note that the existing EP closure activity is not considered part of this Demonstration.

3.7 Narrative Discussion of the Progress Made to Obtain Alternative Capacity for the CCR and/or Non-CCR Wastestreams

As described in Section 3.6 and as shown in Figure 3.2, CPS Energy has made considerable progress in developing a path forward for obtaining alternative disposal capacity for the non-CCR wastestreams that are currently managed in the existing EP. As of the date of this Demonstration, a 30% design has been completed for the project as part of the initial study/evaluation and a design review meeting has been conducted. CPS Energy has evaluated multiple iterations of the project scoping and cost estimate

development in order to find the best compliance solution for the Calaveras Power Station. EPA should note CPS Energy did not have a CCR closure trigger under the original CCR Rule as published in 2015. CPS Energy has evaluated alternatives as described in Section 3.4, and is in the process of developing the project design to support procurement of the new equipment and construction of the required scope items.

4. COMPLIANCE WITH SUBPART D

As identified in 40 CFR §257.103(f)(1)(iv)(B), to demonstrate that the criteria in 40 CFR §257.103(f)(1)(iii) have been met, the owner or operator must submit all of the following, if applicable:

1. A certification signed by the owner or operator that the facility is in compliance with all of the requirements of this subpart (See Appendix A);
2. Visual representation of hydrogeologic information at and around the CCR unit(s) that supports the design, construction and installation of the groundwater monitoring system. This includes all of the following:
 - i. Map(s) of groundwater monitoring well locations in relation to the CCR unit(s) (See Appendix B);
 - ii. Well construction diagrams and drilling logs for all groundwater monitoring wells (See Appendix C); and
 - iii. Maps that characterize the direction of groundwater flow accounting for seasonal variations (See Appendix D);
3. Constituent concentrations, summarized in table form, at each groundwater monitoring well monitored during each sampling event (See Appendix E);
4. A description of site hydrogeology including stratigraphic cross-sections (See Appendix F);
5. Any corrective measures assessment conducted as required at §257.96 (Not Applicable – no corrective measures assessment has been required);
6. Any progress reports on corrective action remedy selection and design and the report of final remedy selection require at §257.97(a) (Not Applicable – no corrective action remedy has been required);
7. The most recent structural stability assessment required at §257.73(d) (See Appendix G); and
8. The most recent safety factor assessment required at §257.73(e) (See Appendix G).

FIGURES




Environmental Resources Management

FIGURE 2.1
FACILITY LOCATION MAP


CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 7/25/2016	SCALE: AS SHOWN	REVISION: 1
W.O.NO.: K:\GIS\CPS\Calaveras\MXD\0337367_CPSCalaveras_SiteLoc.mxd		



San Antonio East	Marathon	East Hedrick
Southwest	Midland	La Villa SW
Lubbock	Brewster	Pecos/El



Environmental Resources Management

FIGURE 2.2
CCR UNIT LOCATION MAP

CPS Energy - Calaveras Power Station
San Antonio, Texas




DESIGN: CC	DRAWN: RLM	CHKD.: CC
DATE: 9/19/2018	SCALE: AS SHOWN	REV.:
W.O. NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_CCRUnitLocs_topo.dwg		

ERM-Southwest, Inc. TX PE Firm No. 2393

- PLANT WORK AREA**
- A GMS / ELECTRICAL / WELDING SHOP (WAREHOUSE # 1)
 - B SEWAGE TREATMENT
 - C THORPE WAREHOUSE
 - D STORE ROOM (WAREHOUSE #2)
 - E 591 STORE ROOM (WAREHOUSE #3)
 - F RAIL CAR MAINTENANCE
 - G FUEL ISLAND
 - H GENERATION OPERATION BUILDING
 - I JK SPRUCE 1
 - J JK SPRUCE 2
 - K JK SPRUCE OFFICE
 - L ENGINEERING SERVICE BUILDING
 - M CONSTRUCTION OFFICE BUILDING
 - N JT DEELY & OW SOMMERS OFFICE
 - O OWS 1
 - P OWS 2
 - Q JTD 1
 - R JTD 2
 - S WAREHOUSE #4
 - T WAREHOUSE #5
 - U NEUTRALIZATION PIT
 - V BAG HOUSE
 - W COAL CAR UNLOADING BLDG. / DUMPER BLDG.
 - X TRANSFER BLDG

LEGEND

 SURFACE IMPOUNDMENTS



- SURFACE IMPOUNDMENTS**
- 1 DIKED OIL STORAGE AREA (NOR UNIT 28)
 - 2 COAL PILE RUNOFF POND (NOR UNIT 018)
 - 3 NORTH BOTTOM ASH POND (NOR UNIT 5)
 - 4 SOUTH BOTTOM ASH POND (NOR UNIT 6)
 - 5 STORM WATER (SOUTHWEST RUNOFF POND 3)
 - 6 STORM WATER (CRP RUNOFF POND 1)
 - 7 SRH / FGD POND (DIVIDED TO NORTH AND SOUTH)
 - 8 STORM WATER (CRP RUNOFF POND 2)
 - 9 FLY ASH RUNOFF POND (NOR UNIT 27)
 - 10 EVAPORATION POND (NOR UNIT 21)
 - 11 CLARIFIER SLUDGE RECYCLING POND (NOR UNIT 25)
 - 12 STORM WATER (COAL CONVEYOR AREA TEMP HOLDING POND) NOR UNIT 32

FIGURE 3.1
 SURFACE IMPOUNDMENT LOCATION MAP
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

CPS Extension Project





FIGURE 3.2
NEW EVAPORATION POND PROJECT SCHEDULE
 CPS Energy - Calaveras Power Station - San Antonio, Texas

APPENDIX A OWNER CERTIFICATION OF COMPLIANCE

**ALTERNATIVE CAPACITY DEMONSTRATION CERTIFICATION
40 CFR §257.103(f)(1)(iv)(B)(1)**

**CPS Energy Calaveras Power Station
San Antonio, Texas**

CERTIFICATION

As owner and operator of the Evaporation Pond, I hereby certify that the Calaveras Power Station is in compliance with all the requirements of Subpart D – Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments.






 11/2/20



Benjamin L. Ethridge, P.E.
Senior VP Power Generation
CPS Energy

APPENDIX B GROUNDWATER MONITORING WELL LOCATIONS MAP

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  Plugged and Abandoned Monitor Well
-  CCR Unit



Environmental Resources Management


FIGURE 1
CCR WELL NETWORK LOCATION MAP
CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN: WZ	DRAWN: EFC	CHKD.: WZ
DATE: 1/17/2020	SCALE: AS SHOWN	REVISION: 0

\\ushoufs011\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\IMXD\2019\gwm\fig1_0503422_CPSCalv_WellLocs.mxd

APPENDIX C WELL CONSTRUCTION DIAGRAMS AND DRILLING LOGS



PROJECT NAME

CALAVERAS PLANT - UNITS 5 AND 6
LANDFILL AREA EXPLORATION
San Antonio, Texas


Monitor Well No. B-31

PROJECT NO.

312-75036

DATE

7-9-87



PROJECT NAME

CALAVERAS PLANT - UNITS 5 AND 6
LANDFILL AREA EXPLORATION
San Antonio, Texas

Monitor Well No. B-33


PROJECT NO

312-75036

DATE

7-9-87

BW-36



* Calibration problem on resistivity curve



ESPEY, HUSTON & ASSOCIATES, INC.
Engineering & Environmental Consultants

FIGURE A-2
MONITORING WELL BW-36
GEOPHYSICAL/LITHOLOGIC LOGS



ERM Environmental Resources Management

**JKS-45
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-45 Date Drilled 2016-04-04
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 62.00' Boring Diam. 8.25"
 N. Coord. 13667132.78' E. Coord. 2186615.40' Surface Elevation 528.31' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 40.00' Sump Length 0'
 Top of Casing Elevation 531.46' Stickup 3.15'
 Depth to Water: 1. Ft. btoc 47.19 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South
 Central State Plane 4204.
 Elevations in NAVD88
 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
528.31	0			0		0-5	NO RECOVERY: Previously excavated by hydrovac truck.
525	5			100		5-7	SILTY CLAY: Brown; dry to damp; medium stiff; medium plasticity; some white calcareous concretions present. At 5.5' bgs: Slight orange mottling. At 6' bgs: White silt lens.
520	10			50		7-10	CLAY: Grey; dry to damp; stiff; medium to high plasticity; minor silt content at depth; white calcareous concretions throughout. At 7.5' bgs: Orange mottling. At 9' bgs: Yellowish orange silt lens.
515	15			75		10-12.5	SILT: Alternating light grey and yellowish brown, stratified with orange, yellow, and red; damp; loose; non-plastic.
						12.5-15	NO RECOVERY.
510	20					15-22	SILT: Brownish light grey; damp; loose to medium dense; non-plastic; some yellow stringers. At 16' bgs: Alternating pinkish brown stratifications (2" thick). At 16.5' bgs: Orange band (2" thick). At 17.5' bgs: Orange band (1" thick). At 19' bgs: Light grey and pinkish brown laminations; minor clay content; occasional orange silt stringers.



ERM Environmental Resources Management

**JKS-45
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-45 Date Drilled 2016-04-04
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 62.00' Boring Diam. 8.25"
 N. Coord. 13667132.78' E. Coord. 2186615.40' Surface Elevation 528.31' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 40.00' Sump Length 0'
 Top of Casing Elevation 531.46' Stickup 3.15'
 Depth to Water: 1. Ft. btoc 47.19 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
505	20	[Hatched pattern]	[Solid black]	75		22-25	CLAYEY SILT: Pinkish brown laminated with light grey; dry to damp; medium dense to dense; slight plasticity; trace yellow and orange silt stringers.
500	25	[Hatched pattern]	[Solid black]	100	JKS-45_28-30 USCS: Fat Clay (CH) AL: 61 / 22 / 39 -200 Sieve: 91.6	25-34.5	SILTY CLAY: Dark reddish brown; dry to damp; medium stiff; low plasticity; fractures along planar surfaces. At 25.5' bgs: Light grey silt lens (2" thick). At 28' bgs: Light grey silt stringers; yellow silt stringers and minor gypsum crystals from 28' to 30' bgs. Non-cohesive grab sample collected from 28'-30' bgs.
495	30	[Hatched pattern]	[Solid black]	100			At 31.5' bgs: Dry; yellow silt stringers; abundant yellowish orange silt stringers to 32' bgs. At 33.5' bgs: Trace gypsum crystals.
490	35	[Hatched pattern]	[Solid black]	100	JKS-45_36-38 USCS: Fat Clay (CH) AL: 67 / 24 / 43 -200 Sieve: 90.5	34.5-35 35-36	SILT: Dark pinkish brown laminated with greyish brown; dry; dense; non-plastic; some clay content.
						36-38	SILTY CLAY: Very dark reddish brown; damp to moist; medium stiff; low plasticity; trace yellow silt; minor gypsum crystals; brownish black band (2" thick) at 35' bgs.
						38-43	CLAY: Pinkish grey; dry; very stiff to hard; very high plasticity (fat). Non-cohesive grab sample collected from 36'-38' bgs. At 36.5' bgs: Yellow and orange silt stringers to 37.5' bgs. SILT: Orangish brown; dry to damp; medium dense to dense; slight plasticity; slight clay content.
40	40	[Dotted pattern]	[Dotted pattern]				



JKS-45
DRILLING LOG

Proj. No. 0337367 Boring/Well ID JKS-45 Date Drilled 2016-04-04
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 62.00' Boring Diam. 8.25"
 N. Coord. 13667132.78' E. Coord. 2186615.40' Surface Elevation 528.31' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 40.00' Sump Length 0'
 Top of Casing Elevation 531.46' Stickup 3.15'
 Depth to Water: 1. Ft. btoc 47.19 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
485	40	[Hatched pattern]	[Dotted pattern]	80		43-45	At 38.75' bgs: Brownish black band (1.5" thick). At 39.25' bgs: Yellow silt stringers. At 39.5' bgs: Color change to brownish grey; very dense; increased clay content. At 40' bgs: Yellow and orange silt stringers to 43' bgs; some compacted silt pieces to 43' bgs. CLAYEY SILT: Dark reddish brown; damp; medium dense; slight plasticity; orange silt stringers throughout.
480	45	[Dotted pattern]	[Dotted pattern]	50	JKS-45_50-52 USCS: Silty Sand (SM) AL: Non-plastic -200 Sieve: 12.6	45-55	At 44.5' bgs: Trace fine-grained sand content. SAND: Light grey to grey stratified with yellow, orange and red; wet to saturated; fine-grained to medium grained with depth; sub-rounded; well sorted; loose; non-plastic; minor clay lenses (1/16" to 1/8" thick).
475	50	[Dotted pattern]	[Dotted pattern]	50			At 48' bgs: Color change to orangish brown with orange laminations; no clay content. At 49.5' bgs: Intermixed red color to 50' bgs. At 50' bgs: Color change to pinkish brown. Non-cohesive grab sample collected from 50'-52' bgs.
470	55	[Hatched pattern]	[Dotted pattern]	100	JKS-45_55-57 USCS: Fat Clay (CH) AL: 75 / 28 / 47 -200 Sieve: 97	55-62	At 54.5' bgs: Brownish orange band (2" thick). CLAY: Dark grey; damp; stiff to very stiff; very high plasticity (fat); occasional light grey silt stringers; fractures along silt stringers. Non-cohesive sample collected from 55'-57' bgs.
60		[Hatched pattern]	[Dotted pattern]				



ERM Environmental Resources Management

**JKS-45
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-45 Date Drilled 2016-04-04
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 62.00' Boring Diam. 8.25"
 N. Coord. 13667132.78' E. Coord. 2186615.40' Surface Elevation 528.31' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 40.00' Sump Length 0'
 Top of Casing Elevation 531.46' Stickup 3.15'
 Depth to Water: 1. Ft. btoc 47.19 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South
 Central State Plane 4204.
 Elevations in NAVD88
 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
60				100	JKS-45_60-62 USCS: Fat Clay (CH) AL: 75 / 26 / 49 -200 Sieve: 86.4 k: 1.82x10 ⁻⁸		Cohesive sample (Shelby tube) collected from 60'-62' bgs. Boring terminated at 62' bgs.
465							
65							
460							
70							
455							
75							
450							
80							

STATE OF TEXAS WELL REPORT for Tracking #424209

Owner: CPS Energy	Owner Well #: JKS-45
Address: PO Box 2906 San Antonio, TX 78299	Grid #: 68-46-5
Well Location: Calaveras Power Station San Antonio, TX	Latitude: 29° 19' 01" N
Well County: Bexar	Longitude: 098° 18' 08" W
	Elevation: 528 ft. above sea level
Type of Work: New Well	
	Proposed Use: Monitor

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	62

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	38	56	Sand	20/40

Annular Seal Data: **No Data**

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	52	62

Water Quality: Strata Depth (ft.) **No Data** Water Type **No Data**
 Chemical Analysis Made: **No**
 Did the driller knowingly penetrate any strata which
 contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
112 S. Norwood Drive
Hurst, TX 76053

Driller Name: **Joseph Ray** License Number: **58794**

Comments: **No Data**

Lithology:
 DESCRIPTION & COLOR OF FORMATION MATERIAL

Casing:
 BLANK PIPE & WELL SCREEN DATA


Top (ft.)	Bottom (ft.)	Description	Dia (in.)	Type	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
0	5	Ash						
5	8	Lt brn sandy clay	2	Riser	New Plastic (PVC)	40	0	40
8	14	Lt gry sandy clay	2	Screen	New Plastic (PVC)	40 10	40	55
14	20	Lt gray sand						
20	40	Brn silty clay						
40	45	Lt gray sand						
45	55	yellow/org silty sand						
55	62	Green/gray clay						

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

**Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880**



ERM Environmental Resources Management

**JKS-46
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-46 Date Drilled 2016-04-05
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 30.00' Boring Diam. 8.25"
 N. Coord. 13667810.11' E. Coord. 2187972.31' Surface Elevation 495.75' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 499.08' Stickup 3.33'
 Depth to Water: 1. Ft. btoc 19.38 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
495.75	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			100		5-8	CLAYEY SAND: Reddish orange; damp to moist; fine-grained; sub-round; well-sorted; medium dense; slight to low plasticity; some silt content.
						8-10	At 7.5' bgs: Dense grey clay lenses (1/2" thick). SANDY CLAY: Reddish orange; medium stiff; slight to low plasticity; minor silt content; dense grey clay lenses (1/2" thick); yellow and yellowish orange silt stringers.
485	10			75		10-11	At 9.5' bgs: Increased silt content. CLAY: Grey; dry; stiff; medium plasticity; minor silt content; fractures along tan silt to fine-grained sand stringers.
						11-15	SAND: Tan; damp; fine-grained; sub-round, well sorted; loose; non-plastic.
							At 13' bgs: Striated with pink and orange.
480	15			85		15-19.5	At 14' bgs: Color change to reddish orange; some silt content; occasional clay lenses. At 14.75' bgs: Orange silt lens. SILT: Red with orange; damp to dry; loose; slight plasticity. At 15.5' bgs: Color change to grey. At 15.75' bgs: Color change to red.
							At 16' bgs: Color change to tan with yellow; fractures along planar surfaces. At 17' bgs: Moist.
						19.5-25	At 18.75' bgs: Color change to red and orange. SAND: Tan; moist; fine-grained, coarsens with depth; sub-round; well sorted; loose; non-plastic; minor silt and trace clay; orange and yellow silt stringers.



ERM Environmental Resources Management

**JKS-46
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-46 Date Drilled 2016-04-05
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 30.00' Boring Diam. 8.25"
 N. Coord. 13667810.11' E. Coord. 2187972.31' Surface Elevation 495.75' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 499.08' Stickup 3.33'
 Depth to Water: 1. Ft. btoc 19.38 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
475	20	[Dotted pattern]	[Well casing]	75	No Samples Collected	25-30	<p>At 20' bgs: Color change to brownish tan with orange band (2" thick) at 20.25' bgs. At 21.5' bgs: Color change to tannish grey with yellowish orange band (2" thick). At 22.5' bgs: Color change to tan stratified with pinkish orange and orange.</p> <p>CLAY: Dark greyish brown; damp to dry; very stiff; high to very high plasticity (fat); fractures along planar surfaces; Light grey and yellowish orange silt lenses throughout.</p> <p>At 29.75' bgs: Dark grey silt lenses; some very small gypsum crystals. Boring terminated at 30' bgs.</p>
470	25	[Diagonal lines]	[Well casing]	100			
465	30	[Diagonal lines]	[Well casing]				
460	35						
40	40						

STATE OF TEXAS WELL REPORT for Tracking #424210

Owner: CPS ENERGY	Owner Well #: JKS-46
Address: PO BOX 2906 SAN ANTONIO, TX 78299	Grid #: 68-46-5
Well Location: Calaveras Power Station SAN ANTONIO, TX	Latitude: 29° 19' 01" N
Well County: Bexar	Longitude: 098° 18' 08" W
	Elevation: 496 ft. above sea level

Type of Work: New Well	Proposed Use: Monitor
-------------------------------	------------------------------

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	30

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	13	25	Sand	20/40

Annular Seal Data: **No Data**

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: Surface Slab Installed	Surface Completion by Driller
---	--------------------------------------

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	26	30

Water Quality: *Strata Depth (ft.)* *Water Type*
 No Data **No Data**

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
 112 S. Norwood Drive
 Hurst, TX 76053

Driller Name: **Joseph Ray** License Number: **58794**

Comments: **No Data**


<i>Lithology:</i>			<i>Casing:</i>						
DESCRIPTION & COLOR OF FORMATION MATERIAL			BLANK PIPE & WELL SCREEN DATA						
<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	
0	5	ASH							
5	8	LT BRN SANDY CLAY	2	Riser	New Plastic (PVC)	40	0	15	
8	14	LT GRY CLAY	2	Screen	New Plastic (PVC)	40 10	15	25	
14	28	LT GRY SAND							
28	30	BRN CLAY							

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-47
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-47 Date Drilled 2016-04-05
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 48.00' Boring Diam. 8.25"
 N. Coord. 13665709.79' E. Coord. 2186503.87' Surface Elevation 510.28' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 25.00' Sump Length 0'
 Top of Casing Elevation 513.63' Stickup 3.35'
 Depth to Water: 1. Ft. btoc 31.37 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
510.28 510	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
505	5			0		5-9.5	CLAYEY SILT: Pinkish brown with grey; damp to moist; loose; slight to low plasticity; occasional yellow and orange silt lenses. At 5.5' bgs: Clay lens (2" thick).
500	10			90		9.5-20	At 9.25' bgs: Clay lens (2" thick). SILT: Light grey; damp; medium dense; slight plasticity; minor clay content, decreases with depth; abundant yellow and orange silt stringers; fractures along planar surfaces. At 10' bgs: Striated with pinkish brown to 12' bgs.
495	15			50			At 12.5' bgs: No clay content. At 13' bgs: Color change to tan; dry; yellow and orange silt stringers.
	20						



ERM Environmental Resources Management

**JKS-47
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-47 Date Drilled 2016-04-05
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 48.00' Boring Diam. 8.25"
 N. Coord. 13665709.79' E. Coord. 2186503.87' Surface Elevation 510.28' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 25.00' Sump Length 0'
 Top of Casing Elevation 513.63' Stickup 3.35'
 Depth to Water: 1. Ft. btoc 31.37 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
490	20	[Graphic Log]	[Well Construction]	75	No Samples Collected	20-23	At 20' bgs: Whitish tan striated with yellow; minor fine-grained sand content. SANDY SILT: Whitish tan; dry; loose; non-plastic; occasional yellow and orange silt stringers, occurrence increases with depth.
485	25	[Graphic Log]	[Well Construction]	50		23-48	SAND: Whitish tan; dry to moist with depth; fine-grained; sub-round; well sorted; minor yellow and orange silt stringers; thin clay pinkish brown to brown clay laminations to 23.25' bgs. At 25' bgs: Color change to tannish brown; very moist.
480	30	[Graphic Log]	[Well Construction]	100			At 30' bgs: Saturated; Orange band (1" thick) at 30.25' bgs.
475	35	[Graphic Log]	[Well Construction]	50			At 34' bgs: Orange striations to 35' bgs. At 35' bgs: Trace orange silt stringers.
470	40	[Graphic Log]	[Well Construction]				



ERM Environmental Resources Management

**JKS-47
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-47 Date Drilled 2016-04-05
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 48.00' Boring Diam. 8.25"
 N. Coord. 13665709.79' E. Coord. 2186503.87' Surface Elevation 510.28' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 25.00' Sump Length 0'
 Top of Casing Elevation 513.63' Stickup 3.35'
 Depth to Water: 1. Ft. btoc 31.37 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South
 Central State Plane 4204.
 Elevations in NAVD88
 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	40	[Dotted pattern]	[Solid black]	75	No Samples Collected		At 40' bgs: Clayey sand lens (2" thick). At 40.5' bgs: Occasional pinkish brown silt stringers to 41' bgs. At 41.5' bgs: Abundant yellowish orange silt stringers to 42.5' bgs. At 41.5' bgs: Orange and brown laminated silt stringers to 43' bgs. At 44' bgs: Medium-grained; no silt content. At 46' bgs: Orangish brown silt layer (1/2" thick). At 46.5' bgs: Color change to greyish tan; fine to medium-grained with decreasing grain size with depth. Boring terminated at 48' bgs.
465	45	[Dotted pattern]	[Solid black]	100			
460	50						
455	55						
60							

STATE OF TEXAS WELL REPORT for Tracking #424211

Owner:	CPS ENERGY	Owner Well #:	JKS-47
Address:	PO BOX 2906 SAN ANTONIO, TX 78299	Grid #:	68-46-5
Well Location:	Calaveras Power Station SAN ANTONIO, TX	Latitude:	29° 18' 01" N
Well County:	Bexar	Longitude:	098° 18' 08" W
		Elevation:	510 ft. above sea level

Type of Work: New Well	Proposed Use: Monitor
-------------------------------	------------------------------

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	48

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	23	41	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	2	23	Bentonite 15 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **No Data**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	41	48

Water Quality: *Strata Depth (ft.)* *Water Type*
 No Data **No Data**

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
 112 S. Norwood Drive
 Hurst, TX 76053

Driller Name: **Joseph Ray** License Number: **58794**

Comments: **No Data**


Lithology:			Casing:						
DESCRIPTION & COLOR OF FORMATION MATERIAL			BLANK PIPE & WELL SCREEN DATA						
<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	
0	5	ASH							
5	8	LT BRN SANDY CLAY	2	Riser	New Plastic (PVC)	40	0	25	
8	14	LT GRAY SANDY CLAY	2	Screen	New Plastic (PVC)	40 10	25	40	
14	20	LT GRAY SAND							
20	40	BRN SILTY CLAY							
40	48	LT GRAY SAND							

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-48
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-48 Date Drilled 2016-04-06
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 30.00' Boring Diam. 8.25"
 N. Coord. 13659658.78' E. Coord. 2186490.78' Surface Elevation 493.71' Ft MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 18.50' Sump Length 0'
 Top of Casing Elevation 497.19' Stickup 3.48'
 Depth to Water: 1. Ft. btoc 11.28 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens


SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
493.71	0			0		0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			100		5-6	CLAYEY SILT: Orangish brown; damp; medium dense to dense; slight to low plasticity. At 5.5' bgs: Brown band (2" thick). At 5.75' bgs: Color change to brown; damp to dry; minor clay content; fractures along planar surfaces.
485	10			75	JKS-48_10-12.5 USCS: Clayey Sand (SC) AL: 35 / 16 / 19 -200 Sieve: 44.6	6-6.5 6.5-7 7-7.5	SILTY CLAY: Orangish brown heavily mottled with grey and orange; damp; stiff; medium plasticity; occasional grey and orange silt stringers. SILT: Brownish tan with grey and orange; damp; medium dense; slight plasticity; trace clay.
480	15			80	JKS-48_15-16.5 USCS: Sandy Lean Clay (CL) AL: 48 / 19 / 29 -200 Sieve: 58.9	7.5-12.5	SILTY CLAY: Orangish brown heavily mottled with grey and orange; damp; stiff; medium plasticity; occasional grey and orange silt stringers. CLAYEY SILT: Brown; damp to moist; medium dense; low plasticity; light grey and orange silt stringers. At 9' bgs: Dense silty clay layer (2" thick). At 9.25' bgs: Dense silty clay layer (2" thick). Non-cohesive grab sample collected from 10'-12.5' bgs. At 10.5' bgs: Dense silty clay layer (2" thick).
475	20				JKS-48_19-20 USCS: Clayey Sand (SC) AL: 26 / 16 / 10 -200 Sieve: 48.7	12.5-15	SAND: Brownish grey; damp to moist; fine-grained; sub-angular; moderately sorted; loose; non-plastic; minor silt content. At 13.5' bgs: Dense clay lens (1" thick). At 14.5' bgs: Color change to dark brown.
						15-16.5	CLAY: Brownish orange heavily mottled with dark brown, orange, and orangish red; moist; stiff; high plasticity; trace silt content, increases with depth; orange silt stringers. Non-cohesive grab sample collected from 15'-16.5' bgs.
						16.5-19	CLAYEY SILTY SAND: Brownish tan; very moist; loose to medium dense; slight plasticity; decreasing clay content with depth; occasional orange silt stringers. At 16.5' bgs: Wet.
						19-20	SAND: Orangish brown; very moist to wet; fine-grained; sub-angular; moderately sorted; loose; non-plastic; minor silt content, decreases with depth; laminated with light grey clay to 19.25' bgs. Non-cohesive grab sample collected from 19'-20' bgs.



ERM Environmental Resources Management

**JKS-48
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-48 Date Drilled 2016-04-06
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 30.00' Boring Diam. 8.25"
 N. Coord. 13659658.78' E. Coord. 2186490.78' Surface Elevation 493.71' Ft MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 18.50' Sump Length 0'
 Top of Casing Elevation 497.19' Stickup 3.48'
 Depth to Water: 1. Ft. btoc 11.28 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South
 Central State Plane 4204.
 Elevations in NAVD88
 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20	[Graphic Log]	[Well Construction]	50		20-22.5	SILTY SAND: Orangish brown; saturated; fine to very-fine grained; sub-angular, poorly sorted; loose; non-plastic; minor clay content. At 20.25' bgs: Thin grey clay laminations.
470	25	[Graphic Log]	[Well Construction]	50		22.5-25	SAND: Tannish brown with grey; saturated; fine-grained; sub-angular; moderately sorted; loose; non-plastic; some silt content; orange silt stringers. At 24.5' bgs: Orange silt lens to 24.75' bgs.
465	25	[Graphic Log]	[Well Construction]	50		25-27.5	INTERBEDDED SILTY SAND AND CLAY: Tannish grey; saturated; medium dense; laminated silty fine-grained sand with pinkish brown clay; clay laminations fracture along planar surfaces; yellow and orange silt stringers throughout.
465	30	[Graphic Log]	[Well Construction]	50		27.5-30	CLAYEY SILTY SAND: Tannish grey; saturated; loose; slight plasticity; orange 1/16" thick silt laminations throughout. At 29.5' bgs: Pinkish brown (1/16" thick) clay laminations to 30' bgs. Refusal (bedrock) encountered at 30' bgs.
460	35	[Graphic Log]	[Well Construction]				
455	40	[Graphic Log]	[Well Construction]				

STATE OF TEXAS WELL REPORT for Tracking #424212

Owner:	CPS ENERGY	Owner Well #:	JKS-48
Address:	PO BOX 2906 SAN ANTONIO, TX 78299	Grid #:	68-46-5
Well Location:	Calaveras Power Station SAN ANTONIO, TX	Latitude:	29° 19' 01" N
Well County:	Bexar	Longitude:	098° 18' 08" W
		Elevation:	494 ft. above sea level
Type of Work: New Well		Proposed Use: Monitor	

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	30
Drilling Method:	Hollow Stem Auger		
Borehole Completion:	Filter Packed		
	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>
Filter Pack Intervals:	16.5	20.5	Sand
	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	2	16.5	Bentonite 15 Bags/Sacks
Seal Method:	Hand Mixed		
Sealed By:	Driller		
			Distance to Property Line (ft.): No Data
			Distance to Septic Field or other concentrated contamination (ft.): No Data
			Distance to Septic Tank (ft.): No Data
			Method of Verification: No Data
Surface Completion:	Surface Slab Installed		Surface Completion by Driller

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	29.5	30

Water Quality: Strata Depth (ft.) No Data Water Type No Data
Chemical Analysis Made: No

Did the driller knowingly penetrate any strata which contained injurious constituents?: No

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: Strata Core Services, LLC
112 S. Norwood Drive
Hurst, TX 76053

Driller Name: Joseph Ray License Number: 58794

Comments: No Data


Lithology: DESCRIPTION & COLOR OF FORMATION MATERIAL			Casing: BLANK PIPE & WELL SCREEN DATA					
Top (ft.)	Bottom (ft.)	Description	Dia (in.)	Type	Material	Sch./Gage	Top (ft.)	Bottom (ft.)
0	5	ASH						
5	8	LT BRN CLAY	2	Riser	New Plastic (PVC)	40	0	18.5
8	14	LT GRAY CLAY	2	Screen	New Plastic (PVC)	40 10	18.5	28.5
14	20	LT GRAY SAND						
20	30	BRN SILTY CLAY						

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



JKS-49
DRILLING LOG

Proj. No. 0337367 Boring/Well ID JKS-49 Date Drilled 2016-04-06
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 19.00' Boring Diam. 8.25"
 N. Coord. 13660519.40' E. Coord. 2186229.15' Surface Elevation 495.17' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 7.00' Sump Length 0'
 Top of Casing Elevation 498.63' Stickup 3.46'
 Depth to Water: 1. Ft. btoc 9.32 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
495.17 495	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			50		5-6 6-10	SAND: Greyish tan; very moist; fine-grained; sub-angular; moderately sorted; loose; non-plastic; orange silt stringers. SILT: Greyish tan; very moist; loose; non-plastic; minor fine-grained sand; occasional yellow silt stringers.
485	10			100		10-15	At 9.5' bgs: Color change to light brown; wet; orange silt stringers. SAND: Light brown; wet; fine-grained; sub-angular; moderately sorted; loose to medium dense; non-plastic; minor silt content; abundant orange silt stringers. At 11.75' bgs: Orange silt lens (2" thick); trace silt stringers. At 12' bgs: Decreasing silt content.
480	15			100		15-16.5 16.5-19	At 14' bgs: Color change to greyish tan. SANDY SILT: Light brown; wet to saturated; loose; non-plastic; occasional orange silt stringers. At 17.5' bgs: Pinkish brown clay lens (3/16" thick). SILT: Brownish orange; wet to saturated; loose; non-plastic; minor fine-grained sand content. At 18.25' bgs: Color change to light brown. At 18.25' bgs: Color change to orange; pinkish brown clay lens (1/16" thick). At 18.5' bgs: Minor orange and red sandstone pieces, occurrence increases at depth. Refusal (bedrock) encountered at 19' bgs.
475	20						

STATE OF TEXAS WELL REPORT for Tracking #424213

Owner:	CPS ENERGY	Owner Well #:	JKS-49
Address:	PO BOX 2906 SAN ANTONIO, TX 78299	Grid #:	68-46-5
Well Location:	Calaveras Power Station SAN ANTONIO, TX	Latitude:	29° 19' 01" N
Well County:	Bexar	Longitude:	098° 18' 08" W
		Elevation:	495 ft. above sea level

Type of Work: New Well	Proposed Use: Monitor
-------------------------------	------------------------------

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	19
Drilling Method:	Hollow Stem Auger		
Borehole Completion:	Filter Packed		

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	7	17	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	2	7	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**
Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**
Distance to Septic Field or other concentrated contamination (ft.): **No Data**
Distance to Septic Tank (ft.): **No Data**
Method of Verification: **No Data**

Surface Completion: Surface Slab Installed	Surface Completion by Driller
---	--------------------------------------

Water Level: **No Data**
Packers: **No Data**
Type of Pump: **No Data**
Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	18	19

Water Quality:	<i>Strata Depth (ft.)</i> No Data	<i>Water Type</i> No Data	
----------------	---	-------------------------------------	--

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
112 S. Norwood Drive
Hurst, TX 76053

Driller Name: **Joseph Ray** License Number: **58794**

Comments: **No Data**

Lithology:
DESCRIPTION & COLOR OF FORMATION MATERIAL

Casing:
BLANK PIPE & WELL SCREEN DATA


<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>
0	5	ASH						
5	8	LT BRN CLAY	2	Riser	New Plastic (PVC)	40	0	7
8	14	LT GRAY CLAY	2	Screen	New Plastic (PVC)	40 10	7	17
14	19	LT GRAY SAND						

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-50
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-50 Date Drilled 2016-04-06
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 14.00' Boring Diam. 8.25"
 N. Coord. 13660122.87' E. Coord. 2186836.72' Surface Elevation 494.87' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 7.50' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 2.50' Sump Length 0'
 Top of Casing Elevation 498.20' Stickup 3.33'
 Depth to Water: 1. Ft. btoc 11.76 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
494.87	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			80		5-7.75	SILTY CLAY: Orangish brown heavily mottled with light grey, brown, and tan; damp; stiff; medium to high plasticity; increasing silt content with depth; orange silt stringers. At 6' bgs: Tan silt lens (2" thick).
485	10			25		7.75-8.25	At 7.5' bgs: Color change to brownish orange; minor fine-grained sand content.
						8.25-9.25	SAND: Tan; damp; fine-grained, sub-angular; moderately sorted; dense; non-plastic; minor silt content; occasional orange silt stringers.
						9.25-10	SILTY CLAY: Orangish brown mottled with grey, brown, red and occasional yellow; damp; stiff; medium plasticity; orange silt stringers throughout.
						10-13	SILT: Tan; moist; loose; non-plastic; trace orange silt stringers. At 9.75' bgs: Soft clay lens (3/16" thick).
							NO RECOVERY.
						13-13.75	SILTY CLAY: Brown; saturated; loose; low plasticity; orange silt stringers; sandstone pieces (3/8" thick) near 13.75' bgs.
480	15					13.75-14	SANDSTONE: Brownish orange laminated with orange, tan, and dark brown.
475	20						Refusal (bedrock) encountered at 14' bgs.

STATE OF TEXAS WELL REPORT for Tracking #424216

Owner:	CPS ENERGY	Owner Well #:	JKS-50
Address:	PO BOX 2906 SAN ANTONIO, TX 78299	Grid #:	68-46-5
Well Location:	Calaveras Power Station SAN ANTONIO, TX	Latitude:	29° 19' 01" N
Well County:	Bexar	Longitude:	098° 18' 08" W
		Elevation:	489 ft. above sea level

Type of Work: New Well	Proposed Use: Monitor
-------------------------------	------------------------------

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	14
Drilling Method:	Hollow Stem Auger		
Borehole Completion:	Filter Packed		
	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>
Filter Pack Intervals:	1.5	10	Sand
			20/40
	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0.5	1.5	Bentonite 1 Bags/Sacks
Seal Method:	Hand Mixed		
Sealed By:	Driller		
			Distance to Property Line (ft.): No Data
			Distance to Septic Field or other concentrated contamination (ft.): No Data
			Distance to Septic Tank (ft.): No Data
			Method of Verification: No Data
Surface Completion:	Surface Slab Installed		Surface Completion by Driller

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	10	14

Water Quality:	<i>Strata Depth (ft.)</i> No Data	<i>Water Type</i> No Data	Chemical Analysis Made: No
----------------	---	-------------------------------------	-----------------------------------

Did the driller knowingly penetrate any strata which contained injurious constituents?:	No
---	-----------

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
112 S. Norwood Drive
Hurst, TX 76053

Driller Name: **Joseph Ray** License Number: **58794**

Comments: **No Data**

<i>Lithology:</i>			<i>Casing:</i>						
DESCRIPTION & COLOR OF FORMATION MATERIAL			BLANK PIPE & WELL SCREEN DATA						
<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	
0	5	ASH							
5	8	LT BRN CLAY	2	Riser	New Plastic (PVC)	40	0	2.5	
8	14	LT GRAY CLAY	2	Screen	New Plastic (PVC)	40 10	2.5	10	
14	15	LT GRAY SAND							

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



Environmental Resources Management

JKS-50R
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-50R Date Drilled 2016-10-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 22.50' Boring Diam. 8.25"
 N. Coord. 13660149.90' E. Coord. 186841.92' Surface Elevation 494.96' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 9.50' Sump Length 0'
 Top of Casing Elevation 498.48' Stickup 3.52'
 Depth to Water: 1. Ft. btoc 12.67 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
494.96	0				No Samples Collected	0-15	See boring log JKS-50 from 4/6/16.
490	5			0			
485	10			0			
480	15			50		15-17.5	CLAYEY SAND: Light brown; wet; loose; trace dark gray sandy clay content; very coarse gravel (2" diam.) present.
475	20					17.5-22.5	CLAYEY SILTY SAND: Light brown; saturated; loose; light gray pieces of clay; few large (2" diam.) very coarse (2" diam.) angular rocks present.



JKS-50R DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-50R Date Drilled 2016-10-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 22.50' Boring Diam. 8.25"
 N. Coord. 13660149.90' E. Coord. 186841.92' Surface Elevation 494.96' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 9.50' Sump Length 0'
 Top of Casing Elevation 498.48' Stickup 3.52'
 Depth to Water: 1. Ft. btoc 12.67 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			50		22-22.5	CLAYEY SAND: Brownish gray; dry to damp; loose. Boring terminated at 22.5' bgs.
465	25						
460	30						
455	35						
455	40						

STATE OF TEXAS WELL REPORT for Tracking #443567

Owner: Calaveras Power Station	Owner Well #: JKS-50R
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
<hr/>	
Type of Work: New Well	Proposed Use: Monitor

Drilling Start Date: **10/7/2016** Drilling End Date: **10/7/2016**

	Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
Borehole:	8.25	0	19.5

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	Top Depth (ft.)	Bottom Depth (ft.)	Filter Material	Size
Filter Pack Intervals:	7.5	19.5	Sand	20/40

	Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	7.5	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

Water Quality: *Strata Depth (ft.)* *Water Type*
 No Data **No Data**

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents? **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
 112 S. Norwood Drive
 Hurst, TX 76053

Driller Name: **William Fields** License Number: **56033**

Apprentice Name: **Ryan Spaust**

Comments: **No Data**


<i>Lithology:</i>			<i>Casing:</i>						
DESCRIPTION & COLOR OF FORMATION MATERIAL			BLANK PIPE & WELL SCREEN DATA						
<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	
0	17.5	Clayey sand -light brown	2	Riser	New Plastic (PVC)	40	0	9.5	
17.5	19.5	Clayey silty sand - light brown	2	Screen	New Plastic (PVC)	40 10	9.5	19.5	

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-51
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-51 Date Drilled 2016-04-07
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 29.50' Boring Diam. 8.25"
 N. Coord. 13660243.53' E. Coord. 2185630.39' Surface Elevation 494.04' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 7.00' Sump Length 0'
 Top of Casing Elevation 496.92' Stickup 2.88'
 Depth to Water: 1. Ft. btoc 10.56 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
494.04	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			60		5-6.5	SILTY CLAY: Light brown with occasional orange mottling; wet; soft; low plasticity; occasional gravel (1/16" thick).
485	10			100		6.5-10	SAND: Light brown; very moist; fine-grained; sub-angular; moderately sorted; medium dense; slight plasticity; minor silt and clay content. At 7.5' bgs: Clay lenses (up to 3/4" thick) to 8.5' bgs. At 8.5' bgs: Occasional orange silt stringers to 9.5' bgs. At 9' bgs: Clay lamina (1/16" thick) to 10' bgs. At 9.5' bgs: Wet.
480	15			100		10-15	SILT: Light brown; wet; medium dense; low plasticity; laminated with grey clay (1/16" to 3/16" thick) throughout; minor fine-grained sand; orange silt stringers throughout. At 12.5' bgs: Sand lens (2" thick). At 13.5' bgs: Sand lens (2" thick); fractures in planar surfaces to 14.5' bgs. At 14' bgs: Occasional thin clay lamina to 15' bgs. At 14.5' bgs: Color change to light grey.
475	20					15-17.75	CLAY: Pinkish grey; moist; medium stiff; low to medium plasticity; laminated with orange and grey silt (up to 3/4" thick) throughout. CLAY: Grey; moist; medium stiff; low plasticity; trace silt content; abundant orange silt stringers.
						17.75-18.25	SILTY SAND: Light brown; wet to saturated; very fine to fine-grained; sub-angular; poorly sorted; loose; non-plastic.
						18.25-19.75	At 19.25' bgs: Pinkish grey clay lens (2" thick); thin red silt lens below clay; occasional orange silt stringers.
						19.75-26.5	SAND: Light grey; wet; fine-grained; sub-angular; moderately sorted; loose; non-plastic; occasional orange silt stringers.



ERM Environmental Resources Management

**JKS-51
DRILLING LOG**

Proj. No. 0337367 Boring/Well ID JKS-51 Date Drilled 2016-04-07
 Project Groundwater Investigation Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 29.50' Boring Diam. 8.25"
 N. Coord. 13660243.53' E. Coord. 2185630.39' Surface Elevation 494.04' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 7.00' Sump Length 0'
 Top of Casing Elevation 496.92' Stickup 2.88'
 Depth to Water: 1. Ft. btoc 10.56 (2016-05-31) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Joseph Ray
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			100	No Samples Collected		At 21.25' bgs: Red silt lens (1/16" thick); abundant orange silt stringers.
465	25			100		26.5-27.75	At 24' bgs: Minor silt and trace clay content. At 26.25' bgs: Reddish orange silt lens (1/16" thick). SANDY SILT: Tannish light grey; wet; loose; slight plasticity; occasional yellow and orange silt stringers.
460	30					27.75-28 28-29.5	At 27.5' bgs: Trace clay content. CLAY: Dark brown mottled with tannish brown; moist; stiff; very high plasticity (fat); brown silt stringers throughout. SAND: Tannish light grey; wet; fine-grained; sub-angular; moderately sorted; loose; non-plastic; trace silt, occurrence decreases with depth; abundant orange silt stringers. At 29.25' bgs: Color change to light brown; occasional orange silt stringers. Refusal (bedrock) encountered at 29.5' bgs.
455	35						
450	40						

STATE OF TEXAS WELL REPORT for Tracking #424218

Owner: CPS ENERGY Address: PO BOX 2906 SAN ANTONIO, TX 78299 Well Location: Calaveras Power Station SAN ANTONIO, TX Well County: Bexar	Owner Well #: JKS-51 Grid #: 68-46-5 Latitude: 29° 19' 01" N Longitude: 098° 18' 08" W Elevation: 491 ft. above sea level
Type of Work: New Well	
Proposed Use: Monitor	

Drilling Start Date: **4/4/2016** Drilling End Date: **4/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	29.5

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	5	23	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	2	5	Bentonite 3 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**


Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

	<i>Description (number of sacks & material)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Plug Information:	Bentonite	23	29.5



JKS-52
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-52 Date Drilled 2016-09-01
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 32.50' Boring Diam. 8.25"
 N. Coord. 13659683.26' E. Coord. 2186139.05' Surface Elevation 493.56' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 19.00' Sump Length 0'
 Top of Casing Elevation 493.15' Stickup -0.41'
 Depth to Water: 1. Ft. btoc 7.30 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
493.56	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			0		5-7	CLAYEY SILT: Orangish brown with red and light gray; damp; loose; slight plasticity; red nodules throughout. no odor. At 5' bgs: Red clay lense (1" thick). At 5.8' bgs: Light gray clay lensee.
				100		7-8	SILTY CLAY: Tan; damp.
485						8-10	CLAYEY SILT: Gray with light gray and tan streaks; damp.
	10					10-12	CLAY: Dark gray to brownish gray, mottled with light gray and bluish gray; damp; medium dense; slight plasticity.
				100		12-12.5	SILTY CLAY: Dark gray.
480						12.5-13.5	SAND: Tan with light brownish gray; damp; loose; layered with iron-oxide staining, (1/4" thick).
	15					13.5-15	CLAYEY SILT: Tan with light brownish gray; damp; medium dense; non-plastic.
				100		15-19	SAND: Tan with gray clay stringers; damp; loose.
475						19-20	SAND: Light tan; saturated; loose.
	20						



Environmental Resources Management

JKS-52
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-52 Date Drilled 2016-09-01
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 32.50' Boring Diam. 8.25"
 N. Coord. 13659683.26' E. Coord. 2186139.05' Surface Elevation 493.56' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 19.00' Sump Length 0'
 Top of Casing Elevation 493.15' Stickup -0.41'
 Depth to Water: 1. Ft. btoc 7.30 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20	[Graphic Log Pattern]	[Well Construction Pattern]	100		20-24	SAND: Light orange and tan; damp; medium dense; no odor. At 21' bgs: Color change to tan with gray striations. At 22' bgs: Color change to tan; damp; and loose; At 22.5' bgs: Two gray striations layered within iron-oxide staining.
465	25	[Graphic Log Pattern]	[Well Construction Pattern]	100		24-25 25-30	CLAYEY SAND: Tan; saturated; medium dense. INTERBEDDED CLAY AND SAND: Gray and tan; damp; loose. At 27.5' bgs: Intermittent pinkish gray coloration of clay content to 30' bgs.
460	30	[Graphic Log Pattern]	[Well Construction Pattern]	100		30-31 31-32.5	SAND: Gray; damp; loose. INTERBEDDED CLAY AND SAND: Orange with pinkish gray; damp; loose; medium plasticity. Boring terminated at 32.5' bgs.
455	35	[Graphic Log Pattern]	[Well Construction Pattern]				
450	40	[Graphic Log Pattern]	[Well Construction Pattern]				

STATE OF TEXAS WELL REPORT for Tracking #443571

Owner: Calaveras Power Station	Owner Well #: JKS-52
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
<hr/>	
Type of Work: New Well	Proposed Use: Monitor

Drilling Start Date: **9/1/2016** Drilling End Date: **9/1/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	29

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	7.5	19.5	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	17	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**




JKS-53
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-53 Date Drilled 2016-09-02
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.00' Boring Diam. 8.25"
 N. Coord. 13659757.34' E. Coord. 2185892.80' Surface Elevation 491.33' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 494.74' Stickup 3.41'
 Depth to Water: 1. Ft. btoc 8.50 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
491.33	0			0		0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490							
	5					5-7.5	SANDY SILTY CLAY: Tan to reddish gray; wet; low plasticity; no odor. At 6' bgs: Pockets of orange colored sand.
485				100		7.5-10	SANDY CLAY: Orangish brown and gray; moist; low plasticity. At 9' bgs: Pockets of orange colored sand.
	10				JKS-53_10-12.5 USCS: Clayey Sand (SC) AL: 30 / 14 / 16 - #200: 35.9 k: 5.34x10 ⁻⁶	10-15	NO RECOVERY Cohesive sample (Shelby tube) collected from 10'-12' bgs.
480				0	JKS-53_12.5-15 USCS: Clayey Sand (SC) AL: 29 / 15 / 14 - #200: 48.8 k: 4.13x10 ⁻⁸		Cohesive sample (Shelby tube) collected from 12.5'-15' bgs.
	15					15-16	CLAYEY SAND: Tan; wet; loose; non-plastic; no odor.
475				100		16-17.5	INTERBEDDED CLAY AND SAND: Orangish light brown sand interbedded with pinkish gray clay. At 16.5 - 17' bgs: Tan sand; damp.
						17.5-19.5	CLAYEY SAND: Light brown and tannish gray; saturated; loose; slight plasticity. At 18.5-19' bgs: Tan sand.
	20					19.5-20	INTERBEDDED CLAY AND SAND: Tan sand interbedded with pinkish gray clay; layered with iron-oxide staining; damp; loose.



JKS-53
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-53 Date Drilled 2016-09-02
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.00' Boring Diam. 8.25"
 N. Coord. 13659757.34' E. Coord. 2185892.80' Surface Elevation 491.33' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 494.74' Stickup 3.41'
 Depth to Water: 1. Ft. btoc 8.50 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			100	JKS-53_20-21 USCS: Clayey Sand (SC) AL: 27 / 14 / 13 - #200: 37.6	20-25	CLAYEY SAND: Gray with tannish orange staining; saturated; loose; non-plastic. Non-cohesive grab sample collected from 20'-21' bgs. At 22-22.5' bgs: Color change to orangish light brown; moist. At 22.5-25' bgs: Saturated.
465	25			100		25-27	SAND: Reddish brown mixed with light gray; damp; medium dense; non-plastic; dry and crumbly with depth. Boring terminated at 27' bgs.
460	30						
455	35						
450	40						

STATE OF TEXAS WELL REPORT for Tracking #443589

Owner: Calaveras Power Station	Owner Well #: JKS-53
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/2/2016** Drilling End Date: **9/2/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	25

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	17	25	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	17	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



JKS-54
DRILLING LOG


Proj. No. 0366643 Boring/Well ID JKS-54 Date Drilled 2016-09-02
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.50' Boring Diam. 8.25"
 N. Coord. 13659753.34' E. Coord. 2185641.96' Surface Elevation 492.69' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 496.40' Stickup 3.71'
 Depth to Water: 1. Ft. btoc 10.79 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
492.69	0					0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490				0			
	5					5-5.8	CLAYEY SILT: Orangish brown with red; damp; loose; non-plastic; no odor.
						5.8-7.2	At 5.8' bgs: White chalky material.
						7.2-8	CLAYEY SAND: Light brown to tan; damp.
485				100		8-11.5	INTERBEDDED CLAY AND SAND: Gray clay laminations (1" thick).
	10						CLAYEY SAND: Orangish brown; medium dense; non-plastic.
							At 10.8' bgs: Tan; saturated; and loose.
						11.5-12.5	INTERBEDDED CLAY AND SAND: Tan sand interbedded with light pinkish gray clay; damp; clay laminations are 1/4"-1/2" thick.
480				100	JKS-54_13-14 USCS: Silty Clayey Sand (SC-SM) AL: 22 / 15 / 7 - #200: 33.5	12.5-15	CLAYEY SAND: Tan; wet to saturated; loose; non-plastic. Non-cohesive grab sample collected from 13'-14' bgs. At 13.2-14.2' bgs: Saturated.
	15						At 14.9' bgs: Single thin (1" thick) clay layer.
						15-27.5	INTERBEDDED CLAY AND SAND: Tan fine grained sand and light pinkish gray clay; damp.
475				100			
	20						



JKS-54
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-54 Date Drilled 2016-09-02
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.50' Boring Diam. 8.25"
 N. Coord. 13659753.34' E. Coord. 2185641.96' Surface Elevation 492.69' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 496.40' Stickup 3.71'
 Depth to Water: 1. Ft. btoc 10.79 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20	[Graphic Log]	[Well Construction]	100			
465	25	[Graphic Log]	[Well Construction]	100			At 25-28' bgs: Iron-oxide stained layers between sand and clay; clay content has slight to low plasticity; clay layers are 1/2" thick.
460	30	[Graphic Log]	[Well Construction]				Refusal encountered at 28' bgs.
455	35	[Graphic Log]	[Well Construction]				
440	40	[Graphic Log]	[Well Construction]				

STATE OF TEXAS WELL REPORT for Tracking #443590

Owner: Calaveras Power Station	Owner Well #: JKS-54
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/2/2016** Drilling End Date: **9/2/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	22

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	10	22	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	10	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



JKS-55
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-55 Date Drilled 2016-09-06
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 25.00' Boring Diam. 8.25"
 N. Coord. 13659749.76' E. Coord. 2186840.46' Surface Elevation 490.13' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 493.81' Stickup 3.68'
 Depth to Water: 1. Ft. btoc 8.36 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
490.13	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
485	5			0		5-11.5	NO RECOVERY: Moderately to highly cemented sand.
480	10			0		11.5-12.5	NO RECOVERY: Cuttings are saturated; clayey silt material.
				0		12.5-13.5	SANDY CLAY: Dark olive gray; damp; soft; non-plastic.
475	15			100		13.5-18.5	CLAYEY SAND: Tannish gray with trace iron-oxide staining; damp; loose; non-plastic. At 15' bgs: White chalky material (1" thick); wet. At 15.5-17.5' bgs: Clayey sand mixed with some gravel. At 16.5' bgs: White chalky layer (1/2" thick). At 17.5' bgs: White chalky layer (1/2" thick). At 17.5-18.5' bgs: Saturated; tan clayey sand with trace gravel.
						18.5-19.8	SAND: Gray; wet; fine grained.
	20					19.8-20	SAND: Gray; very dense; moderately to highly cemented.



JKS-55
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-55 Date Drilled 2016-09-06
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 25.00' Boring Diam. 8.25"
 N. Coord. 13659749.76' E. Coord. 2186840.46' Surface Elevation 490.13' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 493.81' Stickup 3.68'
 Depth to Water: 1. Ft. btoc 8.36 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			100		20-21	SANDY CLAY: Gray; damp; soft; slight plasticity.
					21-22.5	INTERBEDDED CLAY AND SAND: Fine grained tan sand interbedded with pinkish gray clay; damp.	
					22.5-23.5	CLAYEY SAND: Tan; trace gravel; one large piece of sandstone (>1" thick).	
					23.5-25	SAND: Pinkish gray; fine grained; damp; very thin layers of iron-oxide staining.	
465	25					Boring terminated at 25' bgs.	
460	30						
455	35						
40							

STATE OF TEXAS WELL REPORT for Tracking #443591

Owner: Calaveras Power Station	Owner Well #: JKS-55
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/6/2016** Drilling End Date: **9/6/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	25

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	12	25	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	12	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



JKS-56
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-56 Date Drilled 2016-09-06
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 25.00' Boring Diam. 8.25"
 N. Coord. 13660382.47' E. Coord. 2186847.61' Surface Elevation 493.07' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Sump Length 0'
 Top of Casing Elevation 496.66' Stickup 3.59'
 Depth to Water: 1. Ft. btoc 11.20 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP



NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
493.07	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5			0		5-5.5 5.5-7	SANDY CLAY: Reddish gray; damp; stiff; non-plastic. At 5.5' bgs: Gray sandstone piece (>1" thick). SAND: Light orangish brown; fine grained; damp; loose.
485	7.5			100	0	7-7.5 7.5-9.5	At 6.25' bgs: Color changes to tannish gray with some orangish brown. SANDY CLAY: Orange; damp; stiff to very stiff; non-plastic. CLAYEY SILT: Orangish tan; saturated; loose; non-plastic; mixed with some gravel and trace pockets of gray, fine grained sand.
480	10			15		9.5-10 10-13	CLAYEY SILTY SAND: Orangish tan; saturated; loose; non-plastic. NO RECOVERY
475	15			50		13-22.5	CLAYEY SAND: Tan; fine grained; saturated; loose; non-plastic. At 15' bgs: Small pocket of gray, fine grained, loose sand (1" thick). At 16' bgs: Coarse, angular gravel layer (~1-2" thick)
	20						



Environmental Resources Management

JKS-56
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-56 Date Drilled 2016-09-06
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 25.00' Boring Diam. 8.25"
 N. Coord. 13660382.47' E. Coord. 2186847.61' Surface Elevation 493.07' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Sump Length 0'
 Top of Casing Elevation 496.66' Stickup 3.59'
 Depth to Water: 1. Ft. btoc 11.20 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			50		22.5-24.9	SAND: Brownish gray; fine grained; saturated; trace clay content.
465	25					24.9-25	SANDY CLAY: Reddish brown; saturated; very soft. Boring terminated at 25' bgs.

STATE OF TEXAS WELL REPORT for Tracking #443592

Owner: Calaveras Power Station	Owner Well #: JKS-56
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/6/2016** Drilling End Date: **9/6/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	25

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	8	25	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	8	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



JKS-57
DRILLING LOG


Proj. No. 0366643 Boring/Well ID JKS-57 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.50' Boring Diam. 0.00"
 N. Coord. 13668235.72' E. Coord. 2187486.38' Surface Elevation 503.83' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 506.91' Stickup 3.08'
 Depth to Water: 1. Ft. btoc 20.07 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES


Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
503.83	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
500	5			100		5-8	CLAYEY SILT: Dark brown; damp; loose to medium dense; very slight plasticity; rootlets present.
495	10			100		8-12.2	CLAYEY SAND: Orangish brown with trace gray and iron-oxide staining; damp; loose to medium dense; slight plasticity; rootlets present. At 10' bgs: Color becomes grayish tan mottled with yellow iron-oxide staining.
490	15			100		12.2-14	SANDSTONE: Magenta red with orangish yellow and gray; damp; several pieces of reddish brown nodules (>1" thick) surrounded by yellow sandy clay.
485	20			100		14-15	SANDY CLAY: Orangish yellow and gray; damp; slight plasticity; gray and orangish yellow striations of sandy clay; white crystalline structures with medium grained sand throughout.
						15-25	INTERBEDDED CLAY AND SAND: Gray with yellow and iron-oxide staining; dry; soft; medium plasticity. At 15-16' bgs: Mostly sand and iron-oxide staining. At 16-17.5' bgs: Mostly gray clay. At 17.5-18.5' bgs: Mostly sand with some yellow and trace iron-oxide staining. At 18.5-20' bgs: Mostly sand with some iron-oxide staining.



JKS-57
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-57 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.50' Boring Diam. 0.00"
 N. Coord. 13668235.72' E. Coord. 2187486.38' Surface Elevation 503.83' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 506.91' Stickup 3.08'
 Depth to Water: 1. Ft. btoc 20.07 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204.
 Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
480	20	[Graphic Log]	[Well Construction]	100			At 20-21' bgs: Mostly sand with yellow and trace iron-oxide staining. At 21-21.5' bgs: 2" thick layer of reddish brown, hard-packed sand; 4" thick layer of tan, very fine grained, loose sand. At 21.5-25' bgs: Mostly dark gray clay; At 22.5' bgs: Reddish brown coloration;
475	25	[Graphic Log]	[Well Construction]	100		25-25.5 25.5-27	At 24-25' bgs: Color is brownish gray with redox stippling. SAND: Gray; fine grained; dry; medium dense; low plasticity. At 25.5' bgs: Very thin (1/8" thick) brownish red coloration. INTERBEDDED CLAY AND SAND: Brownish gray clay interbedded with fine grained sand; dense; hard-packed.
470	30	[Graphic Log]	[Well Construction]			27-27.5	At 26.6' bgs: Thin, tan, dry, very fine grained, sand. SAND: Highly cemented; reddish brown nodules present. Refusal encountered at 27.5' bgs.
465	35	[Graphic Log]	[Well Construction]				
460	40	[Graphic Log]	[Well Construction]				

STATE OF TEXAS WELL REPORT for Tracking #443593

Owner: Calaveras Power Station	Owner Well #: JKS-57
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/7/2016** Drilling End Date: **9/7/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	27

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	10	27	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	10	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**


Well Tests: **No Test Data Specified**



ERM Environmental Resources Management


JKS-58
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-58 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 32.00' Boring Diam. 8.25"
 N. Coord. 13667994.99' E. Coord. 2187797.39' Surface Elevation 500.94' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Sump Length 0'
 Top of Casing Elevation 504.45' Stickup 3.51'
 Depth to Water: 1. Ft. btoc 21.09 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry




NOTES
 Coordinates in Texas South Central State Plane 4204.
 Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
500.94	0					0-5	NO RECOVERY: Previously excavated by hydrovac truck.
500				0			
	5					5-6	SAND: Brown; fine grained; moist; very loose.
495						6-7	CLAYEY SAND: Grayish brown with red; fine grained; damp; loose; non-plastic.
				100		7-10	SAND: Red, orange, and gray; damp medium grained; very loose to medium dense; slight gray, soft to medium dense, sandy clay; (clay content increases with depth).
	10					10-17	At 9.8' bgs: Color change to dark gray. At 10' bgs: Hard, sandstone, iron ore piece (>1" thick). SILTY CLAY: Gray with alternating yellow and orange layers; dry; dense; slight plasticity.
490							At 12.2' bgs: Brown sand seam (3" thick).
	15						At 16-16.5' bgs: Brownish tan sandy clay. At 16.5-17' bgs: Gray clay has fractured texture.
485						17-17.5	CLAY: Gray; damp; mixed with coarse grained sand.
				100		17.5-19.5	SAND: Tan; moist to wet. At 18-19.5' bgs: Color change to gray with black staining; no odor; white, crystalline, coarse grained structures present.
	20					19.5-20	CLAYEY SILTY SAND: Orangish brown; dry; gravel and some small sandstone pieces present.



JKS-58
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-58 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 32.00' Boring Diam. 8.25"
 N. Coord. 13667994.99' E. Coord. 2187797.39' Surface Elevation 500.94' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Sump Length 0'
 Top of Casing Elevation 504.45' Stickup 3.51'
 Depth to Water: 1. Ft. btoc 21.09 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204.
 Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
480	20			100		20-21	CLAY: Gray; dry; stiff; small, tan sandy clay pockets present.
						21-22.5	INTERBEDDED CLAY AND SAND: Gray and orangish tan; damp; clay is pinkish gray interbedded with thin orange sand layers.
						22.5-25.5	CLAY: Dark pinkish gray; dry; stiff; several very thin, light gray, silty sand layers. At 24.5-24.7' bgs: Tan, dry, silty clay.
475	25			100	JKS-58_26-27 USCS: Sandy Lean Clay (CL) AL: 38 / 18 / 20 - #200: 50.9	25.5-30	CLAYEY SAND: Tan; moist to saturated. At 25.5-27.5' bgs: No distinct layers. Non-cohesive grab sample collected from 26'-27' bgs. At 27.5' bgs: Thin saturated seam. At 27.5-30' bgs: Yellow and orange layering.
470	30				JKS-58_30-32.5 USCS: Fat Clay (CH) AL: 57 / 20 / 37 - #200: 89.1 k: 1.53x10 ⁻⁷	30-32.5	NO RECOVERY: Cohesive sample (Shelby tune) collected from 30'-32' bgs. Boring terminated at 32.5' bgs.
465	35						
40							

STATE OF TEXAS WELL REPORT for Tracking #443594

Owner: Calaveras Power Station	Owner Well #: JKS-58
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/7/2016** Drilling End Date: **9/7/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	30

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	18	30	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	18	Bentonite 4 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



ERM Environmental Resources Management

**JKS-59
DRILLING LOG**


Proj. No. 0366643 Boring/Well ID JKS-59 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.00' Boring Diam. 8.25"
 N. Coord. 13667779.88' E. Coord. 2188352.07' Surface Elevation 493.53' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 496.45' Stickup 2.92'
 Depth to Water: 1. Ft. btoc 15.49 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
493.53	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
490	5					5-6.5	SILTY SAND: Brown; damp; loose.
						6.5-7	SAND: Tan; damp; loose.
				100		7-10	SILTY CLAY: Dark brown; damp; soft; slight plasticity.
485	10					10-11	At 9-10' bgs: Decreasing silt content; increasing stiffness; some iron-oxide stained nodules observed. CLAY: Dark brown; damp; medium stiff; low to medium plasticity.
				100		11-15	SILTY CLAY: Dark orangish brown to orangish brown; damp; soft; increasing silt content with depth; increasing gray streaks/fissures with depth.
480	15					15-15.5	CLAY: Dark brown to brown; damp; medium stiff to stiff; low plasticity.
				100		15.5-18	SILTY SAND: Tan; saturated; loose. At 16' bgs: Wet; crumbly; trace clay content.
475	20					18-20	At 17.5' bgs: Saturated. SANDY CLAY: Light bluish gray mottled with orange iron-oxide and black staining; moist; medium stiff; slight plasticity.



JKS-59
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-59 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 27.00' Boring Diam. 8.25"
 N. Coord. 13667779.88' E. Coord. 2188352.07' Surface Elevation 493.53' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 12.00' Sump Length 0'
 Top of Casing Elevation 496.45' Stickup 2.92'
 Depth to Water: 1. Ft. btoc 15.49 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20			100		20-20.5	CLAY: Brown to light brown; damp; medium stiff to stiff; low plasticity. SANDY CLAY: Light gray mottled with orangish iron-oxide staining; moist; medium stiff; slight plasticity. CLAY: Dark pinkish gray; moist; soft; layered with very thin orange/iron-oxide stained silty sand. SILT: Tan; saturated; very loose. CLAY: Dark pinkish gray; soft; layered with very thin orange/iron-oxide stained silty sand. SAND: Gray with orange staining; fine grained; saturated; loose. CLAY: Gray; saturated; very soft; high plasticity. Boring terminated at 27' bgs.
						20.5-21	
						21-22.5	
						22.5-22.8	
						22.8-25	
	25					100	
465	30						
460	35						
455	40						

STATE OF TEXAS WELL REPORT for Tracking #443595

Owner: Calaveras Power Station	Owner Well #: JKS-59
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/7/2016** Drilling End Date: **9/7/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	27

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	10	27	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	10	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



ERM Environmental Resources Management

**JKS-60
DRILLING LOG**

Proj. No. 0366643 Boring/Well ID JKS-60 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 26.00' Boring Diam. 8.25"
 N. Coord. 13667357.02 E. Coord. 2188465.44 Surface Elevation 492.68' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Sump Length 0'
 Top of Casing Elevation 495.70' Stickup 3.02'
 Depth to Water: 1. Ft. btoc 17.40 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204.
Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
492.68	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated with hydrovac truck.
490	5			0		5-10	SAND: Grayish tan with orange and yellow; very fine grained; damp; loose; no odor. At 6' bgs: Color change to light pinkish orange. At 7.5' bgs: Color change to light gray with trace orange and yellow.
485	10			100		10-10.8	CLAY: Dark gray; moist; soft; slight plasticity.
480	10.8-16			100		10.8-16	SAND: White with yellow; very fine grained; damp; loose. At 11.6-13' bgs: Color change to pale yellow. At 13-16' bgs: Color change to light orangish yellow.
475	15			100		16-23.5	At 15' bgs: Thin reddish orange stringer. At 15-16' bgs: Moist. SAND: Light orange; very fine grained; damp; very dense; unable to collect soil core, soil descriptions based on observation of auger cuttings. At 18-23.5' bgs: Color change to pale yellow.
470	20			0			



ERM Environmental Resources Management

JKS-60
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-60 Date Drilled 2016-09-07
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 26.00' Boring Diam. 8.25"
 N. Coord. 13667357.02 E. Coord. 2188465.44 Surface Elevation 492.68' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Sump Length 0'
 Top of Casing Elevation 495.70' Stickup 3.02'
 Depth to Water: 1. Ft. btoc 17.40 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
470	20	[Graphic Log: Dotted pattern]	[Well Construction: Vertical line]	0		23.5-25.7	At 22' bgs: Moisture content increases to wet. SAND: Tan; fine grained; saturated; loose.
465	25	[Graphic Log: Dotted pattern]	[Well Construction: Vertical line]	100		25.7-25.9 25.9-26	At 25.5' bgs: Color change to white with brown; medium grained. SILTY SAND: Dark reddish staining; saturated. CLAY-SHALE: Shaley clay; tan; wet; dense; non-plastic. Boring terminated at 26' bgs.
460	30	[Graphic Log: Dotted pattern]	[Well Construction: Vertical line]				
455	35	[Graphic Log: Dotted pattern]	[Well Construction: Vertical line]				
450	40	[Graphic Log: Dotted pattern]	[Well Construction: Vertical line]				

STATE OF TEXAS WELL REPORT for Tracking #443596

Owner: Calaveras Power Station	Owner Well #: JKS-60
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/7/2016** Drilling End Date: **9/7/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	25

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	8	25	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	8	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

Water Quality: *Strata Depth (ft.)* *Water Type*
No Data **No Data**

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which
contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
112 S. Norwood Drive
Hurst, TX 76053

Driller Name: **William Fields** License Number: **56033**

Apprentice Name: **Ryan Spaust**

Comments: **No Data**

Lithology:
DESCRIPTION & COLOR OF FORMATION MATERIAL

Casing:
BLANK PIPE & WELL SCREEN DATA


<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>
0	7	Clayey silt - orangish brown	2	Riser	New Plastic (PVC)	40	0	10
7	15	Clayey silty - gray to brown	2	Screen	New Plastic (PVC)	40 10	10	25
15	19	Sand - tan with gray						
19	23	Sand - light orange and tan						
23	25	Sand - reddish brown						

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-61
DRILLING LOG**

Proj. No. 0366643 Boring/Well ID JKS-61 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 35.00' Boring Diam. 8.25"
 N. Coord. 13665721.04' E. Coord. 2187196.65' Surface Elevation 502.52' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 18.00' Sump Length 0'
 Top of Casing Elevation 505.51' Stickup 2.99'
 Depth to Water: 1. Ft. btoc 24.46 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
502.52	0				No Samples Collected	0-5	NO RECOVERY: Previously excavated with hydrovac truck.
500	5			0		5-5.2 5.2-10.5	SANDY SILT: Dark brown; damp; loose; contains rootlets. SAND: Light tannish orange; damp; fine grained; loose.
495	10			100		10.5-12.5	INTERBEDDED CLAY AND SAND: Light gray to white; very fine grained; very hard packed; very thin (1/10") pinkish gray clay stringers throughout.
490	15			100		12.5-20	At 10.5' bgs: Pinkish gray clay layer (1" thick). SAND: Light gray to white with trace yellow and orange colorations; dry; very fine grained; very hard packed. At 12.5-15' bgs: Sand is cemented.
485	20			100			At 16.5-19' bgs: Three clay stringers (1/4" thick).



Environmental Resources Management

JKS-61
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-61 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 35.00' Boring Diam. 8.25"
 N. Coord. 13665721.04' E. Coord. 2187196.65' Surface Elevation 502.52' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 18.00' Sump Length 0'
 Top of Casing Elevation 505.51' Stickup 2.99'
 Depth to Water: 1. Ft. btoc 24.46 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
480	20	[Hatched pattern]	[Dotted pattern]	100		20-22.5	CLAYEY SAND: Gray with trace orange; damp; fine grained; loose; trace clay content present. At 21' bgs: Color change to tan with orange and gray; moisture content becomes wet. At 21.8' bgs: Thin pinkish gray clay seam (1/4" thick).
475	25	[Hatched pattern]	[Dotted pattern]	100		22.5-25	SAND: Gray with orange, tan, and yellow; fine grained; wet; loose.
470	30	[Hatched pattern]	[Dotted pattern]	100		25-31.5	CLAYEY SAND: Gray; fine grained; wet to saturated; loose. At 25-25.8' bgs: Saturated. At 27.5-28.5' bgs: Saturated. At 30-31' bgs: Saturated. At 31-32.5' bgs: Wet.
465	35	[Hatched pattern]	[Dotted pattern]			31.5-32.5	SANDY CLAY: Pinkish gray; damp; medium dense; non-plastic to plastic; very thin sand stringers throughout (1/10" thick).
460						32.5-33	CLAYEY SILTY SAND: Gray; saturated; loose.
455						33-35	SANDY CLAY: Pinkish gray; damp; medium dense; slightly plastic; very thin sand stringers throughout (1/10" thick).
450							Boring terminated at 35' bgs.

STATE OF TEXAS WELL REPORT for Tracking #443597

Owner: Calaveras Power Station	Owner Well #: JKS-61
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/8/2016** Drilling End Date: **9/8/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	33

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	15	33	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	15	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

Water Quality: *Strata Depth (ft.)* *Water Type*
 No Data **No Data**

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

The driller did certify that while drilling, deepening or otherwise altering the above described well, injurious water or constituents was encountered and the landowner or person having the well drilled was informed that such well must be completed or plugged in such a manner as to avoid injury or pollution.

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Strata Core Services, LLC**
 112 S. Norwood Drive
 Hurst, TX 76053

Driller Name: **William Fields** License Number: **56033**

Apprentice Name: **Ryan Spaust**

Comments: **No Data**


<i>Lithology:</i>			<i>Casing:</i>						
<i>DESCRIPTION & COLOR OF FORMATION MATERIAL</i>			<i>BLANK PIPE & WELL SCREEN DATA</i>						
<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>	<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	
0	7	Clayey silt - orangish brown	2	Riser	New Plastic (PVC)	40	0	18	
7	15	Clayey silty - gray to brown	2	Screen	New Plastic (PVC)	40 10	18	33	
15	19	Sand - tan with gray							
19	23	Sand - light orange and tan							
23	33	Sand - reddish brown							

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 463-7880



ERM Environmental Resources Management

**JKS-62
DRILLING LOG**

Proj. No. 0366643 Boring/Well ID JKS-62 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 37.00' Boring Diam. 8.25"
 N. Coord. 13666020.13' E. Coord. 2187153.88' Surface Elevation 506.71' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Sump Length 0'
 Top of Casing Elevation 509.84' Stickup 3.13'
 Depth to Water: 1. Ft. btoc 28.90 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.


Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
506.71	0					0-5	NO RECOVERY: Previously excavated with hydrovac truck.
505				0		5-6	SANDY SILT: Dark brown; damp; very loose; slight to low plasticity; trace rootlets.
500				100		6-9	INTERBEDDED CLAY AND SAND: Light gray; dry; sand content fine grained, loose; clay content is pinkish gray with slight to low plasticity.
495				100		9-15	CLAYEY SAND: Light gray with yellowish orange and pale yellow; very fine grained; dry; trace clay content. At 10' bgs: Color change to light pinkish brown and yellowish orange; moisture content increases to damp; sand is loose; clay is soft and non-plastic. At 11' bgs: Color change to white/light gray and tan, clay is darker gray; moisture content decreases to dry; very dense; crumbles easily.
490				50		15-20	SAND: White; dry; dense but crumbles easily.
20	20						



ERM Environmental Resources Management

JKS-62 DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-62 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 37.00' Boring Diam. 8.25"
 N. Coord. 13666020.13' E. Coord. 2187153.88' Surface Elevation 506.71' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 10.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Sump Length 0'
 Top of Casing Elevation 509.84' Stickup 3.13'
 Depth to Water: 1. Ft. btoc 28.90 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry



NOTES
 Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
485	20	[Dotted pattern]	[Dotted pattern]	50		20-25	SAND: Light gray to tannish gray; fine grained; dry to damp; loose. At 21.2' bgs: Moisture content increases to damp. At 21.4' bgs: Yellow and iron-oxide staining.
480	25	[Horizontal lines]	[Horizontal lines]	100		25-27.5	INTERBEDDED CLAY AND SAND: Gray; fine grained; wet; loose. At 25.5' bgs: Iron-oxide staining and thin (1/4" thick) pinkish gray clay layer. At 27.5' bgs: Iron-oxide staining and thin (1/4" thick) pinkish gray clay layer.
475	30	[Diagonal lines]	[Diagonal lines]	0		27.5-29.5	CLAYEY SAND: Gray with iron-oxide staining; saturated; loose; trace clay content. At 29' bgs: Increased iron-oxide staining with clay layers.
470	35	[Cross-hatch]	[Cross-hatch]	0	JKS-62_35-37 USCS: Clayey Sand (SC) AL: 38 / 17 / 21 #200: 32.3 k: 6.63x10 ⁻⁷	29.5-30	INTERBEDDED CLAY AND SAND: Pinkish gray; damp; medium dense; slight plasticity.
						30-30.5	SAND: Gray; fine grained; damp.
						30.5-31	INTERBEDDED CLAY AND SAND: Orange, fine grained, moist sand; gray, low plasticity clay; loose to medium dense.
						31-31.5	CLAY: Brown; moist; loose to medium dense; non plastic.
						31.5-35	At 31.5 bgs: Thin reddish brown nodule layer (1/4" thick). CLAY: Brown; damp; soft; high plasticity; unable to collect soil core; descriptions based on observation of auger cuttings.
						35-37	NO RECOVERY: Cohesive sample (Shelby tube) collected from 35'-37' bgs. Boring terminated at 35' bgs.

STATE OF TEXAS WELL REPORT for Tracking #443598

Owner: Calaveras Power Station	Owner Well #: JKS-62
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well	
Proposed Use: Monitor	

Drilling Start Date: **9/8/2016** Drilling End Date: **9/8/2016**

	Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
Borehole:	8.25	0	30

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	Top Depth (ft.)	Bottom Depth (ft.)	Filter Material	Size
Filter Pack Intervals:	18	30	Sand	20/40

	Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	18	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**



JKS-63
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-63 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 50.00' Boring Diam. 8.25"
 N. Coord. 13666230.86' E. Coord. 2186553.38' Surface Elevation 523.55' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 30.00' Sump Length 0'
 Top of Casing Elevation 526.86' Stickup 3.31'
 Depth to Water: 1. Ft. btoc 44.70 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
523.55	0			0	No Samples Collected	0-5	NO RECOVERY: Previously excavated by hydrovac truck.
520	5			100		5-5.5 5.5-6 6-7.8	SAND: Brown; fine-grained; moist; loose. CLAYEY SAND: Tan; moist; single piece of gray, non-plastic clay. SILTY SAND: Brown lense; fine grained; moist; loose; trace rootlets.
515	10			100		7.8-10.2	SANDY CLAY: Reddish brown to dark gray with red; dry to damp; very stiff; hard-packed; non-plastic.
510	15			100		10.2-12.2	CLAYEY SAND: Orange to pinkish orange; dry to damp; very dense; non-plastic.
505	20			75		12.2-18	INTERBEDDED CLAY AND SAND: Tan; very fine-grained; very dense/hard-packed; layered with thin gray sandy clay seams. At 15' bgs: Sand color changes to very light gray to white; pinkish gray sandy clay seams throughout; layered with pale yellow colorations.
						18-20	SAND: Gray to brownish orange; dry; very fine-grained; medium dense; crumbles easily.



ERM Environmental Resources Management

**JKS-63
DRILLING LOG**


Proj. No. 0366643 Boring/Well ID JKS-63 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 50.00' Boring Diam. 8.25"
 N. Coord. 13666230.86' E. Coord. 2186553.38' Surface Elevation 523.55' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 30.00' Sump Length 0'
 Top of Casing Elevation 526.86' Stickup 3.31'
 Depth to Water: 1. Ft. btoc 44.70 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
500	20	[Graphic Log]	[Well Construction]	80		20-30	INTERBEDDED CLAY AND SAND: Light gray; very fine-grained; dry to damp; dense/hard-packed; layered with thin pinkish gray clay seams and iron-oxide staining.
495	25	[Graphic Log]	[Well Construction]	80		30-39	SAND: Gray; dry to saturated; fine-grained; very hard packed; crumbles easily. At 32.5' bgs: Medium-grained.
490	35	[Graphic Log]	[Well Construction]	80		39-39.5 39.5-50	CLAYEY SAND: Dark reddish brown; wet; loose. SAND: Gray; wet; fine-grained; loose.



ERM Environmental Resources Management

**JKS-63
DRILLING LOG**

Proj. No. 0366643 Boring/Well ID JKS-63 Date Drilled 2016-09-08
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras Power Station - San Antonio Boring T.D. 50.00' Boring Diam. 8.25"
 N. Coord. 13666230.86' E. Coord. 2186553.38' Surface Elevation 523.55' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 20.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 30.00' Sump Length 0'
 Top of Casing Elevation 526.86' Stickup 3.31'
 Depth to Water: 1. Ft. btoc 44.70 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
40							
480				80			
45							At 45' bgs: Moisture content increases to saturated; trace iron-oxide staining.
475				80			
50							Boring terminated at 50' bgs.
470							
55							
465							
60							

STATE OF TEXAS WELL REPORT for Tracking #443599

Owner: Calaveras Power Station	Owner Well #: JKS-63
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
Type of Work: New Well Proposed Use: Monitor	

Drilling Start Date: **9/8/2016** Drilling End Date: **9/8/2016**

	Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
Borehole:	8.25	0	50

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	Top Depth (ft.)	Bottom Depth (ft.)	Filter Material	Size
Filter Pack Intervals:	28	50	Sand	20/40

	Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	28	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**


Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**




JKS-63R
DRILLING LOG

Proj. No. 0503422 Boring/Well ID JKS-63R Date Drilled 2019-05-02
 Project Calaveras Power Station - Well Re-Install Owner CPS Energy
 Location Calaveras Power Station Boring T.D. 24.00' Boring Diam. 8.25"
 N. Coord. NA E. Coord. NA Surface Elevation 0.00' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 35.00' Sump Length 0'
 Top of Casing Elevation 0.00' Stickup 3.50'
 Depth to Water: 1. Ft. 36.00 (SB Installation) 2. Ft. 0.00 ()
 Drilling Company Vortex Drilling Partners, LP Driller James Neal
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP
NOTES

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
0.00	0			100	No Samples Collected	0-3.5	SAND: Brown; dry to damp; very-fine grained; sub-angular; poorly sorted; loose; minor silt and trace clay content; no odor. Ground surface to 5 ft. bgs logged via post hole digger soil cuttings.
-5	5			100		3.5-7.5	SAND □ CLA □: Brown with occasional red and black mottling; damp; medium stiff; low plasticity; trace silt content; no odor. At 4' bgs: Color change to reddish brown. At 5' bgs: Stiff; medium plasticity. At 6' bgs: Occasional thin, light brown, very-fine grained sand seams. At 6.5' bgs: Interbedded clay and sand seam (6" thick); dry; clay content dark brown, stiff; sand content very-fine grained, sub-angular; occasional light brown and yellow silt stringers.
-10	10			90		7.5-8.5	CLA □ E □ SAND: Reddish brown; damp; medium dense; non-plastic to slightly plastic; very-fine grained; sub-angular; minor yellow silt stringers; no odor.
-10	10			100		8.5-10	SILT: Light grey; dry; loose to medium dense; non-plastic; minor to occasional very-fine grained sand content, with increasing sand content with depth; minor yellow silt stringers; no odor.
-10	10			100		10-17.5	SAND: Light grey; dry; loose to medium dense; very-fine grained; sub-angular; poorly to moderately sorted; trace clay content; occasional yellow silt stringers; no odor. At 12.5' bgs: Medium dense.
-15	15			100		17.5-24	INTERBEDDED CLA □ AND SAND: Light grey (sand content) and light brown (clay content); dry to damp; clay content medium stiff, slight to low plasticity; sand content medium dense, very-fine grained, sub-angular; occasional yellow silt stringers; no odor. At 19' bgs: Decreasing clay content; sand content fine grained.
-20	20			100			




JKS-63R
DRILLING LOG

Proj. No. 0503422 Boring/Well ID JKS-63R Date Drilled 2019-05-02
 Project Calaveras Power Station - Well Re-Install Owner CPS Energy
 Location Calaveras Power Station Boring T.D. 24.00' Boring Diam. 8.00"
 N. Coord. NA E. Coord. NA Surface Elevation 0.00' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 35.00' Sump Length 0'
 Top of Casing Elevation 0.00' Stickup 3.50'
 Depth to Water: 1. Ft. 36.00 (SB Installation) 2. Ft. 0.00 ()
 Drilling Company Vortex Drilling Partners, LP Driller James Neal
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP
NOTES

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
-20	20			100	No Samples Collected	24-50	<p>At 22' bgs: Sand seam (3" thick); light grey; fine grained; no clay content.</p> <p>At 22.5' bgs: Increasing clay content; medium stiff to stiff.</p> <p>SAND: Light brownish grey; damp; medium dense to loose; fine grained; sub-angular; poorly sorted; minor yellow silt stringers; no odor.</p> <p>At 25' bgs: Trace red silty clay content; medium plasticity.</p> <p>At 27.5' bgs: No clay content.</p> <p>At 30' bgs: Minor clay content to 31' bgs.</p> <p>At 31.5' bgs: Moist.</p> <p>At 32' bgs: Occasional to abundant yellow and orange silt stringers.</p> <p>At 32.5' bgs: Very moist; minor to occasional yellow and orange silt stringers.</p> <p>At 35' bgs: Fine to very-fine grained; trace yellow and orange silt stringers.</p> <p>At 36' bgs: Wet.</p> <p>At 37.5' bgs: Saturated; fine grained; no clay content.</p>
-25	25			100			
-30	30			60			
-35	35			100			
-40	40			80			
				60			



JKS-63R
DRILLING LOG

Proj. No. 0503422 Boring/Well ID JKS-63R Date Drilled 2019-05-02
 Project Calaveras Power Station - Well Re-Install Owner CPS Energy
 Location Calaveras Power Station Boring T.D. 24.00' Boring Diam. 8.00"
 N. Coord. NA E. Coord. NA Surface Elevation 0.00' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 35.00' Sump Length 0'
 Top of Casing Elevation 0.00' Stickup 3.50'
 Depth to Water: 1. Ft. 36.00 (SB Installation) 2. Ft. 0.00 ()
 Drilling Company Vortex Drilling Partners, LP Driller James Neal
 Drilling Method Hollow-Stem Auger Log By Nick Houtchens

SKETCH MAP
NOTES

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
-40	40			80	No Samples Collected		At 40' bgs: Abundant orange silt stringers.
				80			At 42.5' bgs: Fine to medium grained; occasional orange silt stringers.
-45	45			60			At 45' bgs: Fine grained;
				60			At 47.5' bgs: Trace orange silt stringers.
-50	50						Boring terminated at 50' bgs.
-55	55						
-60	60						

STATE OF TEXAS WELL REPORT for Tracking #511515

Owner: CPS Energy	Owner Well #: JKS-63R
Address: P.O. Box 2906 San Antonio , TX 78299	Grid #: 68-46-5
Well Location: Calaveras Power Station 12940 US 181 San Antonio, TX 78263	Latitude: 29° 19' 27.98" N
	Longitude: 098° 18' 56.77" W
Well County: Bexar	Elevation: 516 ft. above sea level

Type of Work: New Well	Proposed Use: Monitor
-------------------------------	------------------------------

Drilling Start Date: **5/2/2019** Drilling End Date: **5/2/2019**

	Diameter (in.)	Top Depth (ft.)	Bottom Depth (ft.)
Borehole:	8.25	0	50

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	Top Depth (ft.)	Bottom Depth (ft.)	Filter Material	Size
Filter Pack Intervals:	33	50	Sand	12/20

	Top Depth (ft.)	Bottom Depth (ft.)	Description (number of sacks & material)
Annular Seal Data:	0	2	Concrete 1.16 Bags/Sacks
	2	33	Bentonite 15.08 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: Surface Sleeve Installed	Surface Completion by Driller
---	--------------------------------------

Water Level: **36 ft. below land surface on 2019-05-02**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

Water Quality:

<i>Strata Depth (ft.)</i>	<i>Water Type</i>
No Data	No Data

Chemical Analysis Made: **No**

Did the driller knowingly penetrate any strata which contained injurious constituents?: **No**

Certification Data: The driller certified that the driller drilled this well (or the well was drilled under the driller's direct supervision) and that each and all of the statements herein are true and correct. The driller understood that failure to complete the required items will result in the report(s) being returned for completion and resubmittal.

Company Information: **Vortex Drilling**
4412 Bluemel Road
San Antonio, TX 78240

Driller Name: **James E. Neal** License Number: **4868**

Apprentice Name: **Tony Elmendorf**

Comments: **No Data**

Report Amended on 7/12/2019 by Request #28256

Lithology:
DESCRIPTION & COLOR OF FORMATION MATERIAL

Casing:
BLANK PIPE & WELL SCREEN DATA

<i>Top (ft.)</i>	<i>Bottom (ft.)</i>	<i>Description</i>
0	3.5	Sand
3.5	7.5	Sandy Clay
7.5	8.5	Clayey Sand
8.5	10	Silt
10	17.5	Sand
17.5	24	Interbedded Clay and Sand
24	50	Sand

<i>Dia (in.)</i>	<i>Type</i>	<i>Material</i>	<i>Sch./Gage</i>	<i>Top (ft.)</i>	<i>Bottom (ft.)</i>
2	Top Cap (Locking)	New Plastic (PVC)	40		
2	Bottom Cap	New Plastic (PVC)	40		
2	Riser	New Plastic (PVC)	40	-3	35
2	Screen	New Plastic (PVC)	40 0.010	35	50

IMPORTANT NOTICE FOR PERSONS HAVING WELLS DRILLED CONCERNING CONFIDENTIALITY

TEX. OCC. CODE Title 12, Chapter 1901.251, authorizes the owner (owner or the person for whom the well was drilled) to keep information in Well Reports confidential. The Department shall hold the contents of the well log confidential and not a matter of public record if it receives, by certified mail, a written request to do so from the owner.

Please include the report's Tracking Number on your written request.

Texas Department of Licensing and Regulation
P.O. Box 12157
Austin, TX 78711
(512) 334-5540



ERM Environmental Resources Management

JKS-64
DRILLING LOG


Proj. No. 0366643 Boring/Well ID JKS-64 Date Drilled 2016-09-09
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras power Station - San Antonio Boring T.D. 32.00' Boring Diam. 8.25"
 N. Coord. 13665627.14' E. Coord. 2186778.76' Surface Elevation 504.38' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 507.84' Stickup 3.46'
 Depth to Water: 1. Ft. btoc 25.06 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
504.38	0			0		0-5	NO RECOVERY: Previously excavated with hydrovac truck.
500	5					5-6.5	SILTY SAND: Brown; moist; loose.
				100		6.5-8	INTERBEDDED CLAY AND SAND: Pinkish gray and orange; fine grained, orange sand; pinkish gray clay layered with iron-oxide staining; damp; non-plastic.
495	10					8-13	SAND: Light gray and pale yellow; dry; very fine-grained; dense; very hard-packed; trace clay content; layered appearance.
490	15			100		13-22.5	INTERBEDDED CLAY AND SAND: Light gray and pale yellow, fine-grained sand; dark gray, slightly plastic, medium stiff clay.
485	20						At 17' bgs: Thickness of clay layers increases (1-2" thick); low plasticity.



JKS-64
DRILLING LOG

Proj. No. 0366643 Boring/Well ID JKS-64 Date Drilled 2016-09-09
 Project Ground Water Investigation - Phase II Owner CPS Energy
 Location Calaveras power Station - San Antonio Boring T.D. 32.00' Boring Diam. 8.25"
 N. Coord. 13665627.14' E. Coord. 2186778.76' Surface Elevation 504.38' Ft. MSL Datum
 Screen: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Slot Size 0.01"
 Casing: Type Sch. 40 PVC Diam. 2.00" Length 15.00' Sump Length 0'
 Top of Casing Elevation 507.84' Stickup 3.46'
 Depth to Water: 1. Ft. btoc 25.06 (2016-05-21) 2. Ft. _____ (_____)
 Drilling Company Strata Core Services, LLC Driller Ryan Spaust
 Drilling Method Hollow-Stem Auger Log By Andrew Henry

SKETCH MAP

NOTES

Coordinates in Texas South Central State Plane 4204. Elevations in NAVD88 computed using Geoid03.

Elevation (Ft MSL)	Depth (Feet)	Graphic Log	Well Construction	Recovery (%)	Lab Sample Data	Description Interval (Feet)	Description/Soil Classification (Color, Texture, Structure)
480	20	[Graphic Log]	[Well Construction]	100	JKS-64_20-30 USCS: Clayey Sand (SC) AL: 29 / 14 / 15 - #200: 30.1	20-22.5	At 20' bgs: Saturated; clay color changes to pinkish gray. Non-cohesive grab sample collected from 20'-30' bgs.
480	22.5	[Graphic Log]	[Well Construction]	100		22.5-25	SAND: Gray with bluish gray and orange; fine-grained; loose.
480	25	[Graphic Log]	[Well Construction]	100		25-30	At 23.8' bgs: Bluish gray, low plasticity clay (1/2" thick); sand color changes to greenish blue. INTERBEDDED CLAY AND SAND: Tannish gray; wet to saturated; fine-grained; wet to saturated; loose; clay layers are pinkish gray with iron-oxide staining.
475	26.8	[Graphic Log]	[Well Construction]	100		26.8-27.5	At 26.8' bgs: Wet.
475	27.5	[Graphic Log]	[Well Construction]	100		27.5-28.3	At 27.5' bgs: Saturated.
475	28.3	[Graphic Log]	[Well Construction]	100		28.3-30	At 28.3' bgs: Wet.
475	30	[Graphic Log]	[Well Construction]	100		30-32	At 30' bgs: Gray clay; dense/stiff; low plasticity; 1" thick. NO RECOVERY: Geotechnical sample collected, but not analyzed.
470	32	[Graphic Log]	[Well Construction]	100			Boring terminated at 32' bgs.
465	35	[Graphic Log]	[Well Construction]	100			
465	40	[Graphic Log]	[Well Construction]	100			

STATE OF TEXAS WELL REPORT for Tracking #443600

Owner: Calaveras Power Station	Owner Well #: JKS-64
Address: 12940 US 181 San Antonio, TX 78223	Grid #: 68-46-5
Well Location: 12940 US 181 San Antonio, TX 78223	Latitude: 29° 18' 28.4" N
Well County: Bexar	Longitude: 098° 19' 01.91" W
	Elevation: No Data
<hr/>	
Type of Work: New Well	Proposed Use: Monitor

Drilling Start Date: **9/9/2016** Drilling End Date: **9/9/2016**

	<i>Diameter (in.)</i>	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>
Borehole:	8.25	0	30

Drilling Method: **Hollow Stem Auger**

Borehole Completion: **Filter Packed**

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Filter Material</i>	<i>Size</i>
Filter Pack Intervals:	12	30	Sand	20/40

	<i>Top Depth (ft.)</i>	<i>Bottom Depth (ft.)</i>	<i>Description (number of sacks & material)</i>
Annular Seal Data:	0	2	Cement 1 Bags/Sacks
	2	12	Bentonite 2 Bags/Sacks

Seal Method: **Hand Mixed**

Sealed By: **Driller**

Distance to Property Line (ft.): **No Data**

Distance to Septic Field or other concentrated contamination (ft.): **No Data**

Distance to Septic Tank (ft.): **No Data**

Method of Verification: **No Data**

Surface Completion: **Surface Slab Installed** **Surface Completion by Driller**

Water Level: **No Data**

Packers: **No Data**

Type of Pump: **No Data**

Well Tests: **No Test Data Specified**

APPENDIX D GROUNDWATER FLOW DIRECTION MAPS

All monitoring wells associated with the CCR units were gauged for water levels during the eight background monitoring events between December 2016 and October 2017 and were gauged semi-annually in 2018 and 2019. Potentiometric surface maps that are representative of groundwater water level conditions during these periods are provided in Appendix D. Note: Water levels were also gauged semi-annually in 2020 and these potentiometric surface maps will be provided in the 2020 Annual Groundwater Monitoring and Corrective Action Reports for the CCR units.

Based on the water levels at these CCR units, the following wells were selected as background wells because they were consistently upgradient and/or an evaluation of historical data indicated they were representative of background groundwater conditions as presented in the Written Demonstration – Responses to Potential Statistically Significant Increases dated 27 April 2020:

- Bottom Ash Ponds – Wells JKS-49 and JKS-51
- Evaporation Pond – Wells JKS-63/63R, JKS-47, and JKS-64
- Fly Ash Landfill – Wells JKS-57 and JKS-45
- SRH Pond – Wells JKS-49 and JKS-51

BOTTOM ASH PONDS

Legend

- Background Monitor Well
- Downgradient Monitor Well
- CCR UNIT









Source: Google Earth Pro, 2020



POTENTIOMETRIC SURFACE MAP – MARCH 2017
 Southern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure

- Legend**
-  Background Monitor Well
 -  Downgradient Monitor Well
 -  CCR Unit
 -  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
 -  Groundwater Flow Direction
 - 485.23**
 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors © 2018 Microsoft Corporation © 2018 DigitalGlobe © CNES (2018) Distribution AirbusDS

Environmental Resources Management

POTENTIOMETRIC SURFACE MAP -
OCTOBER 2017
Bottom Ash Ponds CCR Unit
CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	1/31/2018	SCALE:	AS SHOWN	REVISION:	1
P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Eight Background Sampling Events\GIS\MXD\2017_CAR\0337367_CPSCalv_pmapS_BotAshPonds_oct2017.mxd					



- Legend**
- Background Monitor Well
 - Downgradient Monitor Well
 - CCR UNIT









Source: Google Earth Pro, 2020



POTENTIOMETRIC SURFACE MAP – April 2018
Bottoms Ash Ponds CCR Unit
CPS Energy – Calaveras Power Station
San Antonio, Texas

Figure

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
-  Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, ©OpenStreetMap contributors © 2019 Microsoft Corporation © 2019 DigitalGlobe ©CNES (2018) Distribution Airbus DS

Environmental Resources Management







POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2018
 Bottom Ash Ponds CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas





DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/14/2019	SCALE: AS SHOWN	REVISION: 1

P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Sampling Events\2016-17\GIS\MXD\2018\0337367_CPSCalv_pmapS_BotAshPonds_oct2018.mxd

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
-  486.11 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS







Environmental Resources Management


POTENTIOMETRIC SURFACE MAP -
 APRIL 2019
 Bottom Ash Ponds CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/13/2020	SCALE: AS SHOWN	REVISION: 1
<small>\\ushoufs011\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks.WZ\GIS_CAD\MXD\2019\gwmom\fig2A_0503422_CPSCalv_BotAshPond_apr2019pmap.mxd</small>		

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
-  Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS

Environmental Resources Management


POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2019
 Bottom Ash Ponds CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/13/2020	SCALE: AS SHOWN	REVISION: 1

\\shoufs011\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\MXD\2019\gwmom\fig2B_0503422_CPSCalv_BotAshPond_oct2019pmap.mxd

EVAPORATION POND




Source: Google Earth Pro, 2020

JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – May 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure




Source: Google Earth Pro, 2020

JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – June 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure



Source: Google Earth Pro, 2020







JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – August 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure

Legend

-  Upgradient Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.96 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer credits: Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors, DigitalGlobe, CNES (2018), © 2018 Microsoft Corporation, © 2018 Distribution: Airbus DS






Environmental Resources Management


POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2017
 Evaporation Pond CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/10/2018	SCALE: AS SHOWN	REVISION: 1

P:\Projects\0337367 CPS Energy CCR GW Investigation.WZ\Eight Background Sampling Events\GIS\XDO\2017_CAR\0337367_CPSCalv_pmapN_EvapPond_oct2017.mxd

- Legend**
-  Background Monitor Well
 -  Downgradient Monitor Well
 -  CCR Unit
 -  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
 -  Groundwater Flow Direction
 - 484.87 Potentiometric Surface Elevation (Feet, Mean Sea Level)
 - [481.43] Potentiometric Surface Elevation not considered for contouring



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors
© 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020) Distribution Airbus DS

Environmental Resources Management







POTENTIOMETRIC SURFACE MAP -
APRIL 2018
Evaporation Pond CCR Unit
CPS Energy - Calaveras Power Station
San Antonio, Texas


DESIGN: NH	DRAWN: AJB	CHKD.: WZ
DATE: 10/14/2020	SCALE: AS SHOWN	REVISION: 0

\\usbdcfs021\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\WXD\2018\gwmonr\fig2_0503422_CPSCalv_Evap_apr2018\pmap.mxd



Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.91 Potentiometric Surface Elevation (Feet, Mean Sea Level)
- NA Water level not available due to blockage in the well casing



Service Layer Credits: Esri, HERE, Garmin, © OpenStreetMap Contributors
 © 2018 Microsoft Corporation © 2018 DigitalGlobe © CNES (2018)
 Distribution Airbus DS

Environmental Resources Management






POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2018
 Evaporation Pond CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/14/2019	SCALE: AS SHOWN	REVISION: 1

P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Sampling Events\2016-17\GIS\MXD\2018\0337367_CPSCalv_pmapN_EvapPond_oct2018.mxd

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  483 Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 485.25 Potentiometric Surface Elevation (Feet, Mean Sea Level)
- NA Water level not available due to blockage in the well casing
- [486.66] Potentiometric Surface Elevation not considered for contouring



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors
 © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020) Distribution Airbus DS

Environmental Resources Management









POTENTIOMETRIC SURFACE MAP -
 APRIL 2019
 Evaporation Pond CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas




DESIGN: NH	DRAWN: AJB	CHKD.: WZ
DATE: 10/13/2020	SCALE: AS SHOWN	REVISION: 0

\\usbdcfs021\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\MXD\2019\gwm\fig2_0503422_CPSCalv_Evap_apr2019pmap.mxd

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  Plugged and Abandoned Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
-  482.79 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS

Environmental Resources Management


POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2019
 Evaporation Pond CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/15/2020	SCALE: AS SHOWN	REVISION: 0

\\ushoufs011\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\IMXD\2019\gwmon\fig_0503422_CPSCalv_Evap_oct2019pmap.mxd

FLY ASH LANDFILL




Source: Google Earth Pro, 2020

JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – May 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure




Source: Google Earth Pro, 2020

JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – June 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure



Source: Google Earth Pro, 2020







JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – August 2017
 Northern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure

Legend

-  Upgradient Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.96 Potentiometric Surface Elevation (Feet, Mean Sea Level)
- [480.61] Elevations in brackets were not utilized to contour potentiometric surface



Environmental Resources Management


POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2017
 Fly Ash Landfill CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	1/10/2018	SCALE:	AS SHOWN	REVISION:	1

P:\Projects\0337367 CPS Energy CCR GW Investigation.WZ\Eight Background Sampling Events\GIS\MXD\2017_CAR\0337367_CPSCalv_pmapN_FlyAshFill_oct2017.mxd

© 2013 Microsoft Corporation. © 2013 DigitalGlobe. © CNES (2013) Distribution Airbus DS



Source: Google Earth Pro, 2020







JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.




POTENTIOMETRIC SURFACE MAP – April 2018
 Evaporation Pond CCR Unit
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.91 Potentiometric Surface Elevation (Feet, Mean Sea Level)
- NA Water level not available due to blockage in the well casing



Service Layer Credits: Esri, HERE, Garmin, © OpenStreetMap Contributors
 © 2013 Microsoft Corporation © 2013 DigitalGlobe © CNES (2018)
 Distribution Airbus DS


Environmental Resources Management

POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2018
 Fly Ash Landfill CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/14/2019	SCALE: AS SHOWN	REVISION: 1

P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Sampling Events\2016-17\GIS\MXD\2018\0337367_CPSCalv_pmapN_FlyAshLFill_oci2018.mxd



Source: Google Earth Pro, 2020








JKS-63 was abandoned and replaced in May 2019. Water levels were measured at this location until April 2018 and at JKS-63R after August 2019.
 Potentiometric surface contour interval is 1 foot.



POTENTIOMETRIC SURFACE MAP – April 2019
 Evaporation Pond CCR Unit
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  Plugged and Abandoned Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.83 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS

Environmental Resources Management

POTENTIOMETRIC SURFACE MAP -
OCTOBER 2019
Fly Ash Landfill CCR Unit
CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ	
DATE: 1/15/2020	SCALE: AS SHOWN	REVISION: 0	

\\shoufs01\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\MXD\2019\gwmon\fig2_0503422_CPSCalv_FlyAsh_oct2019\pmap.mxd

SRH POND

Legend

- Background Monitor Well
- Downgradient Monitor Well
- CCR UNIT








Source: Google Earth Pro, 2020



POTENTIOMETRIC SURFACE MAP – MARCH 2017
 Southern CCR Units
 CPS Energy – Calaveras Power Station
 San Antonio, Texas

Figure


- Legend**
-  Background Monitor Well
 -  Downgradient Monitor Well
 -  CCR Unit
 -  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
 -  Groundwater Flow Direction
 - 485.23 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, DeLorme, MapmyIndia, © OpenStreetMap contributors © 2018 Microsoft Corporation © 2018 DigitalGlobe © CNES (2018) Distribution Airbus DS

Environmental Resources Management






POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2017
 SRH Pond CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



ERM

DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	1/31/2018	SCALE:	AS SHOWN	REVISION:	1

P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Eight Background Sampling Events\GIS\MXD\2017_CAR\0337367_CPSCalv_pmapS_SRHPonds_oct2017.mxd

- Legend**
-  Background Monitor Well
 -  Downgradient Monitor Well
 -  CCR Unit
 -  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
 -  Groundwater Flow Direction
 - 489.63 Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors
 © 2020 Microsoft Corporation © 2020 Maxar ©CNES (2020) Distribution Airbus DS






Environmental Resources Management



POTENTIOMETRIC SURFACE MAP -
 APRIL 2018
 SRH Ponds CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: AJB	CHKD.: WZ	
DATE: 10/13/2020	SCALE: AS SHOWN	REVISION: 1	
\\usbdcs02\data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\WXD\2018\gwmom\fig2_0503422_CPSCalv_SRHPPonds_apr2018pmap.mxd			

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 486.47**
Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits | Esri | HERE | Garmin | © OpenStreetMap contributors
© 2019 Microsoft Corporation © 2019 DigitalGlobe © CNES (2018) Distribution Airbus DS

Environmental Resources Management






POTENTIOMETRIC SURFACE MAP -
OCTOBER 2018
SRH Ponds CCR Unit
CPS Energy - Calaveras Power Station
San Antonio, Texas




DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	1/14/2019	SCALE:	AS SHOWN	REVISION:	1

P:\Projects\0337367 CPS Energy CCR GW Investigation\WZ\Sampling Events\2016-17\GIS\MXD\2018\0337367_CPSCalv_pmapS_SRHPonds_oct2018.mxd

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 485.90**
Potentiometric Surface Elevation (Feet, Mean Sea Level)



Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS

Environmental Resources Management






DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/13/2020	SCALE: AS SHOWN	REVISION: 1


\\shouf011\Data\Houston\Projects\0503422_CPS Energy Calaveras 2019 CCR Tasks_WZ\GIS_CAD\MXD\2019gwmon\fig2A_0503422_CPSCalv_SRPonds_apr2019pmap.mxd

POTENTIOMETRIC SURFACE MAP -
APRIL 2019
SRH Ponds CCR Unit
CPS Energy - Calaveras Power Station
San Antonio, Texas



Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  CCR Unit
-  Potentiometric Surface Contour Line (Feet, Mean Sea Level)
-  Groundwater Flow Direction
- 484.92** Potentiometric Surface Elevation (Feet, Mean Sea Level)



Environmental Resources Management

POTENTIOMETRIC SURFACE MAP -
 OCTOBER 2019
 SRH Ponds CCR Unit
 CPS Energy - Calaveras Power Station
 San Antonio, Texas



DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 1/13/2020	SCALE: AS SHOWN	REVISION: 1

\\ushours011\Data\Houston\Projects\0503422 CPS Energy Calaveras 2019 CCR Tasks\WZ\GIS_CAD\MXD\2019\gwmom\fig2B_0503422_CPSCalv_SRHPonds_0ct2019pmap.mxd

Service Layer Credits: Esri, HERE, Garmin, (c) OpenStreetMap contributors © 2020 Microsoft Corporation © 2019 DigitalGlobe © CNES (2019) Distribution Airbus DS

APPENDIX E CONSTITUENT CONCENTRATIONS SUMMARY TABLES

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-49 Upgradient												
Sample Date	Task	12/7/16	2/22/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	3.24	3.28	3.28	3.03 X	3.04 J	2.76	2.85	2.87	2.71	2.70	2.05	2.58	2.47
Calcium	mg/L	130	146	173	113	127	120	145	147	135	117 D	154 D	127 D	114 J
Chloride	mg/L	295 D	383 D	372 D	326	414 D	448 D	459 D	424	446 D	408	449	429	452
Fluoride	mg/L	0.715	0.643 JH	0.665 JH	0.809	0.627 JH	0.617 JH	0.525	0.712	0.697	0.719	0.749	0.793	0.894
Sulfate	mg/L	211 D	232 D	234 D	194	218 D	227	265 D	219 X	237	237	240	205	217
pH - Field Collected	SU	7.19	7.12	7.12	7.02	7.06	6.16	7.05	6.89	7.12	7.12	7.31	6.43	7.15
Total dissolved solids	mg/L	1250	1240	1190	1100	1450	1440	1490	1730	1310	1210	1290	1380	1240
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00173 J	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000676 J	0.000729 J	0.00123 U	0.00123 U	0.000544 J	0.000538 J	0.000478 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0607	0.0575	0.0503	0.0554	0.0783	0.0721	0.0788	0.0735	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000654 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000859 J	0.000572 J	0.00262 U	0.00262 U	0.000963 J	0.000997 J	0.00113 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00102 J	0.00109 J	0.00124 J	0.00155 J	0.00133 J	0.00153 J	0.00155 J	0.00146 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.715	0.643 JH	0.665 JH	0.809	0.627 JH	0.617 JH	0.525	0.712	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	0.0137 J	0.0341	0.0295	0.0427	0.0252	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000690 J	0.0000263 U	0.0000490 J	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00779 J	0.00846	0.00875	0.0106	0.00908 J	0.00938	0.0107	0.0111	NR	NR	NR	NR	NR
Selenium	mg/L	0.00992 J	0.00597	0.00479	0.00521 J	0.00370 J	0.00235	0.00188 J	0.00141 J	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.198 ± 0.197	0.615 ± 0.272	0.747 ± 0.323	0.195 ± 0.167	0.294 ± 0.192	0.241 ± 0.193	0.159 ± 0.191	0.746 ± 0.274	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.1 ± 0.907	-1.37 ± 1.37	0.854 ± 0.724	1.08 ± 1.72	2.23 ± 0.949	0.658 ± 0.636	0.812 ± 0.604	1.43 ± 0.898	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

Sample Date Task Constituents Unit		JKS-51 Upgradient												
		12/8/16	2/22/17	3/28/17	5/3/17	6/21/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
		Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.512	0.517	0.473	0.565	0.512	0.525	0.453	0.509	0.465	0.347	0.489	0.648	0.627
Calcium	mg/L	267	292	322	266	261 X	232	236	256	246	149 D	328	336 D	334 J
Chloride	mg/L	403 D	331 D	414 D	447	424 D	455 D	384 D	375	395 D	301	559	574 D	555
Fluoride	mg/L	0.247	0.341 JH	0.415 JH	0.534	0.354	0.391	0.0960 U	0.407 JH	0.305 J	0.291 J	0.329 J	0.405 J	0.470
Sulfate	mg/L	293 D	330 D	348 D	359	342 D	330 D	314 D	302	354 D	260	428	405 D	439
pH - Field Collected	SU	6.59	6.51	6.48	6.56	6.40	5.48	6.38	6.20	6.44	6.70	6.66	5.73	6.43
Total dissolved solids	mg/L	1650	1650	1490	1980	1530	1580	1390	1650	1320	916	1890	2150	2010
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00120 U	0.000953 J	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000412 J	0.000390 J	0.00123 U	0.000392 J	0.000344 J	0.000395 J	0.000418 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0655	0.0563	0.0517	0.0512	0.0534	0.0520	0.0520	0.0564	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000654 U	0.000212 J	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000941 J	0.000525 U	0.00262 U	0.000657 J	0.000874 J	0.00113 J	0.00133 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000350 U	0.0000770 J	0.0000920 J	0.000350 U	0.000124 J	0.0000940 J	0.0000800 J	0.000108 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.247	0.341 JH	0.415 JH	0.534	0.354	0.391	0.0960 U	0.407 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.000238 U	0.0322	0.0874	0.0790	0.0958 JX	0.0718	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.000199 J	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000255 U	0.000255 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.09 ± 0.376	0.104 ± 0.122	0.618 ± 0.247	0.197 ± 0.145	0.328 ± 0.195	0.0847 ± 0.186	4.83 ± 0.763	0.682 ± 0.309	NR	NR	NR	NR	NR
Radium-228	pCi/L	0.312 ± 0.688	1.09 ± 1.37	2.32 ± 1.45	-1.26 ± 1.37	-0.799 ± 0.928	1.57 ± 0.786	0.762 ± 0.706	0.963 ± 0.954	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-48 Downgradient												
Sample Date		12/7/16	2/22/17	3/30/17	5/2/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	2.21	2.14	--	2.08	2.13	2.15 X	2.02	2.23	2.03	2.13	2.22	2.27	2.36
Calcium	mg/L	130	139	125	NR	111	136 X	134	147	143	128 D	166 D	135 D	130 J
Chloride	mg/L	395 D	408 D	435 D	427	440 D	465 D	166 D	427	433 D	438	467	446	485
Fluoride	mg/L	1.43	1.21 JH	1.62	1.41 JH	1.07	1.62	0.0960 U	1.22	1.35	1.31	1.46	1.25	0.051 JH
Sulfate	mg/L	239 D	251 D	266 D	259	253 D	244	140 D	257	282 D	266	271	213	206
pH - Field Collected	SU	7.06	6.92	6.86	6.99	6.88	5.92	6.90	6.74	6.91	6.92	7.06	6.12	6.89
Total dissolved solids	mg/L	1400	1270	1440	1490	1540	1380 J	850	1470	1400	1410	1420	1520	1400
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	--	0.000240 U	0.00120 U	0.00129 J	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000538 J	--	0.000424 J	0.00123 U	0.000452 J	0.000459 J	0.000475 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0717	0.0699	--	0.0659	0.0686	0.0769	0.0725	0.0761	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	--	0.000131 U	0.000654 U	0.000233 J	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	--	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000608 J	--	0.000525 U	0.00262 U	0.000525 U	0.000863 J	0.00130 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00111 J	0.000844 J	--	0.000920 J	0.000987 J	0.00137 J	0.000917 J	0.00106 J	NR	NR	NR	NR	NR
Fluoride	mg/L	1.43	1.21 JH	1.62	1.41	1.07	1.62	0.0960 U	1.22	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	--	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000203 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	NR	0.0536	0.0501	0.0700	0.0551	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000310 JX	0.0000263 U	0.0000263 UX	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000422 J	--	0.000263 J	0.00128 U	0.000344 J	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	--	0.000454 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	--	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.139 ± 0.250	0.251 ± 0.149	0.0232 ± 0.136	0.357 ± 0.174	0.46 ± 0.235	0.544 ± 0.259	0.562 ± 0.283	0.26 ± 0.241	NR	NR	NR	NR	NR
Radium-228	pCi/L	0.847 ± 1.14	0.317 ± 1.15	1.1 ± 0.737	-0.109 ± 1.35	0.284 ± 0.662	0.273 ± 0.867	0.459 ± 0.649	0.772 ± 0.931	NR	NR	NR	NR	NR

NOTES:
 mg/L: Milligrams per Liter.
 SU: Standard Units.
 pCi/L: Picocuries per Liter.
 -- : Laboratory did not analyze sample for indicated constituent.
 D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
 H: Bias in sample result likely to be high.
 J: Analyte detected above method (sample) detection limit but below method quantitation limit.
 L: Bias in sample result likely to be low.
 NR: Analysis of this constituent not required for detection monitoring.
 U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
 X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-50R Downgradient												
Sample Date		12/7/16	2/22/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	4.70	5.18	5.87	5.92	4.87	4.38	4.18	4.54	3.52	5.17	5.85	6.93	5.52
Calcium	mg/L	126	134	189	120	125	108	130	132	127	116 D	159 D	135 D	126 J
Chloride	mg/L	47.7 X	49.0 J	63.9	81.3	111	123	141 D	100	170	87.9	70.0	60.3	102
Fluoride	mg/L	0.316	0.331 JH	0.447 JH	0.528	0.387 JH	0.390 JH	0.0960 U	0.427 JH	0.335 J	0.392 J	0.319 J	0.380 J	0.510
Sulfate	mg/L	137 X	146	156	160	146	148	195 D	144	131	141	168	172	194
pH - Field Collected	SU	6.83	6.77	NR	6.80	6.63	5.69	6.62	6.43	6.67	6.61	6.80	5.85	6.65
Total dissolved solids	mg/L	737	808	789	902	914	856	992	947	883	688	842	899	918
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00120 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.00111 J	0.000735 J	0.00123 U	0.00123 U	0.000520 J	0.000545 J	0.000596 J	NR	NR	NR	NR	NR
Barium	mg/L	0.133	0.128	0.113	0.117	0.125	0.117	0.123	0.118	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000147 J	0.000187 J	0.000654 U	0.000654 U	0.000131 U	0.000131 U	0.000174 J	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000189 J	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.00251 J	0.00169 J	0.00262 U	0.00262 U	0.000788 J	0.000759 J	0.00108 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00305 J	0.00345	0.00251	0.00215 J	0.00191 J	0.00216	0.00233	0.00285	NR	NR	NR	NR	NR
Fluoride	mg/L	0.316	0.331 JH	0.447 JH	0.528	0.387 JH	0.390 JH	0.0960 U	0.427 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000796 J	0.000988 J	0.000627 J	0.000758 U	0.000758 U	0.000178 J	0.000152 U	0.000168 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	0.000476 U	0.00209 J	0.000476 U	0.00621 J	0.000476 U	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00150 J	0.00153 J	0.00125 J	0.00128 U	0.00128 U	0.00102 J	0.00104 J	0.00108 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000514 J	0.000454 U	0.00227 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.102 ± 0.173	0.479 ± 0.216	-0.0714 ± 0.168	0.197 ± 0.183 U	0.245 ± 0.204	0.408 ± 0.226	0 ± 0.176	0.815 ± 0.292	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.99 ± 1.31	-0.428 ± 1.24	0.665 ± 1.14	0.00273 ± 1.33 U	0.783 ± 0.638	1.08 ± 0.832	0.0172 ± 1.12	1.5 ± 0.842	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-52 Downgradient												
Sample Date		12/7/16	2/21/17	3/28/17	5/2/17	6/21/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.66	2.11	1.63	1.51	1.33	1.43	1.46	1.71 X	1.95	1.54	1.46 X	1.65	2.05
Calcium	mg/L	169	181	189	--	145	140	162	168	175	153 D	195 DX	171 D	174 J
Chloride	mg/L	331 D	377 D	323 DX	320	326 D	343 D	417 D	355	360 D	326	336	320	433
Fluoride	mg/L	0.796	0.665	0.718 JH	0.915 JH	0.705	0.996 JH	0.0960 U	0.740	0.720	0.710	0.831	0.808	0.908
Sulfate	mg/L	277 D	318 D	299 DX	290	287 D	292 D	171 D	289	278 D	292	268	288 D	315
pH - Field Collected	SU	7.01	6.47	6.91	6.94	6.87	5.87	6.81	6.63	6.79	6.76	6.91	6.00	6.83
Total dissolved solids	mg/L	1290	1380	1100	1250	1280	1250	1250	1220	1240	1210	1170	1270	1470
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000565 J	0.000398 J	0.000425 J	0.000427 J	0.000392 J	0.000412 J	0.000448 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0646	0.0583	0.0519	0.0483	0.0527	0.0558	0.0565	0.0616	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000153 J	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000525 U	0.000525 U	0.000525 U	0.000841 J	0.000860 J	0.00123 J	0.00108 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00188 J	0.00233	0.00112 J	0.00119 J	0.00211	0.00183 J	0.00159 J	0.00189 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.796	0.665	0.718 JH	0.915 JH	0.705	0.996 JH	0.0960 U	0.740	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000292 J	0.000152 U	0.000152 U	0.000163 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.0471	0.000476 U	--	0.0616	0.0605	0.0827	0.0588	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.000234	0.0000263 U	0.0000263 U	0.0000263 U	0.0000810 J	0.0000263 U	0.0000263 UX	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.00128 J	0.00115 J	0.00102 J	0.000911 J	0.000865 J	0.000843 J	0.000914 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.71 ± 0.465	0.608 ± 0.289	0.296 ± 0.169	0 ± 0.150	0.435 ± 0.241	0.449 ± 0.196	0.194 ± 0.194	0.704 ± 0.319	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.65 ± 1.12	0.744 ± 0.833	0.0645 ± 0.649	0.53 ± 1.10	0.928 ± 0.784	1.16 ± 0.867	0.716 ± 0.767	1.54 ± 1.22	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-55 Downgradient												
Sample Date		12/7/16	2/22/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.716	0.716	0.785	0.710	0.787	0.651	0.687	0.759	0.645	0.611	0.740	0.771	0.779
Calcium	mg/L	143	153	181	133	133	118	136	146	134	119 D	165 D	145 D	137 J
Chloride	mg/L	384 DX	50.5	403 D	388	395 D	400 D	168 D	386	387 D	429	438	432	452
Fluoride	mg/L	0.857	0.352 JH	0.746 JH	0.891	1.14	1.08 JH	0.0960 U	0.864	0.791	0.820	0.822	0.832	1.01
Sulfate	mg/L	164 X	147	172	173	164	166	139 D	157	168	155	168	159	177
pH - Field Collected	SU	6.85	6.80	6.81	6.82	6.72	5.77	6.72	6.53	6.75	6.70	6.90	5.96	6.81
Total dissolved solids	mg/L	1430	1380	1290	1310	1500	1270	826	1470	1300	1190	1420	1370	1350
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00120 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000650 J	0.000520 J	0.00123 U	0.00123 U	0.000507 J	0.000582 J	0.000599 J	NR	NR	NR	NR	NR
Barium	mg/L	0.103	0.0876	0.0823	0.0758	0.0828	0.0780	0.0801	0.0816	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000134 J	0.000654 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000625 J	0.000525 U	0.00262 U	0.00262 U	0.000525 U	0.000797 J	0.000903 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00702 J	0.00516	0.00579	0.00750 J	0.00642 J	0.00562	0.00565	0.00565	NR	NR	NR	NR	NR
Fluoride	mg/L	0.857	0.352 JH	0.746 JH	0.891	1.14	1.08 JH	0.0960 U	0.864	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	0.0136 J	0.0425	0.0354	0.0495	0.0338	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 UX	0.0000263 U	0.0000263 UX	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00130 J	0.00123 J	0.00108 J	0.00128 U	0.00128 U	0.000804 J	0.000898 J	0.000837 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.00227 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.694 ± 0.358	0.721 ± 0.320	0.745 ± 0.258	0.576 ± 0.261	0.305 ± 0.190	0.0212 ± 0.171	0.327 ± 0.233	0.588 ± 0.314	NR	NR	NR	NR	NR
Radium-228	pCi/L	3.76 ± 1.33	1.87 ± 1.01	-0.0356 ± 1.09	1.01 ± 1.02	0.591 ± 0.843	0.532 ± 0.795	0.234 ± 0.821	1.24 ± 0.848	NR	NR	NR	NR	NR

NOTES:
mg/L: Milligrams per Liter.
SU: Standard Units.
pCi/L: Picocuries per Liter.
-- : Laboratory did not analyze sample for indicated constituent.
D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
H: Bias in sample result likely to be high.
J: Analyte detected above method (sample) detection limit but below method quantitation limit.
L: Bias in sample result likely to be low.
NR: Analysis of this constituent not required for detection monitoring.
U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Bottom Ash Ponds

		JKS-56 Downgradient												
Sample Date		12/7/16	2/22/17	3/30/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	3.97	4.13	--	4.60	3.98	3.60	3.60 X	3.48	3.95	3.95	3.85	4.47	3.55
Calcium	mg/L	137	143	127	124	136	116	137	146	126	121 D	150 D	131 D	103 J
Chloride	mg/L	131	95.7	96.3	95.6	114	126	146 D	150	121	108 JL	81.0	81.2	101
Fluoride	mg/L	0.344	0.354 JH	0.333	0.564	0.407 JH	0.401 JH	0.0960 U	0.448 JH	0.37 J	0.428 J	0.372 J	0.452 J	0.552
Sulfate	mg/L	193	190	188	183	186	194	201 D	200	193	192	193	194	138
pH - Field Collected	SU	6.73	6.63	6.56	6.71	6.56	5.63	6.57	6.38	6.64	6.55	6.76	5.84	6.72
Total dissolved solids	mg/L	1100	969	1020	997	1060	1060	986	1240	992	976	918	968	904
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	--	0.00120 U	0.00120 U	0.000240 U	0.00104 J	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00527 J	0.00425	--	0.00350 J	0.00435 J	0.00373	0.00517	0.00451	NR	NR	NR	NR	NR
Barium	mg/L	0.126	0.0974	--	0.0890	0.0921	0.0897	0.103	0.0909	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	--	0.000654 U	0.000654 U	0.000131 U	0.000136 J	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	--	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000654 J	--	0.00276 J	0.00262 U	0.000525 U	0.00498	0.00141 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00560 J	0.00564	--	0.00641 J	0.00687 J	0.00668	0.00771	0.00746	NR	NR	NR	NR	NR
Fluoride	mg/L	0.344	0.354 JH	0.333	0.564	0.407 JH	0.401 JH	0.0960 U	0.448 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	--	0.000758 U	0.000758 U	0.000152 U	0.000211 J	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.000476 U	0.000476 U	0.00156 J	0.000476 U	0.00598 J	0.000476 U	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000700 J	0.0000263 UX	0.0000263 U	0.0000263 UX	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00360 J	0.00190 J	--	0.00168 J	0.00152 J	0.00156 J	0.00160 J	0.00155 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	--	0.00227 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	--	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.23 ± 0.430	0.254 ± 0.175	0.372 ± 0.215	0.138 ± 0.166	0.273 ± 0.253	0.177 ± 0.213	0.441 ± 0.225	0.397 ± 0.252	NR	NR	NR	NR	NR
Radium-228	pCi/L	0.949 ± 1.38	3.07 ± 1.28	1.09 ± 0.897	1.97 ± 1.35	1.27 ± 0.994	1.16 ± 0.862	1.45 ± 0.895	3.36 ± 1.42	NR	NR	NR	NR	NR

NOTES:
 mg/L: Milligrams per Liter.
 SU: Standard Units.
 pCi/L: Picocuries per Liter.
 -- : Laboratory did not analyze sample for indicated constituent.
 D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
 H: Bias in sample result likely to be high.
 J: Analyte detected above method (sample) detection limit but below method quantitation limit.
 L: Bias in sample result likely to be low.
 NR: Analysis of this constituent not required for detection monitoring.
 U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
 X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-47 Upgradient												
Sample Date		12/8/16	2/28/17	3/29/17	5/3/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	4/10/19	10/23/19	4/29/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.824	0.838	0.696	0.817	0.804	0.828 JH	0.760	1.02	0.844	0.806	0.590	1.05	0.800
Calcium	mg/L	54.0	62.1	168	26.2	71.1	62.7 JH	66.7	36.1	53.5	83.2 D	128	36.5	43.1
Chloride	mg/L	107	150	232 D	193	168	148 JH	210 D	68.5	151	186	279	53.9 X	107
Fluoride	mg/L	0.0360 U	0.0360 U	0.315	0.382 JH	0.213 JH	0.360 U	0.0960 U	0.0360 U	0.0360 U	0.0998 J	0.0985 J	0.154 JH	0.163
Sulfate	mg/L	213 D	267 D	369 D	299	266 D	248 JH	284 D	171	236	262	347	210 X	257
pH - Field Collected	SU	5.82	5.83	5.75	6.00	5.75	5.85	5.90	5.93	5.91	5.72	5.92	4.58	5.87
Total dissolved solids	mg/L	811	922	1170	1060	979	806 JH	904	677	787	727	1240	665	772
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000294 J	0.00120 U	0.000275 J	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00442 J	0.00130 J	0.00136 J	0.00123 U	0.00185 J	0.00105 J	0.00124 J	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0475	0.0132	0.0180	0.0118 J	0.0154	0.00981	0.0104	0.00785	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000813 J	0.000255 J	0.000131 U	0.000654 U	0.000352 J	0.000131 U	0.000172 J	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000637 J	0.000977 J	0.000797 J	0.000735 J	0.000611 J	0.000814 J	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.234	0.00430	0.000988 J	0.00262 U	0.00262 J	0.000855 J	0.00130 J	0.000525 U	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00915 J	0.00102 J	0.00153 J	0.00113 J	0.00227	0.000976 J	0.00107 J	0.0000699 U	NR	NR	NR	NR	NR
Fluoride	mg/L	0.0360 U	0.0360 U	0.315	0.382 JH	0.213 JH	0.360 U	0.0960 U	0.0360 U	NR	NR	NR	NR	NR
Lead	mg/L	0.00586 J	0.000950 J	0.000448 J	0.000758 U	0.00157 J	0.000202 J	0.000449 J	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.0615	0.0478	0.00238 U	0.0207	0.0720	0.0644	0.0799	0.0521	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000600 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.0317	0.00126 J	0.00173 J	0.00128 J	0.000788 J	0.000581 J	0.000653 J	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.0493	0.0697	0.0518	0.0564	0.0613	0.0577	0.0525	0.0854	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.2 ± 0.342	0.578 ± 0.275	0.630 ± 0.237	0.538 ± 0.192	0.729 ± 0.278	0.304 ± 0.233	1.06 ± 0.361	0.246 ± 0.180	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.66 ± 1.15	1.34 ± 1.05	1.27 ± 0.960 U	2.17 ± 1.01	0.664 ± 0.929	0.771 ± 1.48	1.65 ± 1.05	0.463 ± 0.886	NR	NR	NR	NR	NR

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-63 / JKS-63R Upgradient (A)													
Sample Date		12/8/16	2/22/17	3/29/17	5/3/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	8/20/19	10/23/19	4/29/20	
Task		Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020	
Constituents	Unit														
Appendix III - Detection Monitoring															
Boron	mg/L	0.800	0.866	NR	0.981	(1)	1.33 JH	1.23	1.06	1.13	(2)	2.03	1.03	0.950	
Calcium	mg/L	783	914	713	1060	(1)	835	174	872	836	(2)	221	953 D	952	
Chloride	mg/L	1230 D	1160 D	1220 D	1340	(1)	1960 JHD	1890 D	1420	1670	(2)	2360 D	2240	2530	
Fluoride	mg/L	0.0573 J	0.320	0.297	0.364 JH	(1)	0.0971 JH	0.182 JH	0.0360 U	0.0360 U	(2)	0.206 J	0.352 JH	0.018 U	
Sulfate	mg/L	0.0460 U	1860 D	1890 D	1860	(1)	1970 D	1920 D	1820	2110	(2)	1810 D	1750 D	1810	
pH - Field Collected	SU	5.61	5.35	5.60	5.85	(1)	5.88	5.82	5.63	5.64	(2)	--	4.76	5.83	
Total dissolved solids	mg/L	5750	4760	4870	5560	(1)	6410	5000	5080	5220	(2)	6660	5200	7240	
Appendix IV - Assessment Monitoring															
Antimony	mg/L	0.00120 U	0.000459 J	0.000695 J	0.00120 U	(1)	0.000240 U	0.000424 J	0.000240 U	NR	NR	NR	NR	NR	
Arsenic	mg/L	0.00332 J	0.00294	0.00128 J	0.00123 U	(1)	0.000893 J	0.000992 J	0.000246 U	NR	NR	NR	NR	NR	
Barium	mg/L	0.0626	0.0540	0.0336	0.0316	(1)	0.0294	0.0258	0.0222	NR	NR	NR	NR	NR	
Beryllium	mg/L	0.000654 U	0.000930 J	0.000442 J	0.000654 U	(1)	0.000196 J	0.000223 J	0.000131 U	NR	NR	NR	NR	NR	
Cadmium	mg/L	0.00339 J	0.00405	0.00394	0.00316 J	(1)	0.00282	0.00263	0.00285	NR	NR	NR	NR	NR	
Chromium	mg/L	1.49	0.735	0.371	0.114	(1)	0.0742	0.0584	0.0130	NR	NR	NR	NR	NR	
Cobalt	mg/L	0.0802	0.0762	0.0546	0.0331	(1)	0.0137	0.0119	0.0119	NR	NR	NR	NR	NR	
Fluoride	mg/L	0.0573 J	0.320	0.297	0.364 JH	(1)	0.0971 JH	0.182 JH	0.0360 U	NR	NR	NR	NR	NR	
Lead	mg/L	0.00441 J	0.00599	0.00108 J	0.000758 U	(1)	0.000238 J	0.000551 J	0.000152 U	NR	NR	NR	NR	NR	
Lithium	mg/L	0.000476 U	0.116	0.00238 U	0.654	(1)	0.946	1.15	0.791	NR	NR	NR	NR	NR	
Mercury	mg/L	0.000236	0.000237	0.000206	0.0000400 J	(1)	0.000260	0.000441	0.000376	NR	NR	NR	NR	NR	
Molybdenum	mg/L	0.186	0.00789	0.00966	0.00419 J	(1)	0.00281	0.00180 J	0.000255 U	NR	NR	NR	NR	NR	
Selenium	mg/L	0.0188	0.0210	0.0257	0.0188	(1)	0.0288	0.0318	0.0244	NR	NR	NR	NR	NR	
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	(1)	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR	
Radium-226	pCi/L	3.42 ± 0.573	2.76 ± 0.476	5.79 ± 0.790	4.57 ± 0.577	(1)	6.7 ± 0.744	7.36 ± 0.874	5.04 ± 0.711	NR	NR	NR	NR	NR	
Radium-228	pCi/L	2.44 ± 1.44	4.13 ± 1.21	2.04 ± 1.61 U	3.41 ± 0.968	(1)	10.9 ± 2.31	1.79 ± 1.27	6.77 ± 1.48	NR	NR	NR	NR	NR	

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-64 Upgradient													
Sample Date		12/8/16	2/23/17	3/29/17	5/4/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	4/10/19	10/23/19	4/29/20	
Task		Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020	
Constituents	Unit														
Appendix III - Detection Monitoring															
Boron	mg/L	0.839	0.837	1.14	0.962	0.816	0.904 JH	0.835	0.901	0.837	0.805	0.804	0.747	0.711	
Calcium	mg/L	24.0	24.0	31.4	23.8	20.6	21.7 JH	21.6	25.2	23.6	24.4	23.0	24.4	20.3	
Chloride	mg/L	12.7	12.4	11.8	11.0	11.4	11.5	11.5	9.63	14.2	15.5	16.6	17.7	18.2	
Fluoride	mg/L	0.0360 U	0.294 JH	0.332	0.188	0.231 JH	0.157 JH	0.224 JH	0.0360 U	0.0360 U	0.106 J	0.121 J	0.176 JH	0.143	
Sulfate	mg/L	171	182	184	174	172	170 JH	172	164	189	196	193	192 X	209	
pH - Field Collected	SU	6.46	5.50	6.30	6.33	6.21	6.09	6.20	6.21	6.13	5.97	6.14	4.82	5.86	
Total dissolved solids	mg/L	594	585	611	581	572	555 JH	463	576	549	525	551	588	569	
Appendix IV - Assessment Monitoring															
Antimony	mg/L	0.000240 U	0.000240 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR	
Arsenic	mg/L	0.000911 J	0.000730 J	0.000556 J	0.00123 U	0.000476 J	0.000490 J	0.000519 J	0.000246 U	NR	NR	NR	NR	NR	
Barium	mg/L	0.00768	0.00451	0.00392 J	0.00410 J	0.00320 J	0.00324 J	0.00275 BJ	0.000484 U	NR	NR	NR	NR	NR	
Beryllium	mg/L	0.000131 U	0.000131 U	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR	
Cadmium	mg/L	0.000147 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR	
Chromium	mg/L	0.000525 U	0.000905 J	0.000525 U	0.00262 U	0.000867 J	0.000637 J	0.000961 J	0.000525 U	NR	NR	NR	NR	NR	
Cobalt	mg/L	0.000998 J	0.000952 J	0.000851 J	0.000859 J	0.000745 J	0.000856 J	0.000889 J	0.0000699 U	NR	NR	NR	NR	NR	
Fluoride	mg/L	0.0360 U	0.294 JH	0.332	0.188	0.231 JH	0.157 JH	0.224 JH	0.0360 U	NR	NR	NR	NR	NR	
Lead	mg/L	0.000186 J	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR	
Lithium	mg/L	0.0173 J	0.0146 J	0.00238 U	0.0152 J	0.0173 J	0.0181 J	0.0252	0.0208	NR	NR	NR	NR	NR	
Mercury	mg/L	0.0000263 UX	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000540 J	0.0000263 U	NR	NR	NR	NR	NR	
Molybdenum	mg/L	0.000398 J	0.000317 J	0.000255 U	0.00128 U	0.000265 J	0.000255 U	0.000273 J	0.000255 U	NR	NR	NR	NR	NR	
Selenium	mg/L	0.000512 J	0.000550 J	0.000495 J	0.00227 U	0.000468 J	0.000468 J	0.000454 U	0.000454 U	NR	NR	NR	NR	NR	
Thallium	mg/L	0.000332 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR	
Radium-226	pCi/L	0.981 ± 0.400	1.16 ± 0.408	0.530 ± 0.284	0.231 ± 0.174	0.258 ± 0.175	0.286 ± 0.247	1.05 ± 0.361	0.531 ± 0.276	NR	NR	NR	NR	NR	
Radium-228	pCi/L	0.429 ± 1.56	2.07 ± 1.22	-0.102 ± 1.07 U	0.408 ± 0.764	0.699 ± 0.761	2.49 ± 1.54	0.26 ± 0.639	1 ± 0.834	NR	NR	NR	NR	NR	

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-36 Downgradient												
Sample Date		12/8/16	2/23/17	3/29/17	5/4/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	4/10/19	10/22/19	4/29/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.308	0.671	0.748	0.731	0.581	0.625 JH	0.663	0.637	0.625	0.686	0.663	0.632	0.459
Calcium	mg/L	69.7	165	147	282	247	255 JHX	241	289	281	311 D	315 D	265 D	175
Chloride	mg/L	14.5	199 D	37.0	355	364 D	379 JHD	319 D	328	347 X	313	285	274	63.3
Fluoride	mg/L	0.0360 U	0.439 JH	0.330	1.53	1.26	1.37 JH	1.30	1.32	1.95 X	1.47	1.45	1.41	1.18
Sulfate	mg/L	49.2	409 D	271 D	726	731 D	775 JHD	707 D	741	816 X	946	697	756 D	189
pH - Field Collected	SU	6.71	4.96	6.98	4.04	3.72	3.80	5.20	3.24	3.48	3.61	3.71	3.66	3.42
Total dissolved solids	mg/L	368	1010	591	1610	1820	1700 JH	1220	1770	1650	1630	1520	1600	1790
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.00123 J	0.00120 U	0.000240 U	0.00121 J	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 J	0.000588 J	0.00134 J	0.00324 J	0.00276	0.00369	0.00341	0.00372	NR	NR	NR	NR	NR
Barium	mg/L	0.0988	0.0967	0.139	0.0270	0.0187	0.0207	0.0372	0.0225	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.00198 J	0.000131 U	0.0259	0.0226	0.0261	0.0212	0.0259	NR	NR	NR	NR	NR
Cadmium	mg/L	0.00257 J	0.00510	0.000548 J	0.0118	0.0102	0.0117	0.0101	0.0113	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.00608	0.0409	0.0100 J	0.00968	0.0156	0.00792	0.0132	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000579 J	0.0871	0.00751	0.220	0.186	0.216	0.195	0.215	NR	NR	NR	NR	NR
Fluoride	mg/L	0.0360 U	0.439 JH	0.330	1.53	1.26	1.37 JH	1.30	1.32	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000164 J	0.000220 J	0.000261 J	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.0123 J	0.119	0.00238 U	0.326	0.340	0.371	0.372	0.379	NR	NR	NR	NR	NR
Mercury	mg/L	0.000834	0.000289	0.00143	0.00240	0.00244	0.00160	0.00113	0.00226	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00397 J	0.00261	0.0686	0.00183 J	0.000704 J	0.000791 J	0.00151 J	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.0334	0.0448	0.0313	0.0673	0.0616	0.0697	0.0633	0.0663	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000487 J	0.000332 U	0.00166 U	0.000876 J	0.00114 J	0.000889 J	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.0888 ± 0.151	1.12 ± 0.342	0.453 ± 0.276	4.85 ± 0.656	4.02 ± 0.608	4.32 ± 0.667	6.28 ± 0.845	3.6 ± 0.600	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.14 ± 1.02	2.17 ± 0.979	0.166 ± 0.861 U	4.28 ± 1.19	3.44 ± 1.04	3.95 ± 1.79	2.63 ± 0.928	3.3 ± 1.33	NR	NR	NR	NR	NR

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-61 Downgradient												
Sample Date		12/7/16	2/23/17	3/29/17	5/3/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/31/18	4/10/19	10/22/19	4/29/20
Task		Event 1	Event 2	Event 3	Event 4	Event 5	Event 6	Event 7	Event 8	Event 9	Event 10	Event 11	Event 12	Event 13
Constituents	Unit	Dec 2016	Feb 2017	Mar 2017	May 2017	Jun 2017	Jul 2017	Aug 2017	Oct 2017	Apr 2018	Oct 2018	Apr 2019	Oct 2019	Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.07	1.29	1.15	1.18	0.960	1.01 JH	0.994	0.997	1.09	3.25	2.72	2.90	1.82
Calcium	mg/L	134	95.9	155	113	115	107 JH	105	135	171	197 D	176	168 D	154
Chloride	mg/L	198	158	162	168	193	190 JH	218 D	210	285	213	253	248	312
Fluoride	mg/L	0.393	0.503	0.522	0.643 JH	0.459 JH	0.479 JH	0.0960 U	0.0360 U	0.406 J	0.430 J	0.403 J	0.480 J	0.494
Sulfate	mg/L	401 D	377 JD	382 D	388	408 D	390 JHD	385 D	401	562	548	619	548 D	604
pH - Field Collected	SU	6.72	6.51	6.48	6.68	6.53	6.55	7.40	6.27	6.42	6.38	6.52	5.61	6.27
Total dissolved solids	mg/L	1400	1180	1190	1260	1430	1290 JH	1170	1280	1620	514	1650	1790	1870
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000768 J	0.000709 J	0.00123 U	0.000563 J	0.000622 J	0.000569 J	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0364	0.0186	0.0173	0.0178 J	0.0148	0.0167	0.0153	0.0162	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000911 J	0.000525 U	0.00262 U	0.000525 U	0.000604 J	0.000808 J	0.000525 U	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000719 J	0.000725 J	0.000769 J	0.000779 J	0.000805 J	0.000765 J	0.000855 J	0.0000699 U	NR	NR	NR	NR	NR
Fluoride	mg/L	0.393	0.503	0.522	0.643 JH	0.459 JH	0.479 JH	0.0960 U	0.0360 U	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.0158 J	0.00238 U	0.0120 J	0.0342	0.0336	0.0443	0.0335	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00165 J	0.00129 J	0.000984 J	0.00128 U	0.000776 J	0.000742 J	0.000712 J	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.00123 J	0.00123 J	0.00227 U	0.00185 J	0.00154 J	0.00172 J	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.15 ± 0.429	0.723 ± 0.306	0.256 ± 0.237 U	0.237 ± 0.193	0.398 ± 0.239	0.511 ± 0.223	0.821 ± 0.324	0.485 ± 0.212	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.79 ± 1.44	0.358 ± 1.06	0.761 ± 0.688 U	-0.064 ± 0.607	2.03 ± 0.997	0.491 ± 0.813	0.247 ± 0.710	1.64 ± 1.08	NR	NR	NR	NR	NR

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Evaporation Pond

		JKS-62 Downgradient												
Sample Date		12/8/16	2/23/17	3/29/17	5/4/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	4/10/19	10/23/19	4/29/20
Task		Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Constituents	Unit													
Appendix III - Detection Monitoring														
Boron	mg/L	0.549	0.481	0.597	0.601	0.501	0.485 JH	0.485	0.549	0.522	0.559	0.612	0.528	0.484
Calcium	mg/L	155	152	220	156	150	134 JH	150	158	160	161 D	205 D	151 D	122
Chloride	mg/L	257 D	279 DX	279 D	278	291 D	260 JHD	281 D	241	312	279	336	276	284
Fluoride	mg/L	0.246	0.362 JH	0.418	0.388	0.366 JH	0.342 JH	0.233 JH	0.0360 U	0.353 J	0.309 J	0.356 J	0.380 J	0.331
Sulfate	mg/L	190	187	193	188	184	181 JH	188 D	175	200	183	191	183	190
pH - Field Collected	SU	6.79	6.67	6.63	6.71	6.68	6.82	7.51	6.52	6.72	6.58	6.29	5.43	6.54
Total dissolved solids	mg/L	1120	1170	1140	1100	1080	976 JH	1080	1080	1110	956	1190	1160	1100
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.000240 U	0.000240 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.000684 J	0.000293 J	0.000246 U	0.00123 U	0.000254 J	0.000246 U	0.000246 U	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0825	0.0786	0.0813	0.0747	0.0734	0.0737	0.0708	0.0793	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000131 U	0.000131 U	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000147 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00186 J	0.00109 J	0.000525 U	0.00262 U	0.000551 J	0.000691 J	0.00107 J	0.000525 U	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00110 J	0.000198 J	0.000744 J	0.000350 U	0.000278 J	0.000211 J	0.000699 U	0.000699 U	NR	NR	NR	NR	NR
Fluoride	mg/L	0.246	0.362 JH	0.418	0.388	0.366 JH	0.342 JH	0.233 JH	0.0360 U	NR	NR	NR	NR	NR
Lead	mg/L	0.000588 J	0.000152 U	0.000152 U	0.000758 U	0.000154 J	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.0129 J	0.00238 U	0.00134 J	0.0353	0.0305	0.0457	0.0263	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000540 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.000414 J	0.000259 J	0.000255 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.222	0.192	0.196	0.195	0.185	0.181	0.191	0.208	NR	NR	NR	NR	NR
Thallium	mg/L	0.000332 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.485 ± 0.229	0.402 ± 0.220	0.665 ± 0.321	0.0997 ± 0.153	0.425 ± 0.233	0.399 ± 0.220	2.02 ± 0.489	0.669 ± 0.279	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.15 ± 1.38	1.53 ± 1.28 U	0.305 ± 1.10 U	-0.138 ± 0.656	0.66 ± 0.760	1.07 ± 0.949	0.673 ± 0.821	0.371 ± 0.631	NR	NR	NR	NR	NR

NOTES:

(A) JKS-63 plugged and abandoned and replaced with JKS-63R on 5/2/19. Sample events 1 through 10 collected from JKS-63 and thereafter from JKS-63R.

(1) Sample not collected due to the well going dry during sampling activities.

(2) Sample not collected due to blockage in the well casing.

mg/L: Milligrams per Liter.

SU: Standard Units.

pCi/L: Picocuries per Liter.

-- : Laboratory did not analyze sample for indicated constituent.

B: Target analyte or common lab contaminant was identified in the method blank.

D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.

J: Analyte detected above method (sample) detection limit but below method quantitation limit.

H: Bias in sample result likely to be high.

NR: Analysis of this constituent not required for detection monitoring.

U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).

X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Fly Ash Landfill

		JKS-45 Upgradient												
Sample Date	Task	12/6/16	2/23/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/10/19	10/23/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.65	1.51	2.27	1.11	2.03	1.91	2.02	2.21	2.28	3.24	2.78	2.98	3.01
Calcium	mg/L	144	122	184	105	101	103	120	130	128	161 D	195	161 D	141 J
Chloride	mg/L	196	187	181 J	160	152	0.803	345 JHD	24.8	118	137	167	144	113
Fluoride	mg/L	0.0360 U	0.207	0.334	0.337 JH	0.174 J	0.274 JH	0.0960 U	0.131 JH	0.0360 U	0.0360 U	0.0621 UJ	0.101 J	0.100
Sulfate	mg/L	623 D	639 D	661	613 X	602 D	2.95 JH	770 JHD	120	662 D	707	874	698	619
pH - Field Collected	SU	5.41	5.17	3.98	5.62	5.13	5.66	5.82	5.60	5.59	5.70	5.03	5.59	5.85
Total dissolved solids	mg/L	1270	1300	1330	1350	1270	1250	1680 JH	1100	1190	741	1350	1320	1590
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.000240 U	0.000310 J	0.000400 J	0.00120 U	0.00120 U	0.000240 U	0.000348 J	0.000490 J	NR	NR	NR	NR	NR
Arsenic	mg/L	0.000534 J	0.00216	0.00595	0.00123 U	0.00123 U	0.000346 J	0.00283	0.000618 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0185	0.0436	0.103	0.0128 J	0.0176 J	0.0114	0.0480	0.0142	NR	NR	NR	NR	NR
Beryllium	mg/L	0.00261 U	0.000383 J	0.000921 J	0.000654 U	0.000654 U	0.000149 J	0.000408 J	0.000229 J	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000147 U	0.000147 U	0.000189 J	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00743	0.0152	0.0320	0.00403 J	0.00262 U	0.00313 J	0.0135	0.00272 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00506	0.00465	0.00828	0.00346 J	0.00351 J	0.00277	0.00376	0.00358	NR	NR	NR	NR	NR
Fluoride	mg/L	0.0360 U	0.207	0.334	0.337 JH	0.174 J	0.274 JH	0.0960 U	0.131 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000571 J	0.00419	0.0117	0.000758 U	0.000758 U	0.000479 J	0.00482	0.000968 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.0329	0.0601	0.00238 U	0.0600	0.0639	0.0694	0.0935	0.0781	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000320 JX	0.0000263 U	0.0000263 U	0.0000300 J	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00105 J	0.00245	0.00372	0.00128 U	0.00128 U	0.000255 U	0.00115 J	0.000271 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.0147	0.0144	0.0174	0.0121	0.0123	0.00990	0.0136	0.0118	NR	NR	NR	NR	NR
Thallium	mg/L	0.000332 U	0.000332 U	0.000460 J	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	4.78 ± 0.890	4.29 ± 0.612	7.63 ± 0.795	3.29 ± 0.485	4.24 ± 0.671	4.34 ± 0.607	3.65 ± 0.553	5.07 ± 0.718	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.92 ± 1.19	4.59 ± 1.34	2.27 ± 1.19	1.42 ± 0.908	2.84 ± 1.15	1.83 ± 0.868	1.86 ± 0.827	1.66 ± 0.847	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- F: Relative percent difference exceeded laboratory control limits.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- K: Sample analyzed outside of recommended hold time.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Fly Ash Landfill

		JKS-57 Upgradient												
Sample Date	Task	12/7/16	2/22/17	3/28/17	5/2/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/10/19	10/23/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	3.19	3.24	3.17	2.67	3.09	3.08	2.98	3.48	4.49	2.81	3.23	4.14	5.97
Calcium	mg/L	349	362	413	--	290	327	337	393	409	401 D	477 D	479 D	622 J
Chloride	mg/L	70.6	76.2	89.6	130	158	311 D	12.5 JH	185	534 D	3770	119	841	3460
Fluoride	mg/L	3.62	3.32	2.84	2.27	3.42	3.43	0.0960 U	3.28	4.29	2.31	3.03	2.72	4.17
Sulfate	mg/L	2780 D	1980 DX	2090	2470 D	3080	3410 D	450 JH	3610	4260 D	5000	3570	4240	6510
pH - Field Collected	SU	6.73	6.08	5.13	6.63	6.37	6.72	6.60	6.70	6.63	6.35	6.20	6.19	6.49
Total dissolved solids	mg/L	4770	3780	3320	4060	5800	5920	850 JH	5850	7390	9750	6000	6700	15100
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00138 J	0.000630 J	0.000654 J	0.000561 J	0.00123 U	0.000480 J	0.000519 J	0.000486 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0311	0.0211	0.0208	0.0174	0.0164 J	0.0149	0.0128	0.0145	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000161 J	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000687 J	0.000525 U	0.000525 U	0.00262 U	0.000739 J	0.000816 J	0.00104 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000520 J	0.00232	0.000297 J	0.000449 J	0.000407 J	0.000748 J	0.000195 J	0.000322 J	NR	NR	NR	NR	NR
Fluoride	mg/L	3.62	3.32	2.84	2.27	3.42	3.43	0.0960 U	3.28	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000256 J	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.545	0.287 X	0.00238 U	--	0.533	0.649	0.671	0.733	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000300 J	0.0000263 U	0.0000580 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000385 J	0.000278 J	0.000255 U	0.00128 U	0.000329 J	0.000283 J	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00237 J	0.000664 J	0.000594 J	0.000561 J	0.00227 U	0.000612 J	0.000858 J	0.000697 J	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.592 ± 0.325	0.322 ± 0.157	0.519 ± 0.219	0.356 ± 0.176	0.273 ± 0.273	0.338 ± 0.221	0.255 ± 0.176	0.0986 ± 0.153	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.15 ± 0.895	2.31 ± 1.03	0.794 ± 0.818	2.86 ± 1.27	0.903 ± 0.843	0.786 ± 0.900	1.9 ± 0.894	1.73 ± 1.00	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- F: Relative percent difference exceeded laboratory control limits.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- K: Sample analyzed outside of recommended hold time.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Fly Ash Landfill

		JKS-31 Downgradient												
Sample Date	Task	12/8/16	2/21/17	3/29/17	5/2/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/10/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.446	0.580	0.642	0.499	0.573	0.510	0.494	0.553	0.485	0.514	0.557	0.483	0.429
Calcium	mg/L	188	384 X	317	--	216	171	230	228	187	208 D	295 D	200 D	171 J
Chloride	mg/L	223 D	477 D	303 D	317	285 D	0.280 UDXF	0.347 U	288	253 D	256	322	267	272
Fluoride	mg/L	0.801	0.186 J	0.548	0.865	0.661	0.979 JHXF	0.0960 U	0.735 JH	0.839	0.694	0.791 U	0.784	1.00
Sulfate	mg/L	697 D	1130 D	768 D	875	782 D	1.17 JHDXF	0.160 JH	803	771 D	774	852	819	877
pH - Field Collected	SU	3.94	4.04	6.34	4.29	3.84	5.14	3.99	3.98	3.74	3.07	3.56	2.62	3.70
Total dissolved solids	mg/L	1470	2290	2430	1850	1730	1500	25.0 U	1890	1420	1390	1660	1620	1890
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000295 J	0.000301 J	0.00120 U	0.000527 J	0.000240 U	0.000559 J	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00151 J	0.0110	0.00834	0.00501	0.00363 J	0.00134 J	0.00556	0.00279	NR	NR	NR	NR	NR
Barium	mg/L	0.0167 J	0.0141	0.0198	0.0136	0.0127 J	0.0229	0.0129	0.0122	NR	NR	NR	NR	NR
Beryllium	mg/L	0.00793 J	0.00851	0.00885	0.00814	0.00865 J	0.00593	0.00827	0.00857	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.0200 J	0.000663 J	0.000596 J	0.000525 U	0.00262 J	0.000890 J	0.000849 J	0.000760 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000440 J	0.0399	0.0623	0.0227	0.0173	0.0113	0.0302	0.0192	NR	NR	NR	NR	NR
Fluoride	mg/L	0.801	0.186 J	0.548	0.865	0.661	0.979 JHXF	0.0960 U	0.735 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000415 J	0.000223 J	0.000344 J	0.000758 U	0.000348 J	0.00233	0.000580 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.533	0.510	0.00238 U	--	0.572	0.484	0.615	0.590	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000360 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000255 U	0.000255 U	0.000255 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.00163 J	0.00175 J	0.00125 J	0.00227 U	0.00162 J	0.00177 J	0.00155 J	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	2.46 ± 0.574	2.60 ± 0.473	1.44 ± 0.425	1.40 ± 0.338	1.40 ± 0.403	1.28 ± 0.341	1.36 ± 0.399	1.01 ± 0.323	NR	NR	NR	NR	NR
Radium-228	pCi/L	7.35 ± 1.59	8.16 ± 2.15	5.33 ± 1.47	5.85 ± 1.79	4.63 ± 1.23	4.44 ± 1.37	3.58 ± 1.22	4.96 ± 1.43	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- F: Relative percent difference exceeded laboratory control limits.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- K: Sample analyzed outside of recommended hold time.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
 Groundwater Analytical Results Summary
 CPS Energy - Calaveras Power Station
 Fly Ash Landfill

		JKS-33 Downgradient												
Sample Date	Task	12/7/16	2/22/17	3/28/17	5/2/17	6/20/17	7/26/17	8/29/17	10/10/17	4/5/18	10/30/18	4/10/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.940	1.02	1.05	0.987	1.09	1.01	1.03	1.11	0.990	0.791	1.13	1.18	1.18
Calcium	mg/L	564	600	553	--	563	558	567	531	552	385 D	631	553 D	573 J
Chloride	mg/L	735 D	679 D	731 D	690	692 D	693 D	125 JH	666	786	758	806	773 JLKD	756
Fluoride	mg/L	1.86	1.08	1.77	1.36	1.81	1.34	0.480 U	1.69	1.85	1.21	1.23	1.24 JLK	1.68
Sulfate	mg/L	1850 D	1670 D	1780 D	1710	1690 D	1710 D	3170 D	1640	1810	1740	1640	1690 JLKD	1620
pH - Field Collected	SU	6.51	5.90	4.91	6.52	6.15	5.71	6.49	6.49	6.33	6.26	5.98	5.18	6.30
Total dissolved solids	mg/L	4000	3990	4310	4410	3750	4070	3580	4320	3970	3320	2650 JLK	4040 JLK	4370
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.00120 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000246 U	0.00123 U	0.000257 J	0.00123 U	0.000279 J	0.000316 J	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0326	0.0318	0.0297	0.0268	0.0279	0.0274	0.0263	0.0264	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000709 J	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000734 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000611 J	0.00262 U	0.000525 U	0.00262 U	0.000525 U	0.00113 J	0.00108 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000690 J	0.000433 J	0.000487 J	0.000435 J	0.000512 J	0.000731 J	0.000902 J	0.000554 J	NR	NR	NR	NR	NR
Fluoride	mg/L	1.86	1.08	1.77	1.36	1.81	1.34	0.480 U	1.69	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000758 U	0.000152 U	0.000758 U	0.000152 U	0.000157 J	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	--	0.194	0.181	0.255	0.176	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000720 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000255 U	0.00128 U	0.000255 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.0314	0.0356	0.0389	0.0368	0.0451	0.0495	0.0546	0.0342	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.00166 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	2.04 ± 0.439	1.14 ± 0.328	2.36 ± 0.522	1.81 ± 0.365	1.73 ± 0.428	1.55 ± 0.422	1.37 ± 0.394	2.23 ± 0.491	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.95 ± 1.16	3.52 ± 1.07	4.69 ± 1.33	3.24 ± 1.26	1.73 ± 0.902	4.11 ± 1.19	1.98 ± 1.01	2.99 ± 1.26	NR	NR	NR	NR	NR

NOTES:
 mg/L: Milligrams per Liter.
 SU: Standard Units.
 pCi/L: Picocuries per Liter.
 -- : Laboratory did not analyze sample for indicated constituent.
 D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
 F: Relative percent difference exceeded laboratory control limits.
 H: Bias in sample result likely to be high.
 J: Analyte detected above method (sample) detection limit but below method quantitation limit.
 K: Sample analyzed outside of recommended hold time.
 L: Bias in sample result likely to be low.
 NR: Analysis of this constituent not required for detection monitoring.
 U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
 X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
 Groundwater Analytical Results Summary
 CPS Energy - Calaveras Power Station
 Fly Ash Landfill

		JKS-46 Downgradient												
Sample Date	Task	12/6/16	2/22/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/10/19	10/23/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.902	0.837	0.645	0.799	0.920	0.801	0.788	1.01	0.828	0.702	0.997	1.01	0.864
Calcium	mg/L	120	132	145	115	126	117	137	145	140	126 D	212 D	172 D	143 J
Chloride	mg/L	11.6	11.8	12.2	10.5	12.6	11.8	327 JHD	11.7	11.6	11.6	13.2	13.0	17.9
Fluoride	mg/L	1.51	1.38	1.03	1.59	2.25	2.34	0.460 JH	1.83	2.16	1.68	2.52	2.22	1.61 J
Sulfate	mg/L	700 D	692 D	608 D	677	0.0460 U	780 D	288 JHD	800	864 D	855	1030	1020	1180
pH - Field Collected	SU	3.60	3.55	2.10	3.57	2.96	3.54	3.21	3.20	3.15	3.00	2.85	2.62	3.10
Total dissolved solids	mg/L	1160	1040	926	1030	1270	1180	1170 JH	1390	1300	1220	1550	1500	1970
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.000240 U	0.000240 U	0.000240 U	0.00120 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00190 J	0.00227	0.00144 J	0.00196 J	0.00277 J	0.00253	0.00295	0.00290	NR	NR	NR	NR	NR
Barium	mg/L	0.0429	0.0356	0.0308	0.0307	0.0364	0.0317	0.0323	0.0331	NR	NR	NR	NR	NR
Beryllium	mg/L	0.00381 J	0.00362	0.00340	0.00399 J	0.00459 J	0.00415	0.00462	0.00479	NR	NR	NR	NR	NR
Cadmium	mg/L	0.00110 J	0.000988 J	0.00121 J	0.00120 J	0.00101 J	0.00133 J	0.00141 J	0.00136 J	NR	NR	NR	NR	NR
Chromium	mg/L	0.000942 J	0.00140 J	0.00104 J	0.00262 U	0.00262 U	0.00156 J	0.00191 J	0.00202 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.0303	0.0324	0.0329	0.0367	0.0387	0.0383	0.0412	0.0414	NR	NR	NR	NR	NR
Fluoride	mg/L	1.51	1.38	1.03	1.59	2.25	2.34	0.460 JH	1.83	NR	NR	NR	NR	NR
Lead	mg/L	0.0162	0.0134	0.0109	0.0144	0.0192	0.0201	0.0236	0.0257	NR	NR	NR	NR	NR
Lithium	mg/L	0.0646	0.000476 U	0.00238 U	0.0673	0.0749	0.0799	0.107	0.0863	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.000255 U	0.000255 U	0.000255 U	0.00128 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.0255	0.0266	0.0205	0.0247	0.0296	0.0257	0.0298	0.0283	NR	NR	NR	NR	NR
Thallium	mg/L	0.00293	0.00292	0.00235	0.00263 J	0.00314 J	0.00300	0.00335	0.00345	NR	NR	NR	NR	NR
Radium-226	pCi/L	3.16 ± 0.701	1.69 ± 0.387	1.80 ± 0.448	1.2 0± 0.315	1.82 ± 0.420	1.40 ± 0.353	1.52 ± 0.375	1.99 ± 0.459	NR	NR	NR	NR	NR
Radium-228	pCi/L	4.98 ± 1.41	2.17 ± 1.48	2.96 ± 1.24	1.98 ± 0.957	4.39 ± 1.13	2.80 ± 1.05	2.28 ± 1.13	3.82 ± 1.15	NR	NR	NR	NR	NR

NOTES:
 mg/L: Milligrams per Liter.
 SU: Standard Units.
 pCi/L: Picocuries per Liter.
 -- : Laboratory did not analyze sample for indicated constituent.
 D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
 F: Relative percent difference exceeded laboratory control limits.
 H: Bias in sample result likely to be high.
 J: Analyte detected above method (sample) detection limit but below method quantitation limit.
 K: Sample analyzed outside of recommended hold time.
 L: Bias in sample result likely to be low.
 NR: Analysis of this constituent not required for detection monitoring.
 U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
 X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
Fly Ash Landfill

		JKS-60 Downgradient												
Sample Date	Task	12/7/16	2/22/17	3/28/17	5/2/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/10/19	10/23/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 Apr 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.655	0.504	0.449	0.456	0.442	0.394	0.436	0.479	0.399	0.334	0.405	0.377	0.325
Calcium	mg/L	433	375	290	--	379	336	350	383	363	382 D	501 D	524 D	530 J
Chloride	mg/L	411 D	311 D	311 D	285	300 D	319 D	287 JHD	352	366 D	202	149 X	183	168
Fluoride	mg/L	0.0360 U	0.319	0.324	0.421	0.306	0.338 JH	0.0960 U	0.284 JH	0.22 J	0.239 J	0.187 UJ	0.231 J	0.188
Sulfate	mg/L	1480 D	999 D	1010 D	976 X	1020 D	818 D	760 JHDX	759	801 D	906	968	1320	1280
pH - Field Collected	SU	5.82	5.38	4.21	5.75	6.07	6.44	5.93	5.97	6.09	6.42	5.93	6.23	6.61
Total dissolved solids	mg/L	2790	2340	2020	2110	2510	2120	1450 JH	2300	1860	1910	2010	2820	3180
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000861 J	0.000592 J	0.000366 J	0.00123 U	0.000367 J	0.000381 J	0.000266 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0702	0.0491	0.0465	0.0450	0.0469	0.0454	0.0490	0.0503	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000774 J	0.000778 J	0.000786 J	0.000695 J	0.000734 U	0.000359 J	0.000608 J	0.000699 J	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000743 J	0.000525 U	0.000525 U	0.00262 U	0.000690 J	0.00204 J	0.00100 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.115	0.0542	0.0423	0.0389	0.0210	0.00896	0.0166	0.0183	NR	NR	NR	NR	NR
Fluoride	mg/L	0.0360 U	0.319	0.324	0.421	0.306	0.338 JH	0.0960 U	0.284 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000216 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	--	0.0305	0.0179 J	0.0635	0.0314	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000370 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000726 J	0.000622 J	0.000715 J	0.00148 J	0.00162 J	0.00124 J	0.00103 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.00168 J	0.00132 J	0.00981	0.0390	0.0244	0.00761	0.00745	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000425 J	0.000412 J	0.000403 J	0.00166 U	0.000332 U	0.000372 J	0.000387 J	NR	NR	NR	NR	NR
Radium-226	pCi/L	3.01 ± 0.578	2.29 ± 0.421	2.74 ± 0.572	1.71 ± 0.378	0.914 ± 0.341	1.57 ± 0.381	1.34 ± 0.378	4.61 ± 0.650	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.57 ± 1.15	2.62 ± 1.04	0.838 ± 0.826	0.269 ± 0.713	2.24 ± 1.02	0.701 ± 0.850	1.72 ± 0.940	2.48 ± 1.60	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- F: Relative percent difference exceeded laboratory control limits.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- K: Sample analyzed outside of recommended hold time.
- L: Bias in sample result likely to be low.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
SRH Pond

		JKS-49 Upgradient												
Sample Date	Task	12/7/16	2/22/17	3/28/17	5/3/17	6/20/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 April 2020
Appendix III - Detection Monitoring														
Boron	mg/L	3.24	3.28	3.28	3.03 X	3.04 J	2.76	2.85	2.87	2.71	2.70	2.05	2.58	2.47
Calcium	mg/L	130	146	173	113	127	120	145	147	135	117 D	154 D	127 D	114 J
Chloride	mg/L	295 D	383 D	372 D	326	414 D	448 D	459 D	424	446 D	408	449	429	452
Fluoride	mg/L	0.715	0.643 JH	0.665 JH	0.809	0.627 JH	0.617 JH	0.525	0.712	0.697	0.719	0.749	0.793	0.894
Sulfate	mg/L	211 D	232 D	234 D	194	218 D	227	265 D	219 X	237	237	240	205	217
pH - Field Collected	SU	7.19	7.12	7.12	7.02	7.06	6.16	7.05	6.89	7.12	7.12	7.31	6.43	7.15
Total dissolved solids	mg/L	1250	1240	1190	1100	1450	1440	1490	1730	1310	1210	1290	1380	1240
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00173 J	0.00120 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000676 J	0.000729 J	0.00123 U	0.00123 U	0.000544 J	0.000538 J	0.000478 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0607	0.0575	0.0503	0.0554	0.0783	0.0721	0.0788	0.0735	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000654 U	0.000654 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000859 J	0.000572 J	0.00262 U	0.00262 U	0.000963 J	0.000997 J	0.00113 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00102 J	0.00109 J	0.00124 J	0.00155 J	0.00133 J	0.00153 J	0.00155 J	0.00146 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.715	0.643 JH	0.665 JH	0.809	0.627 JH	0.617 JH	0.525	0.712	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000758 U	0.000155 J	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	0.0137 J	0.0341	0.0295	0.0427	0.0252	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000690 J	0.0000263 U	0.0000490 J	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00779 J	0.00846	0.00875	0.0106	0.00908 J	0.00938	0.0107	0.0111	NR	NR	NR	NR	NR
Selenium	mg/L	0.00992 J	0.00597	0.00479	0.00521 J	0.00370 J	0.00235	0.00188 J	0.00141 J	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.198 ± 0.197	0.615 ± 0.272	0.747 ± 0.323	0.195 ± 0.167	0.294 ± 0.192	0.241 ± 0.193	0.159 ± 0.191	0.746 ± 0.274	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.1 ± 0.907	-1.37 ± 1.37	0.854 ± 0.724	1.08 ± 1.72	2.23 ± 0.949	0.658 ± 0.636	0.812 ± 0.604	1.43 ± 0.898	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
SRH Pond

		JKS-51 Upgradient												
Sample Date	Task	12/8/16	2/22/17	3/28/17	5/3/17	6/21/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 April 2020
Appendix III - Detection Monitoring														
Boron	mg/L	0.512	0.517	0.473	0.565	0.512	0.525	0.453	0.509	0.465	0.347	0.489	0.648	0.627
Calcium	mg/L	267	292	322	266	261 X	232	236	256	246	149 D	328	336 D	334 J
Chloride	mg/L	403 D	331 D	414 D	447	424 D	455 D	384 D	375	395 D	301	559	574 D	555
Fluoride	mg/L	0.247	0.341 JH	0.415 JH	0.534	0.354	0.391	0.0960 U	0.407 JH	0.305 J	0.291 J	0.329 J	0.405 J	0.470
Sulfate	mg/L	293 D	330 D	348 D	359	342 D	330 D	314 D	302	354 D	260	428	405 D	439
pH - Field Collected	SU	6.59	6.51	6.48	6.56	6.40	5.48	6.38	6.20	6.44	6.70	6.66	5.73	6.43
Total dissolved solids	mg/L	1650	1650	1490	1980	1530	1580	1390	1650	1320	916	1890	2150	2010
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.00120 U	0.000953 J	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000412 J	0.000390 J	0.00123 U	0.000392 J	0.000344 J	0.000395 J	0.000418 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0655	0.0563	0.0517	0.0512	0.0534	0.0520	0.0520	0.0564	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000654 U	0.000212 J	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000941 J	0.000525 U	0.00262 U	0.000657 J	0.000874 J	0.00113 J	0.00133 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000350 U	0.0000770 J	0.0000920 J	0.000350 U	0.000124 J	0.0000940 J	0.0000800 J	0.000108 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.247	0.341 JH	0.415 JH	0.534	0.354	0.391	0.0960 U	0.407 JH	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.000476 U	0.00238 U	0.0322	0.0874	0.0790	0.0958 JX	0.0718	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.000199 J	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000255 U	0.000255 U	0.00128 U	0.000255 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.09 ± 0.376	0.104 ± 0.122	0.618 ± 0.247	0.197 ± 0.145	0.328 ± 0.195	0.0847 ± 0.186	4.83 ± 0.763	0.682 ± 0.309	NR	NR	NR	NR	NR
Radium-228	pCi/L	0.312 ± 0.688	1.09 ± 1.37	2.32 ± 1.45	-1.26 ± 1.37	-0.799 ± 0.928	1.57 ± 0.786	0.762 ± 0.706	0.963 ± 0.954	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
SRH Pond

		JKS-52 Downgradient												
Sample Date	Task	12/7/16	2/21/17	3/28/17	5/2/17	6/21/17	7/25/17	8/29/17	10/10/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 April 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.66	2.11	1.63	1.51	1.33	1.43	1.46	1.71 X	1.95	1.54	1.46 X	1.65	2.05
Calcium	mg/L	169	181	189	--	145	140	162	168	175	153 D	195 DX	171 D	174 J
Chloride	mg/L	331 D	377 D	323 DX	320	326 D	343 D	417 D	355	360 D	326	336	320	433
Fluoride	mg/L	0.796	0.665	0.718 JH	0.915 JH	0.705	0.996 JH	0.0960 U	0.740	0.720	0.710	0.831	0.808	0.908
Sulfate	mg/L	277 D	318 D	299 DX	290	287 D	292 D	171 D	289	278 D	292	268	288 D	315
pH - Field Collected	SU	7.01	6.47	6.91	6.94	6.87	5.87	6.81	6.63	6.79	6.76	6.91	6.00	6.83
Total dissolved solids	mg/L	1290	1380	1100	1250	1280	1250	1250	1220	1240	1210	1170	1270	1470
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000565 J	0.000398 J	0.000425 J	0.000427 J	0.000392 J	0.000412 J	0.000448 J	NR	NR	NR	NR	NR
Barium	mg/L	0.0646	0.0583	0.0519	0.0483	0.0527	0.0558	0.0565	0.0616	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000153 J	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000525 U	0.000525 U	0.000525 U	0.000841 J	0.000860 J	0.00123 J	0.00108 J	NR	NR	NR	NR	NR
Cobalt	mg/L	0.00188 J	0.00233	0.00112 J	0.00119 J	0.00211	0.00183 J	0.00159 J	0.00189 J	NR	NR	NR	NR	NR
Fluoride	mg/L	0.796	0.665	0.718 JH	0.915 JH	0.705	0.996 JH	0.0960 U	0.740	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000292 J	0.000152 U	0.000152 U	0.000163 J	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.0471	0.000476 U	--	0.0616	0.0605	0.0827	0.0588	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.000234	0.0000263 U	0.0000263 U	0.0000263 U	0.0000810 J	0.0000263 U	0.0000263 UX	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.00128 J	0.00115 J	0.00102 J	0.000911 J	0.000865 J	0.000843 J	0.000914 J	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	1.71 ± 0.465	0.608 ± 0.289	0.296 ± 0.169	0 ± 0.150	0.435 ± 0.241	0.449 ± 0.196	0.194 ± 0.194	0.704 ± 0.319	NR	NR	NR	NR	NR
Radium-228	pCi/L	2.65 ± 1.12	0.744 ± 0.833	0.0645 ± 0.649	0.53 ± 1.10	0.928 ± 0.784	1.16 ± 0.867	0.716 ± 0.767	1.54 ± 1.22	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
SRH Pond

		JKS-53 Downgradient												
Sample Date	Task	12/8/16	2/23/17	3/29/17	5/2/17	6/21/17	7/26/17	8/30/17	10/11/17	4/4/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 April 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.50	1.38	1.55	1.54	1.47	1.45	1.36	1.45	1.60	1.61	1.42	1.36	1.43
Calcium	mg/L	134	105	156	NR	94.1	97.0	99.0	113	113	111 D	116	123 D	114 J
Chloride	mg/L	383 D	336 D	315 D	322	335 D	329 X	341	313	361	350	354	342	381
Fluoride	mg/L	0.230	0.377	0.408	0.547 JH	0.339	0.385 J	0.412	0.0360 U	0.392 J	0.265 J	0.270 J	0.352 J	0.428
Sulfate	mg/L	283 D	267 D	238 D	241	236 D	234 X	227	214	249	236	224	213	244
pH - Field Collected	SU	6.80	6.63	6.54	6.56	6.67	6.69	6.62	6.50	6.67	6.65	6.60	5.60	6.67
Total dissolved solids	mg/L	1390	1250	1160	1180	1150	1220	1150	1140	1160	1140	1150	1250	1160
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000284 J	0.000266 J	0.000274 J	0.000276 J	0.000246 U	0.000246 U	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0692	0.0633	0.0633	0.0623	0.0597	0.0638	0.0541	0.0617	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000701 J	0.000525 U	0.000525 U	0.000525 U	0.000557 J	0.000906 J	0.000525 U	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000356 J	0.000140 J	0.000135 J	0.000165 J	0.000137 J	0.000150 J	0.000163 J	0.0000699 U	NR	NR	NR	NR	NR
Fluoride	mg/L	0.230	0.377	0.408	0.547 JH	0.339	0.385 J	0.412	0.0360 U	NR	NR	NR	NR	NR
Lead	mg/L	0.000758 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.0279	0.0816	0.000476 U	NR	0.0931	0.104	0.125	0.109	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000780 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000470 JX	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000290 J	0.000255 U	0.000255 U	0.000255 U	0.000255 U	0.000255 U	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.306 ± 0.261	0.909 ± 0.363	0.117 ± 0.211 U	0.519 ± 0.221	0.558 ± 0.232	0.385 ± 0.244	2.76 ± 0.582	0.451 ± 0.270	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.09 ± 1.24	2.33 ± 1.13	1.81 ± 1.61	0.906 ± 1.02	-0.0622 ± 0.583	1.9 ± 1.24	1.44 ± 0.713	0.919 ± 0.853	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

TABLE 3
Groundwater Analytical Results Summary
CPS Energy - Calaveras Power Station
SRH Pond

		JKS-54 Downgradient												
Sample Date	Task	12/8/16	2/23/17	3/28/17	5/2/17	6/21/17	7/26/17	8/30/17	10/11/17	4/5/18	10/30/18	4/9/19	10/22/19	4/28/20
Constituents	Unit	Event 1 Dec 2016	Event 2 Feb 2017	Event 3 Mar 2017	Event 4 May 2017	Event 5 Jun 2017	Event 6 Jul 2017	Event 7 Aug 2017	Event 8 Oct 2017	Event 9 Apr 2018	Event 10 Oct 2018	Event 11 Apr 2019	Event 12 Oct 2019	Event 13 April 2020
Appendix III - Detection Monitoring														
Boron	mg/L	1.24	1.16	1.35	1.26	1.14	1.26	1.16	1.28	1.26	1.30	1.38	1.50	1.23
Calcium	mg/L	114	106	160	--	103	102	95.8	113	111	98.2 D	117	117 D	118 J
Chloride	mg/L	345 D	350 D	353 D	344	355 D	354 D	339 D	328	382	356	385	368	380
Fluoride	mg/L	0.718	0.731	0.655 JH	0.850 JH	0.623	0.728	0.0960 U	0.661	0.742	0.643	0.711	0.773	0.861
Sulfate	mg/L	308 D	312 D	315 D	312	304 D	305 D	298 D	287	309	283	309	341 D	443
pH - Field Collected	SU	6.98	6.78	6.92	6.89	6.88	6.91	6.79	6.69	6.86	6.85	6.75	5.60	6.76
Total dissolved solids	mg/L	1370	1430	1310	1310	1410	1320	1360	1500	1230	1240	1470	1470	1570
Appendix IV - Assessment Monitoring														
Antimony	mg/L	0.00120 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	0.000240 U	NR	NR	NR	NR	NR
Arsenic	mg/L	0.00123 U	0.000369 J	0.000898 J	0.000351 J	0.000354 J	0.000484 J	0.000324 J	0.000246 U	NR	NR	NR	NR	NR
Barium	mg/L	0.0631	0.0564	0.0611	0.0537	0.0543	0.0593	0.0471	0.0558	NR	NR	NR	NR	NR
Beryllium	mg/L	0.000654 U	0.000131 U	0.000131 U	0.000131 U	0.000162 J	0.000131 U	0.000131 U	0.000131 U	NR	NR	NR	NR	NR
Cadmium	mg/L	0.000734 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	0.000147 U	NR	NR	NR	NR	NR
Chromium	mg/L	0.00262 U	0.000657 J	0.00186 J	0.000525 U	0.000525 U	0.000693 J	0.000765 J	0.000525 U	NR	NR	NR	NR	NR
Cobalt	mg/L	0.000420 J	0.000212 J	0.00199 J	0.000253 J	0.000260 J	0.000532 J	0.000334 J	0.0000699 U	NR	NR	NR	NR	NR
Fluoride	mg/L	0.718	0.731	0.655 JH	0.850 JH	0.623	0.728	0.0960 U	0.661	0.742	0.643	0.711	0.773	0.861
Lead	mg/L	0.000758 U	0.000152 U	0.000862 J	0.000152 U	0.000152 U	0.000241 J	0.000152 U	0.000152 U	NR	NR	NR	NR	NR
Lithium	mg/L	0.000476 U	0.0452	0.00238 U	--	0.0595	0.0599	0.0712	0.0608	NR	NR	NR	NR	NR
Mercury	mg/L	0.0000263 U	0.0000620 J	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	0.0000263 U	NR	NR	NR	NR	NR
Molybdenum	mg/L	0.00128 U	0.000447 J	0.000367 J	0.000377 J	0.000342 J	0.000352 J	0.000260 J	0.000255 U	NR	NR	NR	NR	NR
Selenium	mg/L	0.00227 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	0.000454 U	NR	NR	NR	NR	NR
Thallium	mg/L	0.00166 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	0.000332 U	NR	NR	NR	NR	NR
Radium-226	pCi/L	0.88 ± 0.339	0.878 ± 0.358	0.546 ± 0.213	0.217 ± 0.217	0.433 ± 0.249	0.313 ± 0.254	0.926 ± 0.324	0.42 ± 0.205	NR	NR	NR	NR	NR
Radium-228	pCi/L	1.12 ± 1.11	1.94 ± 1.01	0.429 ± 0.781	0.574 ± 1.41	0.451 ± 0.660	0.766 ± 1.29	1.48 ± 0.968	1.17 ± 0.827	NR	NR	NR	NR	NR

NOTES:

- mg/L: Milligrams per Liter.
- SU: Standard Units.
- pCi/L: Picocuries per Liter.
- : Laboratory did not analyze sample for indicated constituent.
- D: Sample diluted due to targets detected over highest point of calibration curve or due to matrix interference.
- H: Bias in sample result likely to be high.
- J: Analyte detected above method (sample) detection limit but below method quantitation limit.
- NR: Analysis of this constituent not required for detection monitoring.
- U: Analyte not detected at laboratory reporting limit (Sample Detection Limit).
- X: Matrix Spike/Matrix Spike Duplicate recoveries were found to be outside of the laboratory control limits.

APPENDIX F SITE HYDROGEOLOGY AND CROSS-SECTIONS

EXCERPTS FROM LOCATION RESTRICTIONS DEMONSTRATION DATED OCTOBER 2018

2.1

SITE DESCRIPTION

CPS Energy owns and operates the Calaveras Power Station located southeast of San Antonio in Bexar County, Texas. Within this power station, there are two coal-fired plants (J.T. Deely Power Plant and J.K. Spruce Power Plant) that generate CCR that are subject to the CCR Rule. A General Site Location Map is provided as **Figure 1**.

CPS Energy has identified five onsite CCR Units:

1. Fly Ash Landfill (FAL);
2. Evaporation Pond (EP);
3. Sludge Recycle Holding (SRH) Pond;
4. North Bottom Ash Pond (BAP); and
5. South BAP.

For the purposes of this document, the FAL and EP are termed the Northern CCR Units and the SRH Pond and BAPs are termed the Southern CCR Units. The CCR Unit locations are shown in **Figure 2**.

2.2

SITE-WIDE GEOLOGY

According to the Bureau of Economic Geology (BEG) *Geologic Atlas of Texas San Antonio Sheet*, the geology in the area of Calaveras Power Station consists of the Carizzo Sand and the Wilcox Group. According to the United States Geological Survey (USGS), the Carizzo Sand consists of medium- to coarse-grained sandstone, with finer grained material towards the top of the formation and the Wilcox Group consists mostly of mudstone, with various amounts of sandstone, lignite, and ironstone concretions. Information presented in Section 2.2 and the following subsections was obtained from the *Groundwater Monitoring System* report (ERM, October 2017).

2.2.1

Northern CCR Units

The stratigraphic sequence is generally characterized by approximately 8 feet to 32 feet of unconsolidated material (sands, silts, and low to medium plasticity clays), underlain by a clayey/silty to well-sorted sand (groundwater-bearing unit) approximately 5 to over 25 feet thick, underlain by grey to brown, high plasticity clay (lower confining unit). The ground water bearing unit is at its greatest observed thickness near the southwest corner of the EP, and thins towards the northwest (northwest of the FAL). The lower confining unit, generally observed at a depth between approximately 471 feet to 478 feet above mean sea level (msl) was not observed at monitor wells JKS-47 and JKS-60 (drilled to depths of 462 feet and 466 feet above msl, respectively). This possibly suggests the presence of erosional channels or gradational changes in lithology between JKS-45 and JKS-47, and JKS-46 and JKS-60. Interbedded sands and clays were observed within both the unconsolidated material and ground water

bearing unit in monitor wells JKS-57, JKS-58, and JKS-61 through JKS-64. A high plasticity clay interval was observed above the groundwater-bearing unit at monitor well JKS-45, but appears to be discontinuous as it was not encountered during the installation of any other monitor wells in the vicinity of the Northern CCR Units. A CCR Well Network Location Map is provided as **Figure 3**.

Visual classifications of the geologic materials described above are consistent with results from the soil materials testing analysis conducted for samples collected at JKS-45, JKS-58, JKS-62, and JKS-64. The laboratory Unified Soil Classification System (USCS) results classify the high plasticity clay unit (above the groundwater-bearing unit) and the lower confining unit as fat clay (CH). Sandy lean clay (CL) and clayey sand (SC) USCS results from JKS-58 and JKS-62, respectively, suggest that the contact between the groundwater bearing unit and lower confining unit is gradational in some areas. The laboratory USCS results classify the groundwater-bearing unit from a silty sand (SM) at JKS-45 to a clayey sand (SC) at JKS-64. Hydraulic conductivities from cohesive samples collected from the lower confining unit were reported on the order of 10^{-7} to 10^{-8} centimeters per second (cm/sec), which is within the range of values for clay.

2.2.2 *Southern CCR Units*

The stratigraphic sequence is generally characterized by approximately 6 feet to 18 feet of unconsolidated material (sands, silts, and low to medium plasticity clays), underlain by clayey/silty sand to moderately-sorted sand (groundwater-bearing unit) approximately 9.5 to 21.5 feet thick, underlain by bedrock (sandstone). Discontinuous silts and interbedded clay material were observed within the groundwater-bearing unit in monitor wells JKS-48, JKS-49, and JKS-51 through JKS-55. A CCR Well Network Location Map is provided as **Figure 3**.

Visual classifications of the geologic materials described above are consistent with results from the soil materials testing analysis conducted for samples collected at JKS-48, JKS-53, and JKS-54. The laboratory USCS results classify the groundwater-bearing unit from a silty clayey sand (SC-SM) at JKS-54 to a clayey sand (SC) at JKS-48 and JKS-53. Hydraulic conductivities from cohesive samples collected from the lower confining unit were reported on the order of 10^{-6} to 10^{-8} (cm/sec).

2.3 **SITE-WIDE HYDROGEOLOGY**

Based on water level measurements and stratigraphic information collected during the advancement of the soil borings, ERM has provided an interpretation of the confining nature of the underlying stratigraphy. Information presented in the following subsections was obtained from the *Groundwater Monitoring System* report (ERM, October 2017).

2.3.1 *Northern CCR Units*

Groundwater in the vicinity of the Northern CCR Units appears to flow towards Lake Calaveras (southeast to east).

The groundwater-bearing unit in the vicinity of the Northern CCR Units appears to exhibit unconfined conditions based on the potentiometric surface of groundwater in relation to the first encountered water during drilling and the lack of continuous confining units (i.e., clay, sandy clay, or silty clay). The potentiometric surface is within approximately three feet of the first water encountered during drilling, and no continuous confining units are observed. The minimal change in elevation and the stratigraphic information indicates that a significant, laterally continuous confining layer is not present above the groundwater-bearing unit in the northern area. However, a laterally continuous lower confining unit was observed in multiple borings below the groundwater bearing unit.

2.3.2

Southern CCR Units

Groundwater in the vicinity of the Southern CCR Units appears to flow radially toward the lake and adjacent channel and away from a groundwater high represented by the water level elevation measured in JKS-49.

The groundwater-bearing unit in the vicinity of the Southern CCR Units appears to exhibit semi-confined conditions with confining units (i.e., clay, sandy clay, or silty clay) present in all the wells except JKS-49 and JKS-56. The potentiometric surface is within approximately 4 feet to 11 feet of where water was first encountered during drilling for all wells except JKS-56, indicative of groundwater under hydraulic head pressure with semi-confined conditions. JKS-56 appears to demonstrate unconfined conditions, due to the approximately 0.5 foot difference between the first encountered water during drilling and the potentiometric surface. There is a bedrock unit underlying the groundwater-bearing unit in the southern area.

3.1

PLACEMENT ABOVE THE UPPERMOST AQUIFER

The CCR Rule defines an aquifer as “a geologic formation, group of formations, or portion of a formation capable of yielding usable quantities of groundwater to wells or springs”. The CCR Rule also defines uppermost aquifer as “the geologic formation nearest the natural ground surface that is an aquifer, as well as lower aquifers that are hydraulically interconnected with this aquifer within the facility’s property boundary. Upper limit is measured at a point nearest to the natural ground surface to which the aquifer rises during the wet season”.

ERM obtained site-specific information from engineering assessments and site investigations to evaluate whether the bases of the CCR Units are located more than 1.52 meters (5 feet) above the upper limit of the uppermost aquifer.

Information reviewed included:

- *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report, Calaveras Power Station* (ERM, January 2018); and
- *Groundwater Monitoring System, CPS Energy Calaveras Power Station* (ERM, October 2017)

The results of this evaluation are presented below for the individual CCR Units at the Calaveras Power Station.

3.1.1

Fly Ash Landfill (FAL)

Based on the review of the *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report* and as-built drawings, the elevation of the base of the FAL ranges from 514 to 503 feet above msl. The first groundwater beneath the FAL was encountered during well drilling at approximately 483 feet above msl, and static water levels range from 478 to 489 feet above msl based on current and historical water level data. A stratigraphic cross section (Section A-A’) depicting the pertinent elevations is provided as **Figure 4**. Based on geotechnical analysis, the unit that overlies the first groundwater consists of fat clay, which typically has a hydraulic conductivity in the 10^{-8} cm/sec range signifying a very low permeability unit. Based on the above information, the base of the FAL is greater than 5 feet above the uppermost aquifer and unlikely to be in intermittent, recurring, or sustained hydraulic connection with the uppermost aquifer.

3.1.2 *Evaporation Pond (EP)*

Based on the review of the *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report* and as-built drawings, the elevation of the base of the EP ranges from 497 to 500 feet above msl. The first groundwater beneath the EP was encountered during well drilling at approximately 486 feet above msl, and static water levels range from 479 to 484 feet above msl based on current and historical water level data. A stratigraphic cross section (Section C-C') depicting the pertinent elevations is provided as **Figure 5**. Based on geotechnical analysis, the unit that overlies the first groundwater consists of interbedded sandy clay, which typically has a hydraulic conductivity in the 10^{-7} to 10^{-8} cm/sec range signifying a very low permeability unit. Based on the above information, the base of the EP is greater than 5 feet above the uppermost aquifer and unlikely to be in intermittent, recurring, or sustained hydraulic connection with the uppermost aquifer.

3.1.3 *Sludge Recycle Holding (SRH) Pond*

Based on the review of the *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report* and as-built drawings, the elevation of the base of the SRH Pond is 492 feet above msl. Although groundwater is under artesian conditions and rises to an elevation between 485 and 487 feet above msl based on available water level data, the first groundwater beneath the SRH Pond was encountered during well drilling at approximately 476 feet above msl. A stratigraphic cross section (Section D-D') depicting the pertinent elevations is provided as **Figure 6**. Based on geotechnical analysis, the unit that overlies the first groundwater consists of clayey sand, which typically has a hydraulic conductivity in the 10^{-6} to 10^{-8} cm/sec range signifying a low permeability unit. Based on the above information, the base of the SRH Pond is greater than 5 feet above the uppermost aquifer and unlikely to be in intermittent, recurring, or sustained hydraulic connection with the uppermost aquifer. Note that the first groundwater encountered in JKS-51 is perched water and not in hydraulic connection with the deeper, laterally continuous aquifer.

3.1.4 *North Bottom Ash Pond (BAP)*

Based on the review of the *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report* and as-built drawings, the elevation of the base of the BAPs ranges from 488 to 489 feet above msl. Although groundwater is under artesian conditions and rises to an elevation between 485 and 486 feet above msl based on available water level data, the first groundwater beneath the North BAP was encountered during well drilling ranging from 480 feet above msl in the south and 483.5 feet above msl in the north. A stratigraphic cross section (Section F-F') depicting the pertinent elevations is provided as **Figure 7**. Based on geotechnical analysis, the unit that overlies the first groundwater consists of clayey sand, which typically has a hydraulic conductivity in the 10^{-6} to 10^{-8} cm/sec range signifying a low permeability unit. Based on the above information, although portions of the North BAP are unlikely to be in intermittent, recurring, or sustained hydraulic connection with the uppermost aquifer, the base of the

northern portion of the North BAP is less than 5 feet above the uppermost aquifer.

3.1.5 *South Bottom Ash Pond (BAP)*

Based on the review of the *CCR Units – 2017 Annual Inspection and Fugitive Dust Control Report* and as-built drawings, the elevation of the base of the BAPs ranges from 488 to 489 feet above msl. Stratigraphic cross sections (Section D-D' and Section F-F') depicting the pertinent elevations are provided as **Figure 6** and **Figure 7**, respectively. Although groundwater is under artesian conditions and rises to an elevation between 485 and 486 feet above msl based on available water level data, the first groundwater beneath the South BAP was encountered during well drilling at approximately 476 feet above msl. Based on geotechnical analysis, the unit that overlies the first groundwater consists of clayey sand, which typically has a hydraulic conductivity in the 10^{-6} to 10^{-8} cm/sec range signifying a low permeability unit. Based on the above information, the base of the South BAP is greater than 5 feet above the uppermost aquifer and unlikely to be in intermittent, recurring, or sustained hydraulic connection with the uppermost aquifer.




Environmental Resources Management

DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	7/25/2016	SCALE:	AS SHOWN	REVISION:	1
W.O.NO.:	K:\GIS\CPS\Calaveras\MXD\0337367_CPSCalaveras_SiteLoc.mxd				

FIGURE 1
 GENERAL SITE LOCATION MAP
 CPS Energy - Calaveras Power Station
 San Antonio, Texas






QUADRANGLE COORDINATES

San Antonio East	Marathon	San Antonio West
Southwest	Wimberly	La Villa SW
Lampas	Burgess	Flower

ADJOINING 7.5 QUADRANGLES



Environmental Resources Management

FIGURE 2
CCR UNIT LOCATIONS





CPS Energy - Calaveras Power Station
San Antonio, Texas




ERM-Southwest, Inc. TX PE Firm No. 2393

DESIGN: CC	DRAWN: RLM	CHKD.: CC
DATE: 9/19/2018	SCALE: AS SHOWN	REV.:
W.O. NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_CCRUnitLocs_topo.dwg		

Legend

-  Background Monitor Well
-  Downgradient Monitor Well
-  Groundwater Elevation Observation Well
-  CCR Unit





Environmental Resources Management

FIGURE 3
CCR WELL NETWORK LOCATION MAP

CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN:	NH	DRAWN:	EFC	CHKD.:	WZ
DATE:	9/19/2018	SCALE:	AS SHOWN	REVISION:	0
W.O.NO.:	P:\Projects\0366643 CPS Energy Calaveras CCR Well Network\WZ\GIS\MXD\Hydro\Inl\0337367 CPSCalv WellsLocs2.mxd				





- LEGEND**
- SAND, SILTY SAND, AND/OR CLAYEY SAND
 - SILT, SANDY SILT, AND/OR CLAYEY SILT
 - LOW TO MEDIUM PLASTICITY CLAY, SANDY CLAY, AND/OR SILTY CLAY
 - HIGH PLASTICITY CLAY
 - INTERBEDDED SAND, AND CLAY

- LEGEND**
- POTENTIOMETRIC SURFACE (MEASURED DECEMBER 6, 2016)
 - INITIAL GROUNDWATER LEVEL ENCOUNTERED DURING WELL INSTALLATION
 - MONITOR WELL (SCREENED INTERVAL DASHED)
 - BACKGROUND MONITOR WELL

SOIL TEST DATA KEY

Sample ID
USCS Soil Classification



- Notes:**
1. Approximate ground surface elevation interpolated from surveyed elevations.
 2. Aerial Source: ESRI.


Environmental Resources Management

Figure 4
Stratigraphic Cross Section A-A'
Groundwater Monitoring System
CPS Energy - Calaveras Power Station
San Antonio, Texas

DESIGN: NH	DRAWN: RLM	CHKD.:
DATE: 9/17/2018	SCALE: AS SHOWN	REV.:
W.O.NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_xsecs.dwg, 9/17/2018 12:14:56 PM		





ERM



- LEGEND**
- SAND, SILTY SAND, AND/OR CLAYEY SAND
 - SILT, SANDY SILT, AND/OR CLAYEY SILT
 - LOW TO MEDIUM PLASTICITY CLAY, SANDY CLAY, AND/OR SILTY CLAY
 - HIGH PLASTICITY CLAY
 - INTERBEDDED SAND, AND CLAY

- POTENTIOMETRIC SURFACE (MEASURED DECEMBER 6, 2016)
- INITIAL GROUNDWATER LEVEL ENCOUNTERED DURING WELL INSTALLATION

- MONITOR WELL (SCREENED INTERVAL DASHED)
- DOWNGRADE MONITOR WELL
- BACKGROUND MONITOR WELL




- Notes:**
1. Approximate ground surface elevation interpolated from surveyed elevations.
 2. Aerial Source: ESRI.

Environmental Resources Management

Figure 5
Stratigraphic Cross Section C-C'
Groundwater Monitoring System
CPS Energy - Calaveras Power Station
San Antonio, Texas

DESIGN: NH	DRAWN: RLM	CHKD.:
DATE: 9/17/2018	SCALE: AS SHOWN	REV.:
W.O.NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_xsecs.dwg, 9/17/2018 12:14:57 PM		







- SAND, SILTY SAND, AND/OR CLAYEY SAND
- SILT, SILTY SILT, AND/OR CLAYEY SILT
- LOW TO MEDIUM PLASTICITY CLAY, SANDY CLAY, AND/OR SILTY CLAY
- INTERBEDDED SAND, SILT, AND CLAY
- BEDROCK (SANDSTONE)

- LEGEND**
- POTENTIOMETRIC SURFACE (MEASURED DECEMBER 6, 2016)
 - INITIAL GROUNDWATER LEVEL ENCOUNTERED DURING WELL INSTALLATION

SOIL TEST DATA KEY

Sample ID
USCS Soil Classification

- MONITOR WELL (SCREENED INTERVAL DASHED)
- DOWNGRADEMENT MONITOR WELL
- BACKGROUND MONITOR WELL





- Notes:**
1. Approximate ground surface elevation interpolated from surveyed elevations.
 2. Aerial Source: ESRI.

Environmental Resources Management

Figure 6
Stratigraphic Cross Section D-D'
Groundwater Monitoring System
CPS Energy - Calaveras Power Station
San Antonio, Texas



DESIGN: NH	DRAWN: RLM	CHKD.: WZ
DATE: 9/17/2018	SCALE: AS SHOWN	REV.: 1
W.O.NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_xsecs.dwg, 9/17/2018 12:14:58 PM		





- SAND, SILTY SAND, AND/OR CLAYEY SAND
- SILT, SANDY SILT, AND/OR CLAYEY SILT
- LOW TO MEDIUM PLASTICITY CLAY, SANDY CLAY, AND/OR SILTY CLAY
- INTERBEDDED SAND, AND CLAY
- BEDROCK (SANDSTONE)

- LEGEND**
- POTENTIOMETRIC SURFACE (MEASURED DECEMBER 6, 2016)
 - INITIAL GROUNDWATER LEVEL ENCOUNTERED DURING WELL INSTALLATION
 - MONITOR WELL (SCREENED INTERVAL DASHED)
 - DOWNGRADEMENT MONITOR WELL



- Notes:**
1. Approximate ground surface elevation interpolated from surveyed elevations.
 2. Aerial Source: ESRI.

Environmental Resources Management

Figure 7
Stratigraphic Cross Section F-F'
Groundwater Monitoring System
CPS Energy - Calaveras Power Station
San Antonio, Texas

DESIGN: NH	DRAWN: EFC	CHKD.: WZ
DATE: 9/17/2018	SCALE: AS SHOWN	REV.: 1

W.O.NO.: T:\DWG\AutoCAD\dwg\0337367\0337367_xsecs.dwg, 9/17/2018 12:15:01 PM

ERM-Southwest, Inc. TX PE Firm No. 2393

**APPENDIX G STRUCTURAL STABILITY AND SAFETY FACTOR
ASSESSMENTS**

October 17, 2016

Mr. Michael Malone
CPS Energy
145 Navarro, Mail Drop 100406
San Antonio, Texas 78296

Project No. 0352436

Subject: Structural Stability and Safety Factor Assessments
Calaveras Power Station
San Antonio, Texas

**Environmental
Resources
Management**

CityCentre Four
840 W. Sam Houston Pkwy N.
Suite 600
Houston, Texas 77024
(281) 600-1000
(281) 600-1001 (Fax)

Dear Mr. Malone:

Environmental Resources Management Southwest, Inc. (ERM) is pleased to provide this review of structural stability and safety factor assessments performed at the Calaveras Power Station, to assist CPS Energy in complying with Title 40, Code of Federal Regulations, Part 257 (40 CFR §257), Subpart D Coal Combustion Residual (CCR) Rules.



The Calaveras Power Station has five CCR surface impoundments: the North and South Sludge Recycle Holding (SRH) Ponds, the North and South Bottom Ash Ponds (BAPs), and the Evaporation Pond (EP). All ponds were constructed as diked impoundments. The SRH Ponds were constructed as a single impoundment with a divider wall that separates the impoundment into the North and South Ponds. A gate present in the divider wall is closed during normal operating procedures, but can be opened. The North and South BAPs share a common embankment that separates the ponds, and are immediately east of the SRH Pond. Only one BAP is typically in operation at one time. These four ponds are located east of the main Plant site. The EP is approximately a mile north of the main plant, and receives boiler chemical cleaning wastes. While this material is not considered CCR under the regulation, the EP was originally constructed as a fly ash landfill in 1990, and then converted to a fly ash impoundment in 1996. It currently contains solids that are six inches to two feet below the top of the impoundment.

40 CFR §257.73(d) requires that facilities conduct initial and periodic structural stability assessments for CCR surface impoundments to document whether the design, construction, operation, and maintenance of the CCR unit is consistent with recognized and generally accepted good engineering practices for the maximum volume of CCR and CCR wastewater which can be impounded therein. Table 1 provides a summary of the requirements within the regulation, and the relevant information for each surface impoundment.

Factors of safety were calculated by Raba Kistner Consultants, Inc. (RKCI) in May 2014. These assessments were provided in a report entitled "Geotechnical Engineering Study for Ash Pond Berms – Spruce/Deely Generation Units, San Antonio, Texas." ERM reviewed the information in these reports to evaluate whether factors of safety met the limits set forth in 40 CFR §257.73(e). All but one embankment evaluated by RKCI met the safety factor limits. The single non-complying safety factor was for the exterior slope of the northwestern berm on the North BAP, identified as cross-section or Embankment G. The steady-state safety factor for Embankment G was calculated at 1.2, and 1.4 on a reanalysis using a deeper failure surface. The minimum required safety factor for steady-state conditions is 1.5.

The RKCI report indicated that slopes used in the calculation for Embankment G were based on design drawings and field observations, not actual surveys. CPS Energy therefore engaged the services of a land surveyor (Pape-Dawson Engineers, Inc.) to collect measurements in two locations along Embankment G. The results of this survey, and the original RKCI soil data, were provided to HTS, Inc. Consultants (HTS), a geotechnical consulting firm in Houston, Texas. HTS recalculated the steady-state factor of safety utilizing the actual survey data. The calculated safety factors for both slopes were greater than 4. The letter report from HTS is included in Attachment 1.

Based on our evaluation of the available information for the impoundments, the structural stability and safety factor assessments meet the requirements of 40 CFR §257.73(d) and (e).

Sincerely,

Environmental Resources Management


Chris Cunningham, P.E.

Table 1
Attachment 1




TABLE 1
Summary of Impoundment Requirements

Regulatory Citation	Requirement	Sludge Recycle Holding Ponds	Bottom Ash Ponds	Evaporation Pond
(d)(1)(i)	Stable foundations and abutments	Based on calculated factors of safety, foundations and abutments are stable.	Based on calculated factors of safety, foundations and abutments are stable.	Based on calculated factors of safety, foundations and abutments are stable.
(d)(1)(ii)	Adequate slope protection to protect against surface erosion, wave action, and adverse effects of sudden drawdown	Slopes are vegetated with a continuous, maintained grass cover and inspected regularly for evidence of erosion.	Slopes are vegetated with a continuous, maintained grass cover and inspected regularly for evidence of erosion.	Slopes are vegetated with a continuous, maintained grass cover and inspected regularly for evidence of erosion.
(d)(1)(iii)	Dikes mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit	Based on geotechnical analysis and current slope conditions, it is likely that the dikes were mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit. Construction records documenting this are not available.	Based on geotechnical analysis and current slope conditions, it is likely that the dikes were mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit. Construction records documenting this are not available.	Based on geotechnical analysis and current slope conditions, it is likely that the dikes were mechanically compacted to a density sufficient to withstand the range of loading conditions in the CCR unit. Construction records documenting this are not available.
(d)(1)(iv)	Vegetated slopes of dikes and surrounding areas not to exceed a height of six inches above the slope of the dike	Grass on slopes is regularly mowed to maintain height below six inches.	Grass on slopes is regularly mowed to maintain height below six inches.	Grass on slopes is regularly mowed to maintain height below six inches.
(d)(1)(v)(A)	All spillways must be either: (1) Of non-erodible construction and designed to carry sustained flows; or (2) Earth- or grass-lined and designed to carry short-term, infrequent flows at nonerosive velocities where sustained flows are not expected.	Overflow spillways are concrete-lined. Regular discharge is via pumps through steel piping.	Ponds discharge via steel piping for regular and overflow discharges.	Not applicable. There are no outfalls for the pond.
(d)(1)(v)(B)	Spillways must adequately manage flow during and following the peak discharge from the required design storm flow.	Inflow during a storm is limited to direct precipitation. Sufficient headboard is maintained to capture design storm flow without requiring discharge.	Inflow during a storm is limited to direct precipitation. Sufficient headboard is maintained to capture design storm flow without requiring discharge.	Inflow during a storm is limited to direct precipitation. Sufficient headboard is maintained to capture design storm flow without requiring discharge.
(d)(1)(vi)	Hydraulic structures underlying the base of the CCR unit or passing through the dike of the CCR unit must maintain structural integrity	Not applicable. There are no hydraulic structures underlying the pond.	Steel pipes acting as outfalls are regularly inspected to verify no erosion or damage.	Not applicable. There are no hydraulic structures underlying the pond.
(d)(1)(vii)	Maintain structural stability during low pool of the adjacent water body or sudden drawdown of the adjacent water body.	Toe of embankments are at or above pool elevation of Calaveras Lake, which is maintained artificially. Therefore, no rapid drawdown or low pool conditions are likely.	Toe of embankments are at or above pool elevation of Calaveras Lake, which is maintained artificially. Therefore, no rapid drawdown or low pool conditions are likely.	Toe of embankments are at or above pool elevation of Calaveras Lake, which is maintained artificially. Therefore, no rapid drawdown or low pool conditions are likely.



Excellence in Engineering, Consulting, Testing and Inspection

July 20, 2016

**ERM, Inc.
840 W. Sam Houston Parkway N.
Suite 600
Houston, Texas 77024**

Attn: Mr. Chris Cunningham P.E.

**Re: Letter Report
Steady State Slope Stability Analysis
Ash Pond Berms - Spruce/Deely Generation Units
San Antonio, Texas**

HTS Project No.: 16-S-303

Dear Mr. Cunningham:

This letter provides results of the slope stability analyses performed on the 2 sections provided by ERM, Inc. The original geotechnical investigation (report dated May 7, 2014) was performed by Raba Kistner Consultants (RKC). HTS was requested to perform steady state slope stability analyses on 2 sections that were modified due to low factors of safety (below 1.5) against a slope stability failure.

Slope stability analyses were performed using the soil parameters provided on page 11 of RKC report and the subsoil profile defined by Geotechnical Boring No. 7 which is located near section G as presented in RKC report, Figures A-1 and C-1b. The 2 section configurations used in our slope stability analyses are presented in Appendix A.

Slope stability analyses were performed in order to determine the factors of safety of the side slopes of the section configurations against a slope stability failure. The long term (steady state) shear strengths of the cohesive soils are based on the shear strength parameters from consolidated undrained triaxial tests performed and presented on the table on page 11 of RKC report. The cohesion and angle of friction for sands were assumed to be zero and 28°, respectively, for a conservative approach. The water gradient was also considered to be close to the ground surface for a conservative analysis. The results of these analyses are shown below and in Appendix B.

SECTION	FACTOR OF SAFETY (LONG TERM CONDITION)
Section Along CSA	4.06
Section Along CSB	4.08


The results of the stability analyses using the shear strength parameters as discussed above suggest that the slopes of the section configurations provided by ERM will be stable in the long term condition.

Should you have any questions or require additional information pertaining to this letter, please do not hesitate to contact us at your convenience.

Sincerely,

HTS, Inc. Consultants


Bonifacio F. Musngi Jr., P.E.
Senior Engineer




HTS, Inc. Consultants
F-3478

Attachments: Appendix A – Slope Section Configurations
Appendix B – Slope Stability Analyses Results

BFM/ba/cg


h:word/2016/300-349/16-303



APPENDIX A



SECTION ALONG CSA




Note 1: The drawing is not to scale.
 Note 2: The coordinates are in feet.



Typical Section Configuration for Slope Stability Analyses - Section Along CSA		
Steady State Slope Stability Analysis Ash Pond Berms - Spruce/Deely Generation Units San Antonio, Texas		
Date: 7/18/16	HTS Proj No.: 16-S-303	Plate 1

SECTION ALONG CSB




Typical Section Configuration for Slope Stability Analyses - Section Along CSB		
Steady State Slope Stability Analysis Ash Pond Berms - Spruce/Deely Generation Units San Antonio, Texas		
Date: 7/18/16	HTS Proj No.: 16-S-303	Plate 2

APPENDIX B



Ash Pond Berms - Spruce/Deely, B-7 Long Term, CSA

h:\stedwinfiles\16-303- erm-san antonio\erm- section along csa- b-7- long term.pl2 Run By: Username 7/19/2016 3:19PM



#	FS	Soil Desc.	Soil Type	Total Unit Wt. (pcf)	Saturated Unit Wt. (pcf)	Cohesion Intercept (psf)	Friction Angle (deg)	Piez. Surface	Load L1	Value
a	4.06									
b	4.06									
c	4.07	CL	1	131.2	135.0	186.0	25.0	W1		
d	4.08	SC	2	125.0	128.0	0.0	28.0	W1		
e	4.08									
f	4.08									
g	4.08									
h	4.09									
i	4.10									
j	4.10									


STABL6H FSmin=4.06

Safety Factors Are Calculated By The Modified Bishop Method



Ash Pond Berms - Spruce/Deely, B-7 Long Term, CSB

h:\stedwinfiles\16-303- erm-san antonio\erm- section along csb- b-7- long term.pl2 Run By: Username 7/19/2016 3:19PM



STABL6H FSmin=4.08

Safety Factors Are Calculated By The Modified Bishop Method



ERM has over 160 offices across the following countries and territories worldwide

Argentina	The Netherlands
Australia	New Zealand
Belgium	Norway
Brazil	Panama
Canada	Peru
Chile	Poland
China	Portugal
Colombia	Puerto Rico
France	Romania
Germany	Russia
Ghana	Senegal
Guyana	Singapore
Hong Kong	South Africa
India	South Korea
Indonesia	Spain
Ireland	Sweden
Italy	Switzerland
Japan	Taiwan
Kazakhstan	Tanzania
Kenya	Thailand
Malaysia	UAE
Mexico	UK
Mozambique	US
Myanmar	Vietnam

ERM's Austin Office

Capitol Tower
206 East 9th Street, Suite 1700
Austin, Texas 78701

T: 512 459 4700

F: 512 597 8368

www.erm.com